

PP235 Ludowici Mission Tile (Brass) Specification Sheet Snow Guards

PART 1 – GENERAL

1.1 SUMMARY

A. WORK INCLUDES

1. PP235-MISSION snow guard that attaches directly to roof deck.
2. Coordinate with installation of roof to assure proper placement of snow guards.
3. Provide appropriate snow guard and fasteners for roof system

B. RELATED SECTIONS

1. Section 07600: Flashing and Sheet Metal. MasterFormat 2016 07 60 00
2. Section 07310: Shingles. MasterFormat 2016 07 31 00
3. Section 07320: Roofing Tiles. MasterFormat 2016 07 32 00
4. Section 07720: Snow Guards. MasterFormat 2016 07 72 00
5. Division 7: Thermal and Moisture Protection.

1.2 SYSTEM DESCRIPTION

A. COMPONENTS

1. PP235-MISSION Snow guard system consists of snow guard bracket assembly and base tile with snow guard base bracket welded to tile.
2. PP75, tubing
3. PP86, coupling
4. PP56, end caps
5. PP65, end collars
6. PP95, ice flags, optional
7. Fasteners
 - a. To be of metal compatible with snow guards.
 - b. Fasteners should be selected for compatibility with roof deck.
 - c. Fastener strength should exceed or be equal to that of snow guard system.

B. DESIGN REQUIREMENTS

1. Spacing to be recommended by manufacturer or building engineer.
2. Install a minimum of 2 fasteners per snow guard.
3. It is important to design new structures or assess existing structures to make sure they can withstand retained snow loads.

1.3 SUBMITTAL

- A. Submit manufacturer's specifications, standard detail drawings, installation instructions, and recommended layout.

1.4 QUALITY ASSURANCE

- A. Installer to be experienced in the installation of specified roofing material and snow guards for not less than 5 years in the area of the project.

1.5 DELIVERY / STORAGE / HANDLING

- A. Inspect material upon delivery and order replacements for any missing or defective items. Keep material dry, covered and off the ground until installed.



PP235 Ludowici Mission Tile (Brass) Specification Sheet Snow Guards

PART 2 – PRODUCTS

2.1 MANUFACTURER

A. Alpine SnowGuards®, a Division of Vermont Slate & Copper Services, Inc.
289 Harrel St., Morrisville, VT 05661 | 888-766-4273 | www.alpinesnowguards.com

2.2 MATERIALS

A. Snow Guard Bracket

1. 260 Brass
2. Connector Component, C87500 silicon bronze 3/8" thick

B. Base Tile

1. 260 Brass.

C. PP75, tubing

1. Brass – 272 alloy, 1" outside diameter and 1/8" wall thickness;
330 alloy upon request.

D. PP86, coupling

1. Brass – 300 Series, Internal and concealed coupling 3" long.

E. PP56, end caps

1. Brass Plated Stainless Steel.

F. PP65, end collars

1. 260 Brass

G. PP95, ice flags, optional

1. 260 Brass

H. Fasteners (can be purchased from others) to be compatible with chosen roof applications and meet specified pull-out values as shown in load test data.

2.3 FINISH

A. Mill Finish – standard

PART 3 – EXECUTION

3.1 EXAMINATION

A. Substrate

1. Inspect structure on which snow guard system is to be installed and verify it will withstand any additional loading that it may incur. Notify general contractor of any deficiencies before installing Alpine SnowGuards' products.
2. Verify that roofing material has been installed correctly prior to installing snow guards.

3.2 INSTALLATION

A. Comply with architectural drawings and snow guard manufacturer's recommendations for location of system. Comply with manufacturer's written installation instructions for installation and layout.

Document Version 12.19.2023
07 72 53 Snow Guards