
ARIZONA DEPARTMENT OF TRANSPORTATION
Contracts and Specifications Group
205 S. 17th Avenue, MD 121F,
Phoenix AZ 85007
Phone: 602.712.7221
KATIE HOBBS
GOVERNOR
JENNIFER TOTH
DIRECTOR



10/22/2026



ADDENDUM

No. 2

TO ALL CONTRACTORS AND OTHERS INTERESTED IN PROJECT

0000 MA BKY T063001C
BKY-0(216)T
CITY OF BUCKEYE
BUCKEYE FIBER OPTIC BACKBONE (MC 85/MILLER ROAD)

SCHEDULED FOR BID OPENING ON
FRIDAY, OCTOBER 23, 2026, AT 11:00 A.M. (M.S.T.)

REVISIONS TO THE PROJECT PLANS:

Attached are revised plan sheets 5, 21, and 38 of 48. Remove existing plan sheets 5, 21, and 38 of 48 and replace them with the attached revised plan sheets 5, 21, and 38 of 48, and be guided accordingly.

REVISIONS TO THE BID SCHEDULE:

Attached is the Revised Bid Schedule. Remove the existing Bid Schedule, insert the Revised Bid Schedule into the Proposal Pamphlet, and be guided accordingly.

REVISIONS TO THE SPECIAL PROVISIONS:

Page 61 of 116:

108.08 Determination and Extension of the Contract Time: the first paragraph is modified to read:

Construction Phasing: The contractor shall schedule and execute construction activities in accordance with the following phases:

Phase 1 (Administrative and Procurement Phase): Consists solely of administrative efforts, including but not limited to submittals, submittal reviews, project meetings, and the procurement/ delivery of long-lead project materials and equipment. No physical, on-site construction activities, site mobilization, or equipment deliveries to the active work zone shall occur during Phase 1. Phase 1 shall not exceed 365 calendar days.

Phase 2 (Physical Construction Phase): Consists of all physical on-site construction, mobilization, and field activities not explicitly permitted in Phase 1. Phase 2 shall not exceed 130 calendar days.

The contractor shall not commence any Phase 2 activities until Phase 1 is formally concluded. If Phase 2 activities are conducted during Phase 1, the time allowed for Phase 1 will be terminated, and the time allowed for Phase 2 will begin. Upon termination, all remaining unexpended calendar days allocated to Phase 1 shall be permanently forfeited, and the 130 calendar days for Phase 2 shall immediately commence.

No extensions of Contract Time will be considered or granted due to the contractor's failure to provide acceptable or timely equipment submittals, delays in the submittal review cycle resulting from non-compliant contractor submissions, or delays in fabricating, manufacturing, or procuring long-lead items.

The sum total of the actual time utilized for Phase 1 (not to exceed 365 days) and Phase 2 (not to exceed 130 days) will establish the total Contract Time.

Reza Jafari

for/ Brahama Singh, P.E.
Group Manager

Attachments:

- Revised Plan Sheets 5, 21, and 38 of 48,
- Revised bid Schedule.

ARIZONA DEPARTMENT OF TRANSPORTATION
PROJECT DELIVERY AND OPERATIONS DIVISION
CONTRACTS AND SPECIFICATIONS GROUP

BID SCHEDULE

CONTRACT # 2026015

TRACS No.	Project No.	Item	County	District	Gross Length	Net Length	Prepared By:
0000 MA BKY T063001C	BKY-0(216)T	104421	MARICOPA	CENTRAL	0		Noun Mohamed Ali

Highway Termini	Location	Work Description
• CITY OF BUCKEYE	• FIBER OPTIC (MC 85/MILLER RD)	• System Enhancement (Traffic Mgmt and Engineering)

BID SCHEDULE

0000 MA BKY T063001C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7010005	MAINTENANCE AND PROTECTION OF TRAFFIC	L.SUM	1		
7016050	TRUCK-MOUNTED ATTENUATOR	EACH-DAY	93		
7016067	CHANGEABLE MESSAGE BOARD (CONTRACTOR FURNISHED)	EACH-DAY	20		
7016082	FLAGGING SERVICES (LOCAL ENFORCEMENT OFFICER)(WITH AGENCY VEHICLE)	HOUR	192		
7320788	SINGLE MODE FIBER OPTIC CABLE (12 COUNT)	L.FT.	1,135		
9010001	MOBILIZATION	L.SUM	1		
9240011	FORCE ACCOUNT WORK (PULL BOX AND CONDUIT RECONDITIONING)	L.SUM	1	$20,000.00	$20,000.00
9240012	FORCE ACCOUNT WORK (RAILROAD FLAGGING SERVICES)	L.SUM	1	$15,000.00	$15,000.00
9240016	FORCE ACCOUNT WORK (QUALIFIED BIOLOGIST)	L.SUM	1	$10,000.00	$10,000.00
9240050	MISCELLANEOUS WORK (ITS RECORD DRAWINGS)	L.SUM	1		
9240144	MISCELLANEOUS WORK (2, 7-WAY MICRO-DUCT) (DTL I) (DIRECTIONAL DRILL)	L.FT.	11,135		
9240145	MISCELLANEOUS WORK (2, 7-WAY MICRO-DUCT) (DTL A) (TRENCHED)	L.FT.	7,890		
9240148	MISCELLANEOUS WORK (SINGLE MODE FIBER OPTIC CABLE) (LOOSE TUBE 288 FIBERS)	L.FT.	4,315		

BID SCHEDULE

0000 MA BKY T063001C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9240149	MISCELLANEOUS WORK (SINGLE MODE FIBER OPTIC CABLE) (MICRO CABLE 288 FIBERS)	L.FT.	23,910		
9240172	MISCELLANEOUS WORK (NO. 8 PULL BOX, STD DTL F)	EACH	7		
9240173	MISCELLANEOUS WORK (NO. 9 PULL BOX, STD DTL E)	EACH	4		
9240174	MISCELLANEOUS WORK (TERMINATION PANEL)	EACH	11		
9240175	MISCELLANEOUS WORK (FIBER OPTIC SPLICE CLOSURE)	EACH	12		
9240176	MISCELLANEOUS WORK (FIELD HARDENED ETHERNET SWITCH)	EACH	10		
9240181	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (MANUAL / MECHANICAL METHODS)	SQ.YD.	1,421		
9240182	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (HERBICIDE)	SQ.YD.	1,736		

BID SCHEDULE

0000 MA BKY T063001C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9250001	CONSTRUCTION SURVEYING AND LAYOUT	L.SUM	1		

BID TOTAL :