October 27, 2026



ADDENDUM

No. 2

TO ALL CONTRACTORS AND OTHERS INTERESTED IN PROJECT

017 YV 269 F0616 01C
017-B(239)T
CORDES JUNCTION – FLAGSTAFF HIGHWAY (I-17)
E DUGAS ROAD – MP 275

SCHEDULED FOR BID OPENING ON
FRIDAY, NOVEMBER 06, 2026, AT 11:00 A.M. (M.S.T.)

REVISIONS AND ADDITIONS TO THE SPECIAL PROVISIONS:

On Pages 216 and 217 of 275:

ITEM 9240129 MISCELLANEOUS WORK (ROCK SCALING OPERATIONS):

Construction Requirements: the sixth paragraph is revised to read:

The work shall avoid disturbing the stable underlying rock mass, which shall remain as intact as possible. Scaling operations shall not produce overhangs, cavities, or over-steepened slopes. If scaling operations result in an overly steep slope condition, the contractor shall re-slope the area to match adjacent slopes as directed by the Engineer. If instability of the slope results from improper scaling practices or operations as determined by the Engineer, the contractor shall stabilize the slope at no additional cost to the Department.

(B) Clean Up and Disposal of Materials: is revised to read:


All excavated material and debris (rock, soil, vegetation, etc.) within the work area of the scaling shall become property of the contractor and cleaned up and hauled to a disposal site. All existing roadway elements shall be maintained and protected during all cleaning

operations. Damage to roadway elements due to the scaling or clean-up operations shall be repaired or replaced at no additional cost to the Department.

On Page 218 of 275:

Basis of Payment: is modified to add:

No measurement or direct payment will be made for temporary movable rockfall containment system; the cost being considered as included in the cost of the contract item.



For Brahama Singh, PE,
Group Manager,
Contracts & Specifications

Attachment: None,