ARIZONA DEPARTMENT OF TRANSPORTATION
Contracts and Specifications Group
205 S. 17th Avenue, MD 121F,
Phoenix AZ 85007
Phone: 602.712.7221
KATIE HOBBS
GOVERNOR
JENNIFER TOTH
DIRECTOR

OCTOBER 23, 2026



ADDENDUM

No. 3

TO ALL CONTRACTORS AND OTHERS INTERESTED IN PROJECT

0000 CH BIS T062101C
BIS-0(207)T
BENSON-DOUGLAS HIGHWAY (SR 80)
SR80; QUEEN MINE TOUR – OLD BISBEE

SCHEDULED FOR BID OPENING ON
FRIDAY, NOVEMBER 13, 2026, AT 11:00 A.M. (M.S.T.)

REVISIONS AND ADDITIONS TO THE SPECIAL PROVISIONS:

Page 197 of 238: the first paragraph under (g) Timber Lagging is modified to add:

Timber Lagging in the retaining wall is considered temporary shoring and size and design shall be included in the retaining wall shop drawings. Size and thickness of lagging may vary along the height of the wall, however the size shall be no less than 3”x8”.

Page 206 of 238:

ITEM 9240119 MISCELLANEOUS WORK (WAYFINDING SIGNAGE): delete in its entirety and replace it with the following and be guided accordingly.

ITEM 9240010 FORCE ACCOUNT WORK (WAYFINDING SIGNAGE):

Description:

The work under this item shall consist of furnishing all materials, labor, equipment, and incidental items required to construct wayfinding signage in accordance with the requirements of these specifications. The work under this item includes coordinating with the City of Bisbee on determining the information that will be placed on the wayfinding signage.

Materials:

Materials shall be as indicated on the project plans.

Construction Requirements:

The construction of the wayfinding signage shall be coordinated with the City of Bisbee.

Method of Measurement and Basis of Payment:

Wayfinding Signage will be measured and paid for on a force account basis in accordance with the requirements of Subsection 109.04 of the specifications.

Page 207 of 238:

ITEM 9240120 MISCELLANEOUS WORK (BENCHES): delete in its entirety and replace it with the following and be guided accordingly.

ITEM 9240011 FORCE ACCOUNT WORK (BENCHES):

Description:

The work under this item shall consist of furnishing all materials, labor, equipment, and incidental items required to install benches in accordance with the requirements of these specifications. The work under this item includes coordinating with the City of Bisbee on determining the placement of future artwork on the benches.

Materials:

Materials shall be as indicated on the project plans.

Construction Requirements:

The installation of the benches shall be coordinated with the City of Bisbee. Benches shall be installed per manufacturer's specifications.

Method of Measurement and Basis of Payment:

Benches will be measured and paid for on a force account basis in accordance with the requirements of Subsection 109.04 of the specifications.

REVISIONS TO THE PROJECT PLANS:

Attached are revised plan sheets 32, 36 and 40 of 45 of the project plans. Remove sheets 32, 36 and 40 of 45 from the project plans, attach the revised plan sheets and be guided accordingly.

REVISIONS TO THE BID SCHEDULE:

Remove the existing Bid Schedule from your Proposal Pamphlet, replace it with the attached revised Bid Schedule and be guided accordingly.

For/ Brahama Singh, PE,
Group Manager,
Contracts & Specifications

Attachments:

- Revised Plan Sheets 32, 36, and 40 of 45.
- Revised Bid Schedule.

ARIZONA DEPARTMENT OF TRANSPORTATION
PROJECT DELIVERY AND OPERATIONS DIVISION
CONTRACTS AND SPECIFICATIONS GROUP

BID SCHEDULE

CONTRACT # 2025071

TRACS No.	Project No.	Item	County	District	Gross Length	Net Length	Prepared By:
0000 CH BIS T062101C	BIS-0-(207)T	104818	COCHISE	SOUTHEAST	0		Jalal Kamal

Highway Termini	Location	Work Description
• BENSON-DOUGLAS HIGHWAY (SR 80)	• SR 80 Queen Mine Tour To Old B	• System Enhancement (Safety Improvements)

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
2010020	REMOVAL OF TREES	EACH	8		
2020009	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	68		
2020020	REMOVAL OF CONCRETE CURB	L.FT.	77		
2020021	REMOVAL OF CONCRETE CURB AND GUTTER	L.FT.	989		
2020025	REMOVAL OF CONCRETE SIDEWALKS, DRIVEWAYS AND SLABS	SQ.FT.	3,135		
2020036	REMOVAL OF ASPHALTIC CONCRETE PAVEMENT	SQ.YD.	730		
2020045	REMOVAL OF RIPRAP	CU.YD.	88		
2020053	REMOVE (PULL BOX)	EACH	5		
2020366	REMOVE LEAD-BASED PAINT MATERIALS	L.SUM	1		
2020370	DISPOSE OF LEAD-BASED PAINT MATERIALS (FORCE ACCOUNT)	L.SUM	1	$10,000.00	$10,000.00
2020400	REMOVE AND RELOCATE (LIGHT POLES)	EACH	3		
3030022	AGGREGATE BASE, CLASS 2	CU.YD.	62		
4040125	FOG COAT	TON	1		
4040165	BLOTTER MATERIAL	SQ.YD.	370		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
4090006	ASPHALTIC CONCRETE (MISCELLANEOUS STRUCTURAL) (SPECIAL MIX)	TON	102		
6070048	FOUNDATION FOR SQUARE TUBE POST	EACH	10		
6070054	SIGN POST (PERFORATED) (2 S)	L.FT.	12		
6070055	SIGN POST (PERFORATED) (2 1/2 S)	L.FT.	33		
6070057	SIGN POST (PERFORATED) (2 1/2 T)	L.FT.	83		
6080005	REGULATORY, WARNING, OR MARKER SIGN PANEL	SQ.FT.	68		
6080110	REMOVE AND REINSTALL SIGN	EACH	8		
6080120	SIGN (REMOVE AND RELOCATE)	EACH	1		
7010025	TEMPORARY IMPACT ATTENUATION DEVICE (IN-LINE ENERGY ABSORBING TERM.)	EACH	1		
7010026	TEMPORARY IMPACT ATTENUTION DEVICE (IN-LINE ENERGY ABSORBING TERM.) (IN USE)	EACH-DAY	78		
7015010	TEMPORARY CONCRETE BARRIER (INSTALLATION AND REMOVAL)	L.FT.	750		
7015052	OBLITERATE PAVEMENT MARKING (STRIPE)	L.FT.	1,860		
7016020	TEMPORARY CONCRETE BARRIER (IN USE)	L.FT.-DAY	58,500		
7016030	BARRICADE (TYPE 1, TYPE 2, VERT.PANEL, TUBULAR MARKER)	EACH-DAY	3,900		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7016031	BARRICADE (TYPE 3, HIGH LEVEL FLAG TREE)	EACH-DAY	1,320		
7016033	PORTABLE SIGN STAND (SPRING TYPE)	EACH-DAY	6,210		
7016035	WARNING LIGHT (TYPE A)	EACH-DAY	7,530		
7016037	WARNING LIGHT (TYPE C)	EACH-DAY	3,900		
7016050	TRUCK-MOUNTED ATTENUATOR	EACH-DAY	5		
7016051	TEMPORARY SIGN (LESS THAN 10 S.F.)	EACH-DAY	2,200		
7016052	TEMPORARY SIGN (10 S.F. OR MORE)	EACH-DAY	5,330		
7016061	FLASHING ARROW PANEL	EACH-DAY	10		
7016067	CHANGEABLE MESSAGE BOARD (CONTRACTOR FURNISHED)	EACH-DAY	170		
7016075	FLAGGING SERVICES (CIVILIAN)	HOUR	200		
7016081	FLAGGING SERVICES (DPS)	HOUR	200		
7040005	PAVEMENT MARKING (WHITE EXTRUDED THERMOPLASTIC) (0.090")	L.FT.	2,180		
7040006	PAVEMENT MARKING (YELLOW EXTRUDED THERMOPLASTIC) (0.090")	L.FT.	2,450		
7040074	PAVEMENT SYMBOL (EXTRUDED THERMOPLASTIC) (ALKYD) (0.090")	EACH	8		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7042031	PRIMER-SEALER FOR PCCP THERMOPLASTIC STRIPING	L.FT.	2,630		
7042036	PRIMER-SEALER FOR PCCP THERMOPLASTIC SYMBOL/LEGEND	EACH	8		
7042051	REMOVAL OF CURING COMPOUND FOR STRIPING	L.FT.	2,630		
7042056	REMOVAL OF CURING COMPOUND FOR SYMBOL/LEGEND	EACH	8		
7050019	PAVEMENT MARKING, PREFORMED, LEGEND, TYPE I	EACH	2		
7050023	PAVEMENT MARKING, PREFORMED, SINGLE ARROW, TYPE I	EACH	4		
7050028	PAVEMENT MARKING, PREFORMED,SYMBOL, TYPE I	EACH	8		
7050071	PRIMER-SEALER FOR PCCP (SYMBOL/LEGEND)	EACH	14		
7050075	REMOVAL OF CURING COMPOUND (PCCP) (SYMBOL/LEGEND)	EACH	14		
7080201	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED) (WHITE)	L.FT.	1,700		
7080202	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED) (YELLOW)	L.FT.	1,720		
7080301	PAINT BULL NOSE	EACH	1		
7310197	BREAKAWAY BASE FOR LIGHTING POLE OR SIGNAL FLASHER	EACH	3		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7310202	POLE FOUNDATION FOR BREAKAWAY BASE (OVER 30')	EACH	3		
7320030	ELECTRICAL CONDUIT (1") (PVC)	L.FT.	30		
7320050	ELECTRICAL CONDUIT (2") (PVC)	L.FT.	40		
7320055	ELECTRICAL CONDUIT (2") (PVC) (DIRECTIONAL DRILL)	L.FT.	60		
7320110	ELECTRICAL CONDUIT (1") (RIGID METAL)	L.FT.	100		
7320456	PULL BOX (4B)	EACH	4		
7320459	PULL BOX (TRAFFIC RATED)	EACH	3		
7320500	CONDUCTOR (NO. 12)	L.FT.	790		
7320520	CONDUCTOR (NO. 8)	L.FT.	400		
7320585	CONDUCTOR (INSULATED BOND) (NO. 12)	L.FT.	395		
7320590	CONDUCTOR (INSULATED BOND) (NO. 8)	L.FT.	200		
7360113	LUMINAIRE (UNDERDECK)	EACH	1		
8030103	DECOMPOSED GRANITE	SQ.YD.	262		
8061005	TREE (15 GALLON)	EACH	3		
8061296	SHRUB (ONE GALLON)	EACH	7		
8061298	SHRUB (FIVE GALLON)	EACH	4		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
8070001	LANDSCAPING ESTABLISHMENT	L.SUM	1		
8080646	RESET FRAME AND COVER FOR VALVE BOX	EACH	2		
8101014	EROSION CONTROL (WATTLESS) (20")	L.FT.	846		
8101017	EROSION CONTROL (GRAVEL BAGS)	EACH	1		
8101030	EROSION CONTROL (CONSTRUCTION ENTRANCE)	SQ.YD.	196		
9010001	MOBILIZATION	L.SUM	1		
9080041	CONCRETE CURB (C-05.10) (TYPE A)	L.FT.	60		
9080042	CONCRETE CURB (DETAIL A)	L.FT.	231		
9080084	CONCRETE CURB AND GUTTER (C-05.10) (TYPE D)	L.FT.	208		
9080085	CONCRETE CURB AND GUTTER (C-05.10) (TYPE D-3)	L.FT.	436		
9080086	CONCRETE CURB AND GUTTER (C-05.10) (TYPE D-3) (H=8")	L.FT.	142		
9080242	CONCRETE SIDEWALK (SHARED USE BATH)	SQ.FT.	8,382		
9080295	CONCRETE SIDEWALK RAMP	SQ.FT.	173		
9080297	CONCRETE SIDEWALK RAMP (DETECTABLE WARNING STRIP)	SQ.FT.	10		
9080301	CONCRETE DRIVEWAY (C-05.20)	SQ.FT.	663		

BID SCHEDULE

0000 CH BIS T062101C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9130001	RIPRAP (DUMPED)	CU.YD.	1,900		
9140121	RETAINING WALL (REINFORCED CONCRETE)	SQ.FT.	257		
9140153	RETAINING WALL (SOLDIER PILE)	SQ.FT.	2,720		
9240010	FORCE ACCOUNT WORK (WAYFINDING SIGNAGE)	L.SUM	1	$10,000.00	$10,000.00
9240011	FORCE ACCOUNT WORK (BENCHES)	L.SUM	1	$15,000.00	$15,000.00
9240121	MISCELLANEOUS WORK (BIKE RACK)	EACH	1		
9240122	MISCELLANEOUS WORK (TREE STAKING)	EACH	3		
9240170	CONTRACTOR QUALITY CONTROL	L.SUM	1		
9240181	MISCELLANEOUS WORK (PORTLAND GREEN PREFORMED THERMOPLASTIC) (0.120")	SQ.YD.	40		
9250001	CONSTRUCTION SURVEYING AND LAYOUT	L.SUM	1		

BID TOTAL :