ARIZONA DEPARTMENT OF TRANSPORTATION

Contracts and Specifications Group
205 S. 17th Avenue, MD 121F,
Phoenix AZ 85007
Phone: 602.712.7221

KATIE HOBBS
GOVERNOR

JENNIFER TOTH
DIRECTOR





10/26/2026

ADDENDUM

(3)

TO ALL CONTRACTORS AND OTHERS INTERESTED IN PROJECT
0000 MA TOL T0619 01C
TOL-0(200)T
CITY OF TOLLESON
VAN BUREN AT 96TH AVE, TOLLESON

SCHEDULED FOR BID OPENING ON
FRIDAY, NOVEMBER 06, 2026, AT 11:00 A.M. (M.S.T.)

REVISIONS TO THE SPECIAL PROVISIONS:

Page 220 of 364

ITEM 9240050 – MISCELLANEOUS WORK (STEEL TRUSS BRIDGE):

Bridge Aesthetics: is modified to add:

Perforated steel panels shall have a painted steel finish. Contractor shall coordinate color with the Engineer and the City of Tolleson. Contractor shall provide sample of finished perforated steel panel upon request by the Engineer or the City of Tolleson.

Page 225 of 364:

Coordination of Embedded Systems and Attachments: is modified to add:

Bolting of attachments to the structure, limited to attachments of the steel perforated panels, aesthetic lettering, and DMS support beams, will not be permitted without approval of the Engineer. The Contractor shall submit sealed shop drawings and calculations for bolted connections to the Engineer for review and approval prior to construction.

REVSIONS TO THE PROJECT PLANS:

Attached are revised plans sheets 14, and 42 of 70; Remove the existing plan sheets 14, and 42 of 70; insert the revised plan 14, and 42 of 70 into the Proposal Pamphlet, and be guided accordingly.

Reza Jafari

for/ Brahama Singh, PE,
Group Manager,
Contracts & Specifications

Attachments:
Revised plan sheets 14, and 42 of 70.