October 21, 2026



ADDENDUM

No. 02

TO ALL CONTRACTORS AND OTHERS INTERESTED IN PROJECT

089A YV 362 F0624 01C
A89-B(225)T
PRESCOTT – FLAGSTAFF HIGHWAY (SR 89A)
SR 89A AT PAGE SPRINGS ROAD

SCHEDULED FOR BID OPENING ON
FRIDAY, OCTOBER 23, 2026, AT 11:00 A.M. (M.S.T.)

REVISIONS AND ADDITIONS TO THE SPECIAL PROVISIONS:

On Page 51 of 244:

104.17 Archaeological and Cultural Site Protection:

(A) General: revised to read:

The contractor shall avoid archeological or cultural sites within the project limits that have been pre-determined prior to the commencement of construction. The Department will demarcate these areas with plastic temporary orange snow fence or similar. Such pre-determined sites are referred to herein as “cultural avoidance areas”.

The term "Disturbance" shall refer to any act of physical disturbance by the operations of the contractor to the cultural avoidance areas as specified herein.

The site to the west of southbound SR 89A between MP 362.67 and 362.70, as shown in the project plans, will have two boundaries of avoidance fencing (plastic temporary orange snow fence or similar). The outer boundary serves as the primary perimeter, providing initial deterrence and control of access, while the inner boundary provides an additional layer of security for an archaeological or cultural site.

The contractor shall not enter or disturb the cultural avoidance areas with construction operations.

The contractor will not be held liable if the Engineer determines that the Disturbance to the cultural avoidance areas is not due to the actions of the contractor, subcontractor, or supplier

On Page 215 of 244:

ITEM 9240129 – MISCELLANEOUS WORK (ROADWAY OBLITERATION AND RESTORATION):

Basis of Payment: is modified to add:


Removal of asphaltic concrete pavement will be measured and paid for under respective bid items.

REVISIONS TO THE PROJECT PLANS:

Attached are revised plans sheets 2, 3, 4, 5, 28, 30 of 58. Remove the plan sheets 2, 3, 4, 5, 28, 30 of 58 from the project plans; insert the revised plan sheets and be guided accordingly.

REVISIONS AND ADDITIONS TO THE BID SCHEDULE:

Attached is the revised Bid Schedule. Remove the existing Bid Schedule from your proposal pamphlet, insert the revised Bid Schedule, and be guided accordingly.



For Brahama Singh, PE,
Group Manager,
Contracts & Specifications

Attachments:

Revised plans sheets 2, 3, 4, 5, 28, 30 of 58 of the Project Plans

Revised Bid Schedule.

ARIZONA DEPARTMENT OF TRANSPORTATION
PROJECT DELIVERY AND OPERATIONS DIVISION
CONTRACTS AND SPECIFICATIONS GROUP

BID SCHEDULE

CONTRACT # 2025126

TRACS No.	Project No.	Item	County	District	Gross Length	Net Length	Prepared By:
089A YV 362 F062401C	A89-B-(225)T	103629	YAVAPAI	NORTHCENT	0.7		Farhana Jesmin

Highway Termini	Location	Work Description
• PRESCOTT – FLAGSTAFF HIGHWAY (SR 89A)	• SR 89A AT PAGE SPRINGS ROAD	• RECONSTRUCT PAGE SPRINGS ROAD INTERSECTION

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
2010011	CLEARING AND GRUBBING	ACRE	4		
2020029	REMOVAL OF ASPHALTIC CONCRETE PAVEMENT	SQ.YD.	5,634		
2020041	REMOVAL OF PIPE	L.FT.	2		
2020045	REMOVAL OF RIPRAP	CU.YD.	347		
2020053	REMOVE (FLARED END SECTION)	EACH	1		
2020054	REMOVE (SIGN ASSEMBLY)	EACH	29		
2020075	REMOVE BITUMINOUS PAVEMENT (MICRO-MILLING)	SQ.YD.	26,012		
2020115	REMOVE (SIGN PANEL)	EACH	1		
2020157	REMOVE (EXISTING LIGHT POLE)	EACH	2		
2020158	REMOVE (LIGHTING PULL BOX)	EACH	4		
2020159	REMOVE (LED LUMINAIRE)	EACH	3		
2030301	ROADWAY EXCAVATION	CU.YD.	2,229		
2030302	ROADWAY EXCAVATION (OVEREXCAVATION)	CU.YD.	5,730		
2030401	DRAINAGE EXCAVATION	CU.YD.	699		
2030904	BORROW (IN PLACE)	CU.YD.	2,251		
3030021	AGGREGATE BASE, CLASS 1	CU.YD.	1,514		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
4040076	EMULSIFIED ASPHALT (MICRO-SURFACING)	TON	98		
4040171	DRY MINERAL AGGREGATE (MICRO-SURFACING) (TYPE III)	TON	752		
4090006	ASPHALTIC CONCRETE (MISCELLANEOUS STRUCTURAL) (SPECIAL MIX)	TON	1,294		
5010011	PIPE, CORRUGATED METAL, 24"	L.FT.	125		
5010025	PIPE, CORRUGATED METAL, 36"	L.FT.	10		
5014024	FLARED END SECTION, 24" (C-13.25)	EACH	2		
5014636	METAL SAFETY END SECTION (36")	EACH	1		
6070002	BREAKAWAY SIGN POST S4X7.7	L.FT.	46		
6070004	BREAKAWAY SIGN POST W6X12	L.FT.	57		
6070022	FOUNDATION FOR BREAKAWAY SIGN POST S4X7.7	EACH	4		
6070024	FOUNDATION FOR BREAKAWAY SIGN POST W6X12	EACH	4		
6070038	SLIP BASE	EACH	37		
6070055	SIGN POST (PERFORATED) (2 1/2 S)	L.FT.	184		
6070057	SIGN POST (PERFORATED) (2 1/2 T)	L.FT.	462		
6070060	FOUNDATION FOR SIGN POST (CONCRETE)	EACH	61		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
6080005	REGULATORY, WARNING, OR MARKER SIGN PANEL	SQ.FT.	325		
6080018	EXTRUDED ALUMINUM SIGN PANEL	SQ.FT.	228		
6080025	FLAT SHEET ALUMINUM SIGN PANEL	SQ.FT.	136		
6080110	REMOVE AND REINSTALL SIGN	EACH	1		
7015010	TEMPORARY CONCRETE BARRIER (INSTALLATION AND REMOVAL)	L.FT.	4,360		
7015020	TEMPORARY IMPACT ATTENUATORS (INSTALLATION AND REMOVAL)	EACH	8		
7016020	TEMPORARY CONCRETE BARRIER (IN USE)	L.FT.-DAY	151,460		
7016021	TEMPORARY IMPACT ATTENUATORS (IN USE)	EACH-DAY	303		
7016030	BARRICADE (TYPE 1, TYPE 2, VERT.PANEL, TUBULAR MARKER)	EACH-DAY	14,292		
7016033	PORTABLE SIGN STAND (SPRING TYPE)	EACH-DAY	2,163		
7016035	WARNING LIGHT (TYPE A)	EACH-DAY	2,339		
7016037	WARNING LIGHT (TYPE C)	EACH-DAY	14,292		
7016039	EMBEDDED SIGN POST	EACH-DAY	2,280		
7016050	TRUCK-MOUNTED ATTENUATOR	EACH-DAY	225		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7016051	TEMPORARY SIGN (LESS THAN 10 S.F.)	EACH-DAY	396		
7016052	TEMPORARY SIGN (10 S.F. OR MORE)	EACH-DAY	4,087		
7016061	FLASHING ARROW PANEL	EACH-DAY	201		
7016067	CHANGEABLE MESSAGE BOARD (CONTRACTOR FURNISHED)	EACH-DAY	332		
7016082	FLAGGING SERVICES (LOCAL ENFORCEMENT OFFICER)(WITH AGENCY VEHICLE)	HOUR	104		
7080201	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED) (WHITE)	L.FT.	11,711		
7080202	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED) (YELLOW)	L.FT.	6,817		
7080206	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED SYMBOL) (ARROW)	EACH	12		
7080207	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED LEGEND) (STOP/AHEAD)	EACH	2		
7080208	WATERBORNE-TYPE I PAVEMENT MARKING (PAINTED LEGEND) (ONLY)	EACH	4		
7090001	DUAL COMPONENT PAVEMENT MARKING (WHITE EPOXY)	L.FT.	19,246		
7090002	DUAL COMPONENT PAVEMENT MARKING (YELLOW EPOXY)	L.FT.	10,424		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7090005	DUAL COMPONENT PAVEMENT MARKING (TRANSVERSE)	L.FT.	113		
7090010	DUAL COMPONENT PAVEMENT LEGEND	EACH	6		
7090012	DUAL COMPONENT PAVEMENT SYMBOL	EACH	12		
7310070	POLE (TYPE G) (STANDARD BASE)	EACH	17		
7310197	BREAKAWAY BASE FOR LIGHTING POLE OR SIGNAL FLASHER	EACH	17		
7310260	POLE FOUNDATION (TYPE G) (STANDARD BASE)	EACH	17		
7310652	MAST ARM (10 FT) (ALUMINUM)	EACH	17		
7320050	ELECTRICAL CONDUIT (2") (PVC)	L.FT.	2,900		
7320291	ELECTRICAL CONDUIT (2") (HDPE) (DIRECTIONAL DRILL)	L.FT.	90		
7320460	PULL BOX (NO. 4B)	EACH	17		
7320500	CONDUCTOR (NO. 12)	L.FT.	1,400		
7320520	CONDUCTOR (NO. 8)	L.FT.	12,230		
7320585	CONDUCTOR (INSULATED BOND) (N0. 8) (GREEN)	L.FT.	4,125		
7360104	LUMINAIRE (HORIZONTAL MOUNT) (15L) (LED)	EACH	20		
7360236	LOAD CENTER CABINET (LIGHTING) (MODIFY)	EACH	1		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
8050003	SEEDING (CLASS II)	ACRE	4		
8101021	EROSION CONTROL (WATTLES) (9")	L.FT.	1,457		
8101029	EROSION CONTROL (ROCK MULCH) (DETAIL ES2)	CU.YD.	12		
8101035	EROSION CONTROL (SEDIMENT LOGS) (20")	L.FT.	310		
9010001	MOBILIZATION	L.SUM	1		
9130001	RIPRAP (DUMPED)	CU.YD.	289		
9240050	MISCELLANEOUS WORK (ELECTRICAL RECORD DRAWINGS)	L.SUM	1		
9240129	MISCELLANEOUS WORK (ROADWAY OBLITERATION AND RESTORATION)	SQ.YD.	2,154		
9240170	CONTRACTOR QUALITY CONTROL	L.SUM	1		
9240181	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (MANUAL / MECHANICAL METHODS)	SQ.YD.	9,000		
9240182	MISCELLANEOUS WORK (CONTROL OF NOXIOUS PLANTS) (HERBICIDE)	SQ.YD.	11,000		
9240900	AVOIDANCE AREA PROTECTION PLAN AND MONITORING	L.SUM	1		
9250001	CONSTRUCTION SURVEYING AND LAYOUT	L.SUM	1		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9280037	GROUND-IN RUMBLE STRIP (12 INCH)	L.FT.	5,964		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
RCB CULVERT, NORTH U-TURN STA 51+41					
2030501 A	STRUCTURAL EXCAVATION	CU.YD.	92		
2030506 A	STRUCTURE BACKFILL	CU.YD.	124		
6010002 A	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	124		
6050002 A	REINFORCING STEEL	LB.	15,350		

BID SCHEDULE

089A YV 362 F062401C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
RCB CULVERT EXTENSION, NB SR 89A STA 527+08					
2020009 B	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	12		
2030501 B	STRUCTURAL EXCAVATION	CU.YD.	48		
2030506 B	STRUCTURE BACKFILL	CU.YD.	69		
6010002 B	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	61		
6050002 B	REINFORCING STEEL	LB.	7,850		
6050101 B	PLACE DOWELS	EACH	8		

BID TOTAL :