

08 October 2024

Tony can Eekelen Asset Builders 2000 Ltd By Email:

Dear Tony

## **RE: FINAL APPROVAL FOR LOT 1038 PRESTONS PARK**

Thank you for providing us with the requirements for final approval, for the proposed new residence in our Prestons Park development. In accordance with clause 3(h) of the Land Covenants registered on the title under easement instrument 12600266.5, all plans pertaining Lot 1038 have been approved.

Requirements for Final Approval	Approved
Home Plans	<b>✓</b>
External Cladding and Roofing Details	<b>✓</b>
Colour Pallets for the external elements of the home	<b>✓</b>
Landscape Plan	<b>✓</b>
Fencing Plan	<b>/</b>

All building activity associated with the construction and landscaping of the new house shall be confined to Lot 1038. No material is to be stored on any adjoining property without first obtaining written approval from the owners.

Fencing approval has been granted in accordance with the Land Covenant requirements only. To avoid potential non-compliance with the Christchurch City Council District Plan Fencing Provisions, we encourage you to refer your fencing plan to the Christchurch City Council Duty Planner, to ensure it meets the requirements of the District Plan.

As it is a civil offence to remove a survey peg, please ensure that all survey pegs identifying your property are left undisturbed.


We will keep the plans on our file for future reference.

Yours faithfully

COL Land New Zealand Limited

Y > KCMI.

Simone Cromhout




Plans Approved
CDL LAND NEW ZEALAND LIMITED

Simone Cromhout.....

# Asset Builders Residence

31 Tamara Crescent Prestons Park



Joh

## **Proposed Dwelling**

For

## **Asset Builders**

Δŧ

### 31 Tamara Crescent Prestons Park

LOT 1038 DP 577687


© The copyright of frees documents remain the property of Extens Architecture List urises otherwise agreed in wifting - All contraders swifting on this graced shall be Usensed Building Practitioners with current Pland PL insurance in place. - Contractions are responsible to ensure all sorts complies with the NZBC and relevant standards. If contractor finds any decrepancy, all

Date			03/03/2024
Revision			RFI-
Stage	CP 🗌	PP	WD
Drawn			DJ
Job Number			24218

#### Cover Sheet

Drawing Number	Scale
01	1:200
ALL DIMENSIONS TO	D BE VERIFIED ON SITE

Site Areas	
	Area (m²)
Site Coverage	172.88
	172.88 m²



## SITE SEDIMENT CONTROL

ENTRY/ EXIT POINT TO SITE Ensure that a rumble pad is constructed of 40mm Crushed Rock to a depth of 150mm-200mm. This plud should be 2m wide and 10m in length and shall from the kerb to the building site.

SITE ACCESS MUST BE RESTRICTED TO THIS PAD d should be 2m wide and 10m in length and shall extend

BARRIERS AND FENCES Install pediment fence from a specially manufactured geolexities sediment fencing meterial which must be buried to a depth of 200mm. Note that no fence can be constructed on council

Where practicable divert up-slope water around disturbed areas

STOCKPILE Ensure that all stockpiled material is within the Sediment

MAINTENANCE Have extra fence fabric on site to make repairs Reapply Rock to Rumble Pad as required

## CONSTRUCTION SITE MANAGEMENT

ENTRY/ EXIT POINT TO SITE Site must be fenced with 2.0m min. high temporary fencing where it may be accessible to the public and must have the provision to be locked while building site is not occupied

SIGNAGE All Appropriate hazard signs must erected before any work commences on site

SAFTEY FROM FALLING

GENERAL HEALTH AND SAFETY This Interior is a smokefree workplace Temporary toilet and handwashing facilities must be provided

### PIPE SIZES & FALLS

- 1. Shall comply with G13 as follows
- Ø50mm - 1:40 min fall Ø180mm - 1:60 min fal

Ø100mm main & branch drain - 1:100 min fall (main & branch drain only

- 2. All waste pipes in slab Ø40mm unless noted otherwise except L'dry tub, sink & dishwasher waste Ø50mm
- 3. WC wastes Ø100mm, 6m max to main drain. 1:60 fall
- 4. TV shall be 80mmØ unless noted on plan
- Drainlayer and builder to ensure that drains are dear of the foundation loading as per NZBC E1 3.9.7 & fig 14, extend footing if necessary.
- Inspection points to all pipes junctions and comers over 45° except where under 2m in length and servicing only a single GT or DP
- 7. All pipes through slab shall be sleeved or lag to NZBC
- 8. HWC over flow drains shall be copper, ensure that pipe size is 1 size bigger that relief valve outlet (20mm min)
- 9. Final layout for drains to be dertermined by drain layer
- 10. Farthworks undertaken within 5m of the base of the street tree shall be supervised by a works arborist employed or contracted by the Council or a network utility operator

### FLOOR LEVEL NOTES:

House FFL shall have clearance above finished ground level (FGL) as follows:
All other claddings = 225mm to natural FGL & 150mm to paved FGL

## **Proposed Dwelling**

## **Asset Builders**

At

Simone Cromhout.....

### 31 Tamara Crescent **Prestons Park**

LOT 1038 DP 577687

© The copyright of these documents remain the property of Evince Auchthorizer Ltd unless otherwise agreed in writing

- All contractors working on this project shall be Uconsed Building Practitiones with current Pl and P. Insurance in place.

- Contractors are responsible to ensure all work complies with the NZBC and relevant standards. If contractor finds any discrepancy, all work shall stop, contact the designer for further instructions.

Date			03/03/2024
Revision			RFI-
Stage	СР 🗌	PP 🗌	WD
Drawn			Ŋ
Job Number		4.5	24218
D TH.			

## Site Plan


Drawing Number	Scale
02	1:150

File: 242 18 Asset Bulklers pin Pfinted: Sunday, 5 May 2024, 10:19 PM

Floor Areas Area (m²) 172.88 OVER FRAME

## Plans Approved CDL LAND NEW ZEALAND LIMITED

Simone Cromhout.....



#### Floor Coverings

All floor coverings shall comply with requirements of NZBC E3/AS1 & D1/AS1

Tile cover to: Ensuite

Carpet cover to: Halls, Living rooms, Bedrooms

Concrete cover to: Garage

#### Truss & Frame Note

Truss manufacturer respo

- Lintels and beams
   Truss hold down

- Truss bottom chord restria
   Roof bracing
   Top plate and lintel fixing
- Stud sizing and spacing
   Stab thickening

Painting
Wet Areas (e.g. bathroom, ensuite) - Two coats of gloss or semi gloss paint over a undercoat - walks and cellings

### **Utility Key**

Gully Trap



## **Proposed Dwelling**

## **Asset Builders**

At

## 31 Tamara Crescent **Prestons Park**

LOT 1038 DP 577687

The copyright of hese documents remain the property of Extrace Arabbachers List uriess otherable agreed in writing a Lill contractive subject of the United States of Lill contractive subject on the Type Practitioners with current Pland Pt. Instanton inplace. Contractions are reported to cream of such contractive with the NASI and relevent standards. It contractor that any discrepancy, all work shall show counter the design for their instantations.

		RFI-
CP 🗌	PP	WD 🗌
		DJ
		24218
	ωЦ	<u> </u>


## **Ground Floor Plan**

Drawing Number	Scale
03	1:100

ALL DIMENSIONS TO BE VERIFIED ON SITE

## COLOURS:

ROOF 9 FASICA: EBONY WINDOW & DOORS: EBONY OBILOUE WEATERBOARD: EBONY PASTEN CLADDING: WHITE




West Elevation


Plans Approved CDL LAND NEW ZEALAND LIMITED

Risk Factor Wind zone (per NZS 36

Eaves width



South Elevation Scale 1:100 North Elevation



East Elevation

## **Proposed Dwelling**

CONSTRUCTION NOTES

2. Flexible sill tape to all window and door openings 3. H3.2 framing to all chimneys and other framing above roof

4. Linkels not specified by truss manufacturer shall be SG8 grade strength & comply with NZS 3604 as below up to 0.9m = 90x80 1,0m to 1.5m = 140x80 1,6m to 0.20m = 190x80 2,1m to 2.5m = 240x80 2,6m to 3.1m = 290x80 2,6m to 3.1m = 290x80

BUILDING ENVELOPE RISK MATRIX Highest Risk Elevation

> Low risk High risk

Maritum risk Low risk

## **Asset Builders**

### 31 Tamara Crescent **Prestons Park**

LOT 1038 DP 577687

© The copyright of these documents remain the property of Evince Auchitecture Ltd urless otherwise agreed in writing


- All contractors working on this project shall be Lice
Practitioners with current Pl and PL insurance in place. Contractors are responsible to ensure all work complies with the NZBC and relevant standards. If contractor finds any discrepancy, all work shall stop, contact the designer for further instruction

Date		,	03/03/2024
Revision			RFI-
Stage	СР 🗌	PP	WD 🗌
Drawn			DJ
Job Number			24218
Day Jan Tille			


#### Elevations


Drawing Number	Scale
04	1:100
04	1

ALL DIMENSIONS TO BE VERIFIED ON SITE



Section 1-1





Job **Proposed Dwelling** 

## **Asset Builders**

## 31 Tamara Crescent **Prestons Park**

LOT 1038 DP 577687

The copyright of hees documents remain the property of Evince Architecture Ltd unless of horsels agreed in widing — All contractors working on the project shall be Lloansed Building Presidences with current IT and PL Insurance in place. — Contractors are responsible to ensure all work complies with the NZBC and relevant standards. If contractor firsts any discrepancy, all whether the Contractor first any discrepancy, all contracts from the contractor first any discrepancy, all work shall ston contact the designer for Eigher instructions


Date		C	3/03/2024
Revision			RFI-
Stage	CP 🗌	PP	WD 🔲
Drawn			ฌ
Job Number		23.	24218
Danies Tits			

#### Sections

Drawing Number	Scale
10	1:50

ALL DIMENSIONS TO BE VERIFIED ON SITE





## SITE SEDIMENT CONTROL

ENTRY/ EXIT POINT TO SITE Ensure that a rumble pad is constructed of 40mm Crushed Ensure that a number pad is constructed of 40mm Crusted Rock to a depth of 150mm-200mm. This plut should be 2m wide and 10m in length and shall extend from tile kerb to the building site. SITE ACCESS MUST BE RESTRICTED TO THIS PAD

BARRIERS AND FENCES Install pediment fence from a specially manufactured geotexial sediment fencing material which must be buried to a depth of 200mm. Note that no fence can be constructed on council

## **UP SLOPE WATER**

Where practicable divertup-slope water around disturbed areas by diversion banks and geotextile lined trenches.

## STOCKPILE

Ensure that all stockpiled material is within the Sediment Fencing.

#### MAINTENANCE

Have extra fence fabric on site to make repairs Reapply Rock to Rumble Pad as required Renair all Trenches as needed

### CONSTRUCTION SITE MANAGEMENT


#### ENTRY/ EXIT POINT TO SITE

Site must be fenced with 2.0m min. high temporary fencing where it may be accessible to the public and must have the provision to be locked while building site is not occupied

All Appropriate hazard signs must erected before any work commences on site

#### SAFTEY FROM FALLING Safety barriers must be erected where there is danger of falling

GENERAL HEALTH AND SAFETY This Interior is a smokefree workplace Temporary toilet and handwashing facilities must be provided



#### PIPE SIZES & FALLS

1. Shall comply with G13 as follows - 1:40 min fall

Ø50mm - 1:40 min fall - 1:40 min fall - 1:60 min fall

- 1:60 min fall (soil fixtures connecting to main & branch drain - 1:100 min fall (main & branch drain only

2. All waste pipes in slab Ø40mm unless noted otherwise except L'dry tub, sink & dishwasher waste Ø50mm

3. WC wastes Ø100mm, 6m max to main drain. 1:60 fall

4. TV shall be 80mm@ unless noted on plan

- Draintayer and builder to ensure that drains are clear of the foundation loading as per NZBC E1 3.9.7 & fig 14, extend footing if necessary.
- Inspection points to all pipes junctions and comers over 45° except where under 2m in length and servicing only a single GT or DP
- 7. All pipes through slab shall be sleeved or lag to NZBC
- 8. HWC over flow drains shall be copper, ensure that pipe size is 1 size bigger that relief valve outlet (20mm min)
- 9. Final layout for drains to be dertermined by drain layer
- 10. Earthworks undertaken within 5m of the base of the street tree shall be supervised by a works arborist employed or contracted by the Council or a network utility operator.

### FLOOR LEVEL NOTES:

House FFL shall have clearance above finished ground level (FGL) as follows:
All other claddings = 225mm to natural FGL & 150mm to paved FGL

## **Proposed Dwelling**

## **Asset Builders**

## 31 Tamara Crescent **Prestons Park**

LOT 1038 DP 577687

© The copyright of these documents remain the property of Evince Architecture Ltd unless of herwise agreed in writing
- All contractors working on this project shall be Licensed Building Practitioners with current P and PL insurance in place. - Contractors are responsible to ensure all work complies with the NZBC and relevant standards. If contractor finds any discrepancy, all work shall stop, contact the designer for further instructions

Date			03/03/2024
Revision		200-0	RFI-
Stage	СР 🗌	PP 🗌	WD 🔲
Drawn			Ŋ
Job Number			24218
Drawing Title			

#### Site Plan

1:150

ALL DIMENSIONS TO BE VERIFIED ON SITE

File: 242 18 Asset Builders pin Printed: Sunday, 5 New 2024, 10:19 PM