



DRYFLEX P.U.M.P. ATLAS TILE ADHESIVES

SOLUTIONS FOR INDUSTRY



Characteristics:

- Dryflex P.U.M.P. is a blue, water based polyurethane modified, flexible waterproofing membrane.
- Dryflex P.U.M.P. is fast drying and UV stable
- Dryflex P.U.M.P. can be recoated after 4-6 hours @20°C depending on amount of coats applied.
- Dryflex P.U.M.P. doesn't require the use of any reinforcement.
- Dryflex P.U.M.P. is ideal for waterproofing of Shower Recesses, bathrooms and Laundries and light foot trafficable roofs.
- Dryflex P.U.M.P. can be used for internal or external waterproofing applications.
- Dryflex P.U.M.P. can be used over concrete, render, rendered brickwork, block work, Fibre-cement, Gyprock, and particle board surfaces.
- Dryflex P.U.M.P. is easy to clean in water.
- RLA/Atlas cement based Tile Adhesives can be applied over Dryflex P.U.M.P.

Preparation:

- All new concrete surfaces must be allowed to cure for at least 6 weeks and have a wood float finish. Steel trowelled finished slabs must be chemically or mechanically abraded prior to commencing waterproofing.
- All rendered surfaces must be allowed to cure for at least 7 days prior to commencing waterproofing. Ensure all rendered surfaces have a wood float finish.
- The maximum variation in the plane must not exceed 5mm in 3 meters for floors and 4mm in 2 meters for walls.
- Fibre Cement sheet when used as an underlay or wall / floor material must be a minimum of 6mm in thickness. All FC Sheets should be fixed in accordance with the manufacturer's instructions and the relevant standards.
- Compressed Fibre-Cement sheets when used as a floor substrate must be 15mm thick, and when used a wall substrate must 9mm thick and must be installed in accordance with the manufacturer's instructions and the relevant standards.
- Gypsum -plasterboard sheets when used as a wall substrate must be a minimum of 10mm thick, and installed in accordance with the manufacturer's instructions and the relevant standards.
- All screw / nail heads must be sealed with epoxy, and all sheet joints must be covered with a 50mm wide polyethylene / polypropylene tape.
- Ensure all metal surfaces are rust free.
- Small hairline cracks may be filled with the first application of Dryflex P.U.M.P. Cracks larger than 2mm or structural shrinkage cracks must be firstly filled with a flexible silicone / PU type sealant, and then a 50mm wide polypropylene / polyethylene tape placed over the crack prior to the application of Dryflex P.U.M.P.
- Ensure all surfaces are sound, dry and free from excessive movement, oil, dust, grease, wax, curing compounds, release agents, paint and any other loose contaminating materials. Also remove any protrusions from the surface that may pierce the membrane.
- All surfaces must be primed with Uniprime prior to the application of Dryflex P.U.M.P. to the substrate. Except for metal surfaces which should be primed with a Zinc Chromate / etching primer.
- When applying the Uniprime it is recommended to firstly pour some primer in a section then spread the primer using a broom, brush or roller. Then continue this method of application until the entire area is primed. **Note:** This method of application ensures a thorough coat of the primer on the surface.
- Allow the primer to dry for approximately 5-10 minutes at 20°C prior to commencing waterproofing.

Mixing:

- Dryflex P.U.M.P. is a one part premixed product that does not require mixing.

Application:

- Ensure the surface has been appropriately prepared in accordance with RLA/Atlas instructions
- Apply silicone sealer to joints
- Apply the first coat of Dryflex P.U.M.P. to the primed surface using a thick brush or a roller.
- Re-apply a second coat of Dryflex P.U.M.P. at 90° to the first coat to ensuring complete coverage is achieved and no air bubbles exist.
- A third coat may be required if imperfections are present in the membrane.
- Conduct a final inspection on the surface of the membrane prior to commencing tiling to ensure no pinholes exist.
- Once the waterproofing is completed do not disturb the area for at least 24 hours at 20°C.
- Dryflex P.U.M.P. requires to be applied at a minimum thickness of 0.75mm of dry film

Don't just buy another product buy a SOLUTION

Clean Up:

- Excess Dryflex P.U.M.P. tools and other equipment can be cleaned up using water while the membrane is still wet.

Coverage:

- The coverage of Dryflex P.U.M.P. will vary depending upon the substrate, size and type of application and site conditions. As a guide it will cover approximately 1.5L/m² for 2 coats at approx. 1 mm thick dry film.

Packaging / Shelf Life:

- Dryflex P.U.M.P. is available in 15lt pails.
- A pail of Dryflex P.U.M.P. when stored in a cool, dry environment, and is stored above ground level, will have a shelf life of approximately 12 months.


Handy Tips:

- Do not apply Dryflex P.U.M.P. in temperatures above 40°C and below 5°C.
- Dryflex P.U.M.P. cannot be used in areas where negative hydrostatic pressure is evident.
- Dryflex P.U.M.P. cannot be used in areas of permanent water immersion like swimming pools / spas etc.
- Ensure that Dryflex P.U.M.P. is totally dry and the surface is without pinholes before applying any top coat over it.
- For applications / situations not mentioned in these instructions please contact your nearest RLA/Atlas office.
- Dryflex P.U.M.P. is classified as a non-hazardous product.
- For a full MSDS on this product please contact your nearest RLA/Atlas office.

Technical Data:

Properties	Results
Appearance	Blue Paste
Density	1.25 +/- 0.05
Re-coat Time	4 - 6 Hours @ 20°C
Drying Time @ 20°C	Approx 12 Hours
Full cure @ 20°C	3 days
Dry film thickness	0.75 - 1 mm

The information supplied is to the best of our knowledge true and accurate. The actual application of the product is beyond the manufacturer's control. Any failure or damage caused by the incorrect usage of the product is not the responsibility of the manufacturer. The manufacturer insists that all workmanship must be carried out in accordance with AS 3958.1-1991. It is also the responsibility of the end user to ensure that the literature in their possession is the latest issue.



www.rlapolymers.com.au
TECHNICAL ENQUIRIES TOLL FREE No.1800 752 679

Victoria

215 Colchester Road
Kilsyth VIC 3137
Ph: 613 9728 1644
Fax: 613 9728 6009

New South Wales

363 Wentworth Ave
Penrith Hill NSW 2145
Ph: (02) 9636 7444
Fax: (02) 9636 7688

Queensland

25 Computer Road
Yatala QLD 4207
Ph: 617 3807 4022
Fax: 617 3807 4755

New Zealand

67 Dalgety Dr
MANUKAU CITY Auckland
Ph: 649 267 2772
Fax: 649 268 0305

Malaysia

No.5 Lebuhraya Petai
Pandamaran PORT KLANG 42000
Ph: 603 3166 1039
Fax: 603 3166 1037

Russell Brook

From: Support@dvcs.co.nz
Sent: Tuesday, 12 April 2011 12:44 p.m.
To: Russell Brook
Subject: 125 Nikau Palm Road BC090214

Hi Russell

Sorry for the delay busy working out of town.

I would like to apply for an extension to the building consent till the end of the year the reason is that I am undertaking most of the work myself and this extends the time needed to complete.

I have a new address it is all correspondence to be sent there

18 Stellin Street
Avalon
Lower Hutt

Same contact number 0212441643

Consent number BC090214
125 Nikau Palm road

Any queries call

Regards Tom Roulston

OK to extend
CCC 8 months

R Brook 12/4/11

Done! Angie 12/4/11
Letter sent to owner &
agent.

02 March 2016

Tom Roulston
125 Nikau Palm Road,
Paraparaumu

Building Consent: 090214

Dear Sir/Madam

**Building Consent granted subject to a waiver or modification of the
building code**


Description: Excavation of site & construction of New Dwelling
Location: 125 Nikau Palm Road, Paraparaumu
Legal Description: LOT 4 DP 82049

We recently issued you with an amendment to building consent relating to the above building project. The consent was granted subject to a modification of the building code.

The modification granted was with respect to the external cladding complying with clause B2.3.1 from 01/06/2010 instead of from the time of issue of the code of compliance certificate. This modification applies only to building work carried out under the above building consent.

Please keep this letter with your building consent documentation.

Yours sincerely



Russell Brook
Team Leader – Site Inspections

02 March 2016

Tom Roulston
125 Nikau Palm Road,
Paraparaumu

Building Consent: 090214

Dear Sir/Madam

**Building Consent granted subject to a waiver or modification of the
building code**

Description: Excavation of site & construction of New Dwelling
Location: 125 Nikau Palm Road, Paraparaumu
Legal Description: LOT 4 DP 82049


We recently issued you with an amendment to building consent relating to the above building project. The consent was granted subject to a modification of the building code.

The modification granted was with respect to the external cladding complying with clause B2.3.1 from 01/06/2010 instead of from the time of issue of the code of compliance certificate.

This modification applies only to building work carried out under the above building consent.

Please keep this letter with your building consent documentation.

Yours sincerely



Russell Brook
Team Leader – Site Inspections



Statement of Compliance with the NZ Building Code

Consent No: 090214

ISSUED BY: **Kapiti Coast District Council**

PROJECT

Site Address: 125 Nikau Palm Road, Paraparaumu
Legal Description: LOT 4 DP 82049
Work Description: Excavation of site & construction of New Dwelling
Building Category: R3

OWNER

Name(s): Tom Roulston
Address: 28 Stellan Street, Avalon, LOWER HUTT

- [P] Application for CCC received and accepted
- [P] Confirm all required inspections completed and documented in GoGet
- [NA] If inspection(s) have been missed, have they been compensated for?
- [NA] If supervision was required for any inspection - did it occur?
- [P] Work in accordance with approved consent and approved amendments
- [NA] Have any notices to fix been uplifted?
- [P] Supporting documentation required in building consent addenda received
- [P] Quality assurance documentation
- [NA] Restricted building work
- [NA] Additional information required and received
- [NA] Compliance schedule issued
- [NA] Earthquake prone building
- [NA] Swimming Pool details updated
- [P] Approve to issue Code Compliance Certificate if all fees paid
- [NA] Approve to issue Certificate for Public Use if all fees paid
- [NA] Approve to issue Certificate of Acceptance if all fees paid
- [NA] Supervision review

NOTES:

Inspections Prepaid:
Inspections Done:

On review of the documentation and inspection notes it can be considered on reasonable grounds that all work has been completed in compliance with the building consent.

Signed: 
Name: Russell Brook
Position: Building Officer

Date: 2 March 2016

GoGet Inspection Audit Report

Consent No: **090214**
 Applicant: **Architecture DM**
 Site Address: **125 Nikau Palm Road, Paraparaumu**
 Work Type: **Excavation of site & construction of New Dwelling**

Inspection Type: **Final Inspection**
 Inspection Outcome: **Pass**
 Inspected By: **Craig Watson**
 Inspection Date: **26 February 2016 2:58 p.m.**
 Duration: **30 minutes**

Inspection Element	Status
Exterior	Pass
Inspection notes	Pass
Drawings	Pass
Additional information/plan	N/A
Sub-floor ventilation	N/A
Roof fixings	Pass
Spouting and down-pipes to 2 x 22,000litre tanks	Pass
Deck structure	Pass
Flashings - roof	Pass
Penetrations - flashings	Pass
Barriers Glass balustrade	Pass
Gully dishes	Pass
Stormwater and site drainage To tanks	Pass
Handrails	Pass
Wastes to gully	Pass
Fixings - durability	Pass
Steps/stairs	Pass
Terminal vents/AAVs	Pass
Cladding painted/sealed	Pass
Flashings - windows/doors	Pass
Cladding ground clearance	Pass
Road crossing complete	N/A
Final check complete	Pass
Interior	Pass
Inspection notes	Pass
Drawings	Pass
Additional information/plan	N/A
Service areas-floors/walls All sealed.	Pass
Stair design	Pass
Handrails	Pass
Balustrades	Pass
Lightings	Pass
Laundering	Pass


Cooking facilities	Pass
Smoke detectors	Pass
Hardwired.	
Food storage/preparation	Pass
Ventilation	Pass
Insulation and clearance	Pass
HWC flues	Pass
HWC restraint	Pass
Tempering valve	Pass
Glazing - human impact	Pass
Hot water temp	Pass
42 degree	
Solid fuel heater	Pass
Water supply tank	Pass
Trap seals and AAVS	Pass
Cistern flushing	Pass
WC pan connection	Pass
Septic tank	Pass
Window labels	Pass
Road crossing complete	N/A
Final check complete	Pass
Intertenancy/commercial	N/A



Taken at 2:21 PM on Friday 26/02/2016



Taken at 2:21 PM on Friday 26/02/2016



Taken at 2:23 PM on Friday 26/02/2016



Taken at 2:24 PM on Friday 26/02/2016



Taken at 2:28 PM on Friday 26/02/2016



Taken at 2:29 PM on Friday 26/02/2016



Taken at 2:30 PM on Friday 26/02/2016



INSTALLERS CHECKSHEET

NOTE: Please have this form completed by the installer and ready for our Building Inspector to collect when doing the final inspection

INSTALLERS NAME: (Please Print)

BC Number 090214

Tom Roulston

Address: 125 Nikau Palm Road

Ph: 04 2970066

FREESTANDING FIRE OR INBUILT FIRE INSTALLED AT:

Address: 125 Nikau Palm Road

For: Tom Roulston

The following requirements under NZS 7421:1990 or AS/NZ 2918:2001 have been met and the solid fuel burning domestic appliance type and model SCANDIA CUISINE

Has been installed in accordance with the manufacturer's installation instructions.

Please TICK (Where applicable) the following:

- ☐ The Chimney has been Cleaned
- ☐ The Chimney is in a sound condition
- ☐ The Chimney is of pumice and correct dimensions to comply with BRANZ zero clearance certificates
- ☐ The Chimney is ventilated to manufacturer's requirements
- ☐ The appliance is restrained against seismic activity (freestanding & fireplace heaters)
- ☐ The Inbuilt heating appliance has been approved by BRANZ as complying with their zero clearance certificate
- ☐ The hearth is an approved type according to the manufacturer's requirements
- ☐ The hearth is restrained against seismic activity
- ☐ The fire-surround at its connection to the fire place is fully insulated with approved material [see BRANZ Building Information Bulletin 248 (1986)]
- ☐ The ash hearth is of correct dimensions according to the installation instructions

Signed:

Date: / /



Prepared for

SCANDIA STOVES AND STOVES PTY LTD

**THERMAL CLEARANCE TESTING OF THE
CUISINE TOP FIRED BAKERS OVEN MKII SOLID
FUEL COOKING
APPLIANCE TESTED WITH A HAWKWIND
TRIPLE SKIN FLUE KIT**

Test Report No: HCMG/05/008

July 2005

CONFIDENTIAL - CLIENT USE ONLY

by
S Marland

© Copyright - (2003) HRL Limited

No part of this report may be reproduced by any process, stored in a retrieval system, transmitted nor disclosed to others without prior written permission of HRL Limited, except that the client may reproduce the report for its own internal use. The report is issued free of alterations and subject to the foregoing, may only be reproduced in full.

The results presented in this report relate exclusively to the samples selected by the client for the purpose of testing. No responsibility is taken for the representativeness of these samples.

INITIAL DISTRIBUTION

Scandia Stoves and Spares Pty Ltd
Lot 1 Melbourne Crescent
SEYMOUR VIC 3660

Copy No

Mr Ray Cassar

1

HRL Technology Pty Ltd

HRL Report Archive
File: VPM05-0136

2

3

This is copy No

**THERMAL CLEARANCE TESTING OF THE
CUISINE TOP FIRED BAKERS OVEN MKII SOLID FUEL COOKING
APPLIANCE TESTED WITH A HAWKWIND TRIPLE SKIN FLUE KIT**

Report

The appliance and flue system were installed into a standard Clearance Test enclosure and tested in two positions in a manner conforming to joint Australian/New Zealand Standard 2918:2001, Appendix B. A minimum 950mm deep x 1100mm wide x 12mm thick floor protector (cement fibre sheet) should be used under and in front of the appliance base when installing the appliance (see joint AS/NZS 2918:2001 3.3.2). The floor protector should extend 300mm in front of the appliance base. The Thermal conductivity of the floor protector is $0.8 \text{ m}^2 \cdot \text{K/W}$ for 4mm sheets.

The Cuisine top fired bakers oven mkII solid fuel cooking appliance, when installed with a Hawkwind triple skin flue system, conforms to the requirements of joint AS/NZS 2918:2001, Appendix B, with respect to rear wall, side wall, floor and ceiling surface temperatures, when tested in the positions described in this report and using *Pinus radiata* firewood as the fuel type.

TEST POSITIONS

The appliance and flue combinations were tested at the following clearances:

Position A (Parallel)

100mm from rear wall to the edge of the appliance rear panel.
300mm from side wall to the edge of the appliance side panel.

Position B (Corner)

200mm from walls when measured from the rear corners of the appliance (45° to both walls).

Refer to Appendix 1 of this report for clearance diagrams.

Investigation: S. Marland

Report: S. Marland

Checked by: A. Wells

Signed: Approved:
S. Marland B. Ham
Technical Officer Manager, Gippsland

1. INTRODUCTION

HRL Technology Pty Ltd was requested to assess the Cuisine top fired bakers oven mkII solid fuel cooking appliance, in conjunction with a Hawkwind triple flue system. Clearance testing was performed according to joint AS/NZS 2918:2001, Appendix B.

This report provides details of the safety clearance tests performed at the Solid Fuel Heater Testing and Research Laboratory of HRL Technology Pty Ltd. The testing was conducted from the 14th to the 21st of July 2005, by Mr S Marland. The testing was commissioned by Scandia Stoves and Spares Pty Ltd and the test results remain the property of this company.

The appliance was tested using *Pinus radiata* as firewood. No testing was undertaken with coal or briquettes.

2. DETAILS OF APPLIANCE

The test results reported below apply only to the appliance/flue system tested. The details of the appliance given in this section include features which may affect safety clearances. Any change in the construction or design of this model of the appliance or flue could invalidate this report.

Appendix 2 gives test appliance construction details.

3. INSTALLATION OF THE APPLIANCE

The appliance/flue combination was installed in two test positions at clearances specified by the manufacturer after preliminary testing. Floor thermocouples were positioned according to joint AS/NZS 2918:2001, Appendix B.

3.1 Floor Protector

A floor protector was installed beneath and in front of the appliance. The floor protector (cement fibre or similar) must be installed so that its leading edge is a minimum of 300mm in front of the appliance base. The floor protector must be a minimum of 1100mm wide x 950mm deep x 12mm thick. The floor protector consisted of 12mm thick cement fibre sheet with a thermal resistance value of 0.8m².K/W for 4mm sheets.

3.2 Flue System

The flue system used throughout testing was a Hawkwind Triple flue kit which was manufactured by S.V. Metals Pty Ltd. This flue system has not been tested to joint AS/NZS 2918:2001, Appendix F by HRL Technology Pty Ltd. Appendix 3 shows details of the flue system.

The flue height was 4.6 metres $\pm$ 0.3 metres from the floor protector.

4. CLEARANCES

4.1 Position A

The appliance was installed into the test enclosure with a rear wall clearance of 100mm and a side wall clearance of 300mm. Clearance measurements were taken from the appliance rear and side panels respectively (see Appendix 1).

4.2 Position B

The appliance was installed into the test enclosure in a corner position (45° to both side walls) with a clearance of 200mm to the side walls when measured from the appliance rear corners (see Appendix 1).

5. PROCEDURE

All clearance testing took place from July 14th to July 21st 2005. The floor thermocouples were installed into positions as per joint AS/NZS 2918:2001, Appendix B. Other thermocouple positions were determined by monitoring surface temperatures during trial burn cycles. Hot sites were located with the aid of a Linear Laboratories C-600E infra-red pyrometer.

All thermocouple tips were stapled onto the test surfaces, with black tape over the first 100 mm to facilitate consistent and accurate recording of temperatures. Thermocouple positions are shown in Tables 1 and 2.

5.1 High Fire Test

The appliance was fully fired in accordance with Section B9.1 of the joint Standard. The level of fuel was maintained between 50-75% of the full volume level of the fuel chamber during the High Fire test.

The average fuel load for initiating the High Fire tests was 6.6kg with an average refuelling rate of 1.1kg/10 minutes.

During High Fire testing it was found that the highest surface temperatures caused through the operation of the appliance occurred when the primary air control was fully open.

5.2 Flash Fire Test

Immediately after the High Fire test was completed, sufficient embers were removed to bring the fire bed to a level of 15-25% of the fuel chamber volume. The appliance was then fired in accordance with Section B9.2 of the joint Standard. The average fuel load for initiating the Flash Fire tests was 10.4kg. Highest temperature rises were achieved by fully opening the primary air control and leaving the main door 30mm ajar from the door catch

5.3 Fuel

The appliance was fired using a standard firewood fuel of *Pinus radiata* with an average moisture content of 13.4%. Each firewood piece was 300mm x 100 mm x 40 mm.

6. RESULTS

6.1 Uncertainty of Measurement Statement

- (a) The uncertainty of distance measurement for determining clearance distances was not greater than ± 2 mm.
- (b) The uncertainty of temperature measurement during the entire test period was $\pm 2^{\circ}\text{C}$ at the 95% confidence level.


6.2 Test Enclosure Temperatures

Table 3 shows the ambient temperature range during testing. Tables 4 and 5 show the maximum temperature rise above ambient for each test surface.

7. CONCLUSION

The Cuisine top fired bakers oven mkII solid fuel cooking appliance, when installed with a hawkwind flue system, conforms to the requirements of Australian/New Zealand Standard 2918:2001, with respect to floor, ceiling, side wall and rear wall surface temperatures, when tested in the test positions described earlier in this report in accordance with Appendix B of the joint Standard.

Table 1: Position A



Thermocouple	Channel No
11 Ceiling, inside wooden ceiling rim, to front of appliance	11
12 Ceiling, 25 mm from wooden ceiling rim, to front of appliance	12
13 Ceiling, inside wooden ceiling rim, to LHS of appliance	13
14 Ceiling, 25 mm from wooden ceiling rim, to LHS of appliance	14
16 Side wall, 490 mm from corner, 1020mm above floor	16
17 Side wall, 580mm from corner, 1000mm above floor	17
18 Rear wall, 530mm from corner, 1090mm above floor	18
19 Rear wall, 580mm from corner, 880mm above floor	19
20 Ambient temperature	20

Table 2: Position B

Thermocouple	Channel No
11 Ceiling, inside wooden ceiling rim, to RHS of appliance	11
12 Ceiling, 25 mm from wooden ceiling rim, to RHS of appliance	12
13 Ceiling, inside wooden ceiling rim, to LHS of appliance	13
14 Ceiling, 25 mm from wooden ceiling rim, to LHS of appliance	14
16 RHS wall, 590mm from corner, 1000mm above floor	16
17 RHS wall, 750mm from corner, 1180mm above floor	17
18 LHS wall, 550mm from corner, 1160mm above floor	18
19 LHS wall, 730mm from corner, 1060mm above floor	19
20 Ambient temperature	20

Table 3: Ambient Temperature Range °C

Position	High Fire	Flash Fire
A	24.4 – 32.3	27.8 – 31.4
B	17.4 – 31.4	29.3 – 31.9


Table 4: Maximum Temperature Rise - Position A

Position	Thermocouple Number	High Fire Test (°C)	Thermocouple Number	Flash Fire Test (°C)
Floor	6	59.2	5	77.2
Ceiling	12	26.1	13	27.4
Rear Wall	19	46.5	19	48.3
Side Wall	17	52.0	17	47.0

Table 5: Maximum Temperature Rise - Position B


Position	Thermocouple Number	High Fire Test (°C)	Thermocouple Number	Flash Fire Test (°C)
Ceiling	13	19.7	13	21.3
RHS Wall	16	62.0	16	60.2
LHS Wall	18	61.1	18	59.8

**APPENDIX 1:
MINIMUM CLEARANCES FOR THE CUISINE TOP FIRED BAKERS OVEN MKII
SOLID FUEL COOKING APPLIANCE INSTALLED WITH
A HAWKWIND THRIPLE SKIN FLUE KIT**



Position A

The floor protector consisted of 12mm thick cement fibre sheet which had a thermal resistance of $0.8\text{m}^2.\text{K/W}$



Position B

**APPENDIX 2:
SOLID FUEL BURNING APPLIANCE CONSTRUCTION DETAILS**

Appliance Model Name:	Cuisine Top Fired Bakers Oven mkII		
Manufacturer:	Scandia Stoves and spares Pty Ltd		
Serial Number:	Prototype		
Overall Height (to top of top plate):	940mm		
Overall Width (not including top plate):	670mm		
Overall Depth (not including top plate):	540mm		
Top Plate Width:	690mm		
Top Plate Depth:	508mm		
Top Plate Thickness:	25mm		
Appliance Base:	Height: 50mm	Width: 50mm	Depth: 50mm
Appliance Pedestal:	Height: 285mm	Width: 470mm	Depth: 380mm
Firebox Description:	Height: 350mm	Width: 470mm	Depth: 380mm
Firebox Material Type/ Seam Fully Welded:	Cast Iron		
Firebrick Size:	Height: 120mm Thickness: 30mm	Width: 350mm No of: 2.5	
Main Door Opening:	Height: 225mm	Width: 470mm	
Door:	Height: 375mm	Width: 500mm	Depth: 20mm
Door Glass:	Height: 164mm	Width: 338mm	
Primary Air:	2 Ports at 60mm diameter located in base of door.		
Secondary/Tertiary Air:	4 holes at 5mm diameter, 2 in each side of firebox		
Baffle Plate:	None		
Flue Dimensions:	138mm OD		
Spigot Dimensions:	151mm OD	147mm ID	
Spigot to Rear of Appliance:	50mm		
Rear Internal/External Heat Shield:	40mm, rear shield was 670mm x 1050mm		
Side Internal/External Heat Shield:	12mm		
Heat Shield Material Type:	1.2mm sheetmetal		
Fan Location/Speeds:	No fan fitted		
Grate:	☐ Yes	☒ No	
Diagrams:	Over the page		
Signed: Date:			

**APPENDIX 3:
HAWKWIND TRIPLE SKIN FLUE KIT**



The Cuisine

Cast Iron Top Fire Baker's Oven

Adaptability is one of many attributes of the Cuisine. The thermal properties of cast iron firebox combined with its generous size result in a significant heat output

Other features of this solid cast iron oven include being able to heat domestic hot water and the ability to be installed in a kitchen or living area.

A wetback option is available for the heating of domestic hot water:

Fuel

Seasoned and dry wood, or coal all burn effectively and efficiently. Fuel consumption and cooker output will vary according to the calorific value and quantity of fuel used.


Flue

Approved 140mm flue connected to top of cooker.
Minimum length 3.6m.



Features:

- Solid Cast Iron Durability
- Five Year Warranty
- Large Cast Iron Oven with Temperature Gauge
- Large Firebox
- Cast Iron Hot Plate
- Ashpan
- High Heat Output
- Domestic Hot Water Boiler (optional) with (3/4") tappings on back of cooker
- Overnight Burning
- Simple Controls
- Efficiency and Economy
- Thermal clearance testing to AS/NZS 2918:2001 (Appendix B)



The Cuisine Specifications



Clearances from combustible surfaces:

Sides	Rear	Rear with Splashback
300mm	225mm	100mm

Dimensions: Overall

Height	925mm
Depth	565mm
Width	705mm
Oven Size	465w x 285h x 380d
Firebox Size	385w x 330h x 335d
Firebox Door Opening	205h x 385w
Weight	248Kg

The floor protector must consist of 12mm thick cement fibre sheet or similar.



Scandia – a family business with a strong Australian Heritage

The Scandia story dates back to shortly after the Second World War when Mr Vic Cassar was manufacturing and repairing solid fuel stoves which he sold in the markets of Melbourne.

In 1961 he rented three small factories around Fitzroy where he continued to make and repair stoves. By 1972 the business had outgrown these factories and he decided to decentralise to Seymour, taking with him his two sons and a number of skilled tradesmen.

The Seymour complex consisted of a manufacturing and assembly plant, a foundry (shown below) and a vitreous enamelling plant. Stoves were produced for several decades from sheet steel and pig iron to the completed product.



Over the years however, the lack of skilled workers in the hot and physically demanding jobs of the foundry and the enamelling plant saw the closure of these divisions and the eventual sourcing of high-quality castings from China and Taiwan.

In the early 1980s, one of Vic's sons Ray and son-in-law Jeff gradually took over the running of the company continuing to manufacture and assemble solid fuel cookers.

In the late 1990s Ray's sons Ben, Vic and Jake commenced with the company working in the spare parts store, stove building and the steel fabrication divisions.

In recent times Vic has moved on leaving Jake and Ben to run the company. Due to Scandia's pursuit of supplying first-class products they have now set up a factory in China to specifically produce their products using premium materials.

Jake and Ben continually travel to the factory to oversee the production and inspect every shipment of cookers and heaters ensuring superior quality which is guaranteed with a Five Year Warranty.

Three generations of stove builders have made Scandia Australia's leading supplier of quality and reliable solid fuel stoves backed by the largest range of spare parts for most makes and models of combustion heaters and cookers.

Heating Marlborough

55 Grove Road

Blenheim

Phone 03 578 5950

heatingmarlborough@extra.co.nz



Scandia have established an enviable reputation in the manufacture and supply of quality replacement parts for an extensive range of combustion stoves and heaters covering models over the last eighty years.

Due to our policy of continuous improvement of our products and services, technical specifications and claims, correct at the time of going to print, may be subject to variation without prior notice. Scandia Stoves & Spares Pty Ltd has endeavoured to ensure that the information in this document is correct and fairly stated, but does not accept liability for any error or omission.

Scandia Stoves & Spares Pty Ltd

ABN 75 104 878 588 ACN 104 878 588

Lot 1 Melbourne Crescent, Seymour VIC 3660

Postal Address:

PO Box 372, Seymour VIC 3660 Australia

Ph: 03 5792 2388 Fax: 03 5792 2021

Email: info@scandiastoves.com.au

Website: www.scandiastoves.com.au

Dealer Stamp

Fireworx/Fires By Design Ltd
1048 Fergusson Dr, Upper Hutt
Ph: 04 526 2001 Fax: 04 526 2051
email: fireworx@extra.co.nz

GIB® Wall Bracing Calculation Sheet A**lower of two**

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

Job Details

Name	ROLSTON
Street and Number	125 NIKAU PALM RD, PARAPARAUMU
Lot and DP Number	LOT 4 DP 82049
City/Town/District	KAPITI COAST
Designer and date	Dean Robb 1601/2009
Company Name	Architecture DM

Building Specification

Location of Storey	lower	▼	not applicable (slab)
Floor Loading	2 kPa	▼	
Foundation Type	slab	▼	
Building Height to Apex (m)	8	▼	
Roof Height above Eaves (m)	2	▼	
Stud Height (m)	2.7	▼	
Cladding Weight (top or single)	light	▼	
Cladding Weight (lower)	heavy	▼	
Cladding Weight (subfloor)	light	▼	
Roof Weight	light	▼	
Roof Pitch (degrees)	0-25	▼	
Room in Roof Space	no	▼	
Building Length (m)	22.2		
Building Width (m)	11		
Gross Building Plan Area (m2)	193.7		

Building Location

Wind Zone	Very High	Earthquake Zone
Region	R2	A
Terrain	Inland	
Exposure	Exposed	
Topography	Moderate	

Bracing Units required for Wind

per m	subfloor	walls
W along	n/a	215 BUs/m
W across	n/a	202 BUs/m
Totals	subfloor	walls
W along	n/a	2365 BUs
W across	n/a	4484 BUs

Bracing Units required for Earthquake

per m2	subfloor	walls
E	n/a	13.5 BUs/m2
Totals	subfloor	walls
E along	n/a	2615 BUs
E across	n/a	2615 BUs

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
NZS 4229	MASONAF	6	622.5	622.5
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
NZS 4229	MASONAF	6	622.5	622.5
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Wall Bracing Calculation Sheet A

upper of two

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

Job Details

Name	ROLSTON
Street and Number	125 NIKAU PALM RD, PARAPARAUMU
Lot and DP Number	LOT 4 DP 82049
City/Town/District	KAPITI COAST
Designer and date	Dean Robb 1601/2009
Company Name	Architecture DM

Building Specification

Location of Storey	upper	▼	not applicable (slab)
Floor Loading	2 kPa	▼	
Foundation Type	slab	▼	
Building Height to Apex (m)	8	▼	
Roof Height above Eaves (m)	2	▼	
Stud Height (m)	2.7	▼	
Cladding Weight (top or single)	light	▼	
Cladding Weight (lower)	heavy	▼	
Cladding Weight (subfloor)	light	▼	
Roof Weight	light	▼	
Roof Pitch (degrees)	0-25	▼	
Room in Roof Space	no	▼	
Building Length (m)	22.2		
Building Width (m)	11		
Gross Building Plan Area (m2)	201.2		

Building Location

Wind Zone	Very High	Earthquake Zone
Region	R2 ▼	A ▼
Terrain	Inland ▼	
Exposure	Exposed ▼	
Topography	Moderate ▼	

Bracing Units required for Wind

per m	subfloor	walls
W along	n/a	87 BUs/m
W across	n/a	75 BUs/m
Totals		
W along	n/a	957 BUs
W across	n/a	1654 BUs

Bracing Units required for Earthquake

per m2	subfloor	walls
E	n/a	6.2 BUs/m2
Totals		
E along	n/a	1247 BUs
E across	n/a	1247 BUs

GIB® Wall Bracing Calculation Sheet B

upper of two

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

GIB® EzyBrace™									
Along									
Wall or Bracing Line		Bracing Elements provided							
1	2	3	4	5	7	8	6	Wind	Earthq.
Line Label	Minimum BUs Req/Ach	Bracing Element No.	Supplier	Bracing Type	Element Length L (m)	Element Height H (m)	Angle to Bracing line (degrees)	BUs Achieved	BUs Achieved
A	enter	1	GIB®	GS1a	4.8	2.7		320	277
		2	GIB®	GS1a	2.2	2.7		127	108
line totals		3	GIB®	BL1	1.2	2.7		133	123
W	580	4							
EQ	508	5							
B	enter	1	GIB®	GS2	2.2	2.7		156	137
		2	GIB®	GS1a	3.6	2.7		240	208
line totals		3							
W	396	4							
EQ	345	5							
C	enter	1	GIB®	BL1	1.4	2.7		156	143
		2	GIB®	BL1	1.4	2.7		156	143
line totals		3							
W	311	4							
EQ	286	5							
D	enter	1	GIB®	GS1a	2	2.7		116	98
		2							
line totals		3							
W	116	4							
EQ	98	5							
E	enter	1	GIB®	GS1a	3.6	2.7		240	208
		2							
line totals		3							
W	240	4							
EQ	208	5							
F	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
G	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
H	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
								Wind	Earthq.
Totals Achieved								1644	1444
								OK	OK
Totals Required (from Sheet A)								957	1247

GIB® Wall Bracing Calculation Sheet B

upper of two

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

Along		Bracing Elements provided						Wind	Earthq.
Wall or Bracing Line								9W	10EQ
1	2	3	4	5	7	8	6		
Line Label	Minimum BUs Req/Ach	Bracing Element No.	Supplier	Bracing Type	Element Length L (m)	Element Height H (m)	Angle to Bracing line (degrees)	BUs Achieved	BUs Achieved
A	enter	1	GIB®	GS1a	4.8	2.7		320	277
		2	GIB®	GS1a	2.2	2.7		127	108
line totals		3	GIB®	BL1	1.2	2.7		133	123
W	580	4							
EQ	508	5							
B	enter	1	GIB®	GS2	2.2	2.7		156	137
		2	GIB®	GS1a	3.6	2.7		240	208
line totals		3							
W	396	4							
EQ	345	5							
C	enter	1	GIB®	BL1	1.4	2.7		156	143
		2	GIB®	BL1	1.4	2.7		156	143
line totals		3							
W	311	4							
EQ	286	5							
D	enter	1	GIB®	GS1a	2	2.7		116	98
		2							
line totals		3							
W	116	4							
EQ	98	5							
E	enter	1	GIB®	GS1a	3.6	2.7		240	208
		2							
line totals		3							
W	240	4							
EQ	208	5							
F	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
G	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
H	enter	1							
		2							
line totals		3							
W		4							
EQ		5							

Wind Earthq.

1644 1444

Totals Achieved

OK OK

Totals Required (from Sheet A)

957 1247

GIB® Bracing Systems, 2006

<i>For full construction details see literature</i> GIB® Bracing Systems, 2006
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
 All rights reserved

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

KCDC CODE COMPLIANCE REVIEW CHECK SHEET

00061

Criteria: All building work except for minor works or major projects. Refer BL-WI-024

Address: New Dwelling 125 Nikau Palm Road PARAPARAUMU	Date:
	BC No:

application for code compliance certificate (Form 278) completed	Y	N
--	---	---

Confirm all required inspections have been completed and passed: Answer: Yes or No

If inspections have been missed, what supporting info and method of verification has been provided to compensate for missed inspection. (Describe):

Work in accordance with approved consent and approved amendments		Yes	No
If no, has NTF been issued:	N/A	Yes	No
Have items of non compliance been resolved and NTF uplifted.	N/A	Yes	No

Note: If work is not in accordance with consent, (and approved amendments) or NTF matters have not been resolved, suspend application for Code Compliance Certificate

Supporting documentation required in building consent addenda (Accept in accordance with KCDC Policy 002) Form completed during BC Approval process

Tick (✓) indicates yes, N/A indicates considered - but not applicable	Req'd	Supplied	Accept
copy of electrical certificate	✓	✓	
copy of gas certificate	✓	✓	
an "as-built" drainage plan	✓	✓	
plumbing (Form 125) for pressure test and installation piped services	✓	✓	
drainage (Form 126) for stormwater installation	✓	✓	
drainage (Form 127) for private sewer installation	✓	✓	
a Construction Review (PS4) statement for Structural engineering	✓	✓	
a Construction Review (PS4) statement for Fire engineering			
a Construction Review (PS4) statement for Geo-technical engineering			
Roof cladding warranty	✓	✓	
Solar water heating technical specifications			
wall cladding/texture coating installation applicator warranty			
a copy of the lift certificate			
a certificate from the fire alarm installer	✓	✓	
a certificate from the sprinkler installer			
a copy of wet-area membrane installers warranty			
A copy of deck membrane manufacturer's installers warranty/guarantee			
FPIS (verifier) Fire Systems Certification			
Installers Checksheet wood burner	✓	✓	

KCDC Building Consent Authority
Building Consent Documentation Filed

00062

BC No.
Street Address.

090214

**New Dwelling
125 Nikau Palm Road
PARAPARAUMU**

Tick indicates document(s) included in this Building Consent

Tick indicates document(s) included in this submission								
Building Consent Application,								✓
Application checksheet,								✓
Costing schedule,								✓
Plans and specifications,								✓
Invoice and receipt,								✓
Processing records/checksheets,								✓
Inspection page printouts								✓
Building consent and memorandum,								✓
Inspection reports,								
Application for CCC,								
Code of Compliance Certificate.								
Producer statements and supporting documentation,								
Peer review documents,								
Fire design documents,								
Requests for further information and other correspondence,								
Amendments,								
Supplementary information,								
Energy work certificates,								
Notices to Fix.								

This form comprises part of the Building Consent documentation and indicates the contents of the Building Consent File. Refer KCDC Policy 029.

KCDC CODE COMPLIANCE REVIEW CHECK SHEET

If specified supporting documentation has not been provided, what alternative information or verification method has been provided to compensate. (describe):

Compliance Schedule

Is a new or amended compliance schedule required?

Y

N

If "Y" Has it been issued? (Refer note below)

Y

N

If the new/ revised compliance schedule has not been issued, what action has been taken to ensure it will be issued? Outline:

Note: If the draft/ revised compliance schedule has not been issued, the Code Compliance Certificate cannot be issued. Suspend issuing CCC until this matter is addressed.

Building consent requirements.

Are there any item specified in the building consent or PIM that have not been completed.

Outline: -----

Are there any development impact fees to be paid outstanding? Yes / No (if yes, CCC cannot be issued)

Approve to issue Code Compliance Certificate if all other outstanding fees are paid. YES / NO

Building officer:

Signature:

Date:/...../.....

Name:

Co- reviewer:

Signature:

Date:/...../.....

Name:



**COMPUTER FREEHOLD REGISTER
UNDER LAND TRANSFER ACT 1952**

Search Copy



R. W. Muir
Registrar-General
of Land

Identifier WN48D/201
Land Registration District Wellington
Date Issued 26 July 1996

Prior References
WN45B/819

Estate Fee Simple
Area 2.2730 hectares more or less
Legal Description Lot 4 Deposited Plan 82049

Proprietors
Thomas Sinclair Roulston and Olga Roulston

Interests

516880 Subject to reservations as to coal, gold and silver

Appurtenant hereto are water supply rights specified in Easement Certificate B400853.7


B531004.4 Consent Notice pursuant to Section 221 Resource Management Act 1991 imposing ongoing conditions - 26.7.1996 at 12.34 pm


Land Covenant in Transfer B531004.12 - 26.7.1996 at 12.34 pm

Land Covenant in Transfer B727216.2 - 11.6.1999 at 9.59 am

Subject to an electricity and telecommunications right (in gross) over part marked L on DP 87177 in favour of Transpower New Zealand Limited created by Transfer B800861.3 - 6.9.2000 at 3.55 pm

8294552.1 Mortgage to Westpac New Zealand Limited - 25.9.2009 at 12:42 pm





KCDC Building Consent Authority
 Building Consent **AMENDMENTS** Documentation Filed



BC No.	BC 090 214A
Street Address.	123 NIKAU Palm Rd Paraparaumu

Tick indicates document(s) included in this Building Consent

Amendment Consent Application,	☒
Costing schedule,	☒
Amended Plans and specifications,	☒
Invoice and receipt,	☒
Processing records/checksheets,	☒
Inspection page printouts	☒
1-8 11 25-26 28-31	
Amended Building consent and memorandum,	
Producer statements and supporting documentation,	
Peer review documents,	
Fire design documents,	
Requests for further information and other correspondence,	
Supplementary information,	

This form comprises part of the Building Consent documentation and indicates the contents of the Building Consent File. Refer KCDC Policy 029.

PRELINE PLUMBING INSPECTION REQUIRED

WATER PIPES TESTED TO 1500KPA

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

UPPER FLOOR PLAN

06

DATE: 26 MAR 2009
SCALE: 1:100 @
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM


17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LT

A D N Z
ARCHITECTURAL DESIGNERS



LEVEL 2
1:100

RECEIVED

11 JAN 2010

KAPITI COAST
DISTRICT COUNCIL

- SA = SMOKE ALARM
- MV = MECHANICAL VENTILATION
- = ALUMINIUM FARAL LINEAL 80 RADIATORS
- HI-COP 3.61 FUJITSU LOW PROFILE DUCTED INVERTER EMBEDDED IN CEILING
- 2/290x45 MSG8 UNDERSTUDS
- 125x6 SHS COLUMNS

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

- Cantilevered joist size altered
- Balcony membrane changed

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE!

SECTIONS

09

DATE: 5 MAY 2009
SCALE: 1:100 @A3

JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM


17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz


© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC



Section 3

1:100



Section 4

1:100

NOTE: All beams are engineered design - please refer to engineers documentation for all calculations and connection/fixing details

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev:	Description:	Date:
-	Canterlevered joist size altered	
-	Balcony membrane changed	

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE!

SECTIONS

08

DATE: 5 MAY 2000
SCALE: 1:100 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC

Corrugated profile Colorsteel roofing over
Thermakraft 215 self supporting underlay over
70x45 purlins @ 900cirs over PS40-40x09
Post-STRUT MSG8 roof trusses @ 600cirs
with R3.6 insulation

PS40-60X05 Post-STRUT MSG8 floor truss
System @ 400cirs as per MITEK specification

BEAM 8 - 2/290x45 MSG8 above

BEAM 11 - 125x8 SHS


Slack Rain Ties
FlexSeal exterior waterproof deck liquid
membrane on 17mm H3.2 construction
ply packed to a 1.5° fall (to each gutter)
on H3.2 packers @ 400cirs on 240x45
MSG8 joists @ 400cirs

Arena 'Vetro' glass balustrade
with 10mm grade 'A' safety glass
& aluminium balusters @
900max cirs for high wind

CraftStone exterior schist veneer
cladding on Flexco Megamortar
binding additive and primer on
6mm fibre cement backing sheet
fixed on H3.1 Ex 45x20 cavity
battens on Thermakraft Dilex 130
building wrap on 90x45 MSG8 H1.2
framing @ 400 cirs

Section 1

1:100



Corrugated profile Colorsteel roofing over
Thermakraft 215 self supporting underlay over
70x45 purlins @ 900cirs over 90x45 MSG8
trusses @ 900cirs with R3.6 insulation

Corrugated profile Colorsteel roofing over
Thermakraft 215 self supporting underlay over
70x45 purlins @ 900cirs over PS40-40x09
Post-STRUT MSG8 roof trusses @ 600cirs
with R3.6 insulation

Plaster finish over EIFS cladding over 20mm drained
cavity and Thermakraft Dilex 130 building wrap on
140x45 MSG8 H1.2 framing @ 400cirs with R2.6
insulation

PS40-60X05 Post-STRUT MSG8 floor truss
System @ 400cirs as per MITEK specification

25 series reinforced concrete block retaining wall with
control joints @ 6.0m cirs

100mm 25MPa concrete slab @ 28 days with 665
mesh over 0.25 polythene on 50mm sand blinding on
min 100mm compacted basecourse - 40mm R1.3
EPS insulation under slab

Coredrain as per manufacturers specifications

Section 2

1:100

Corrugated profile Colorsteel roofing over
Thermakraft 215 self supporting underlay over
70x45 purlins @ 900cirs over 90x45 MSG8
trusses @ 900cirs with R3.6 insulation

4.5mm Hardiflex soffit lining

Approved truss design

Double glazed powdercoated
aluminium joinery

Plaster finish over EIFS cladding
over 20mm drained cavity and
Thermakraft Dilex 130 building
wrap on 90x45 MSG8 H1.2 framing
@ 400cirs with R2.6 insulation

140x45 MSG8 H3.2 bearers
on 125x125 H6 anchor piles
in 350x350x900 conc pad

25 series reinforced concrete block retaining
wall with control joints @ 6.0m cirs

Engineered retaining wall footing detail

100mm 25MPa concrete slab @ 28 days with 665
mesh over 0.25 polythene on 50mm sand blinding on
min 100mm compacted basecourse - 40mm R1.3
EPS insulation under slab

Standard 13mm GIB to all interior ceilings on Rondo
steel system @450cirs (Ultraline to diaphragms)

Butynol membrane roofing on 17mm H3.2
plywood over packed to a 1.5° fall on H3.2
packers @ 400cirs on on H3.1 140x45
MSG8 rafters @ 600 max cirs

6mm Hardiflex lining fixed to 140x45 outriggers


Double glazed powdercoated
aluminium joinery

Arena 'Vetro' glass balustrade with 10mm
grade 'A' safety glass & aluminium
balusters @ 900max cirs for high wind

Slack Rain Ties
FlexSeal exterior waterproof deck liquid
membrane on 17mm H3.2 construction
ply packed to a 1.5° fall
(to each gutter) on H3.2 packers @ 400cirs on
190x45 MSG8 joists @ 400cirs


CraftStone exterior schist veneer cladding
on Flexco Megamortar binding additive and
primer on 6mm fibre cement backing sheet
fixed on H3.1 Ex 45x20 cavity
battens on Thermakraft Dilex 130 building wrap on
90x45 MSG8 H1.2 framing @ 400 cirs

NOTE: All beams are engineered design - please
refer to engineers documentation for all
calculations and connection/fixing details



MEMBRANE ROOF DETAIL

1:10



MEMBRANE DECK DETAIL

1:10

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

- Canterlevered joist size altered
- Balcony membrane changed

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE!

CONSTRUCTION DETAILS

19

DATE: 5 MAY 2009
SCALE: 1:10 @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC

FOR COUNCIL USE:

Department	✓ For Referral	Comments	Approving Officer / Date
Planning			
Plumbing and Drainage			
Building	✓		<i>[Signature]</i> 26.02.2016
Fire Design			
Compliance Schedule			
Structural			
Hazardous Substances			
Environmental Health			
Other.....			
NOTES:			



AMENDED BUILDING CONSENT APPLICATION COVERSHEET (Green Folder)

125 Nikaia Rd, Porpoara

Building Consent No.	090214B
Building Project	durability modification

CONSENT DATA INPUT REQUIREMENTS

✓	Required Inspections	✓	Required Inspections	✓	Required Inspections	✓	Required Inspections
	Foundation/Piles		Drainage		Pre-lining (Plumbing)		Final (Dwelling)
	Block		Pre-Wrap		Wet areas - membrane		Retaining Wall
	Pre-Slab (Plumbing)		Pre-Clad		Post Lining		
	Pre-Slab (Building)		Weathertightness		Brick Veneer		
	Sub-Floor		Pre-lining (Building)		Retaining Wall		

Office use	✓	Office use	✓
32		23A	
2		25	
3		30	
4		31	
6		33	
9		34	
10		38	
11		39	
12		40	
13		43	
15		44	
21			
23			

Act Ref	✓	Standard Consent Conditions	Comment
37		Resource Consent has not yet been obtained	
72 73		Land subject to natural hazard	
75-80		Construction on two or more allotments	

Non-Standard Addenda

Yes/No ☐ Compliance Schedule

Yes/No ☐ Office - please see additional consent data comments on next page


OGST 51-860-608

Received with thanks by 50/01
KAPITI COAST DISTRICT COUNCIL

23-02-16 10:14 Receipt no.526725

COPY *COPY* *COPY*
DR BC090214B 219.00-
ARCHITECTURE DM
Architecture DM::17 Gear Street:PETONE:
CQ EFT
Architecture DM 219.00

APPROVED
BY
BUILDING
Leon
Smith
26/02/2016



checked on 9/02/2010
00001

DURABILITY MODIFICATION



Address of Property:

125 Nikau Palm Road.
Paraparaumu

Building Consent Number:

BC 090214

Request:

Due to the time delay in my application for a Code of Compliance Certificate, I would like to amend the above Building Consent in relation to a modification of durability clause B2.3.1 of the Building Code.

The commencement date for durability is to be backdated to:

Date 1/6/10

Signature:

Name: (please print)

Thomas Roulston

Signed:

Date

The back dating of the commencement of the date for durability to ~~1st Dec~~ 1st June 2010 is agreeable to both parties.

After going through the inspection records online.

A handwritten signature in cursive script, appearing to read "Steve Smith".

25th. 2. 2016

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

SITE PLAN

02

DATE: 26 MAR 2009
SCALE: 1 : 1000 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE


P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

PLUMBING + DRAINAGE NOTES:

- ALL PLUMBING AND DRAINAGE TO COMPLY WITH AS/NZS 3500 PART 2.2
- ALL STORMWATER AND SEWER PIPES TO BE 110dia PVC @ GRADIENT 1:100MIN.
- PLUMBING INFORMATION SHOWN FOR BUILDING CONSENT ONLY
- DRAINLAYER IS TO PROVIDE AS-BUILT DOCUMENTATION TO T.A. ON COMPLETION.
- INSPECTION POINTS TO BE PROVIDED AT THE FOLLOWING LOCATIONS:
- A) AT EVERY DRAIN JUNCTION TO ANOTHER DRAIN (EXCEPT WHERE BRANCH DRAIN IS LESS THAN 2.0M AND SERVES A G.T. ONLY)
- B) EVERY CHANGE IN HORIZONTAL DIRECTION GREATER THAN 45°
- C) EVERY CHANGE OF GRADIENT GREATER THAN 45°
- D) WITHIN 2.0M OF BUILDING WHERE A DRAIN ENTERS OR EXISTS FROM UNDER A BUILDING
- E) AT DRAIN CONNECTION TO LATERAL



SITE PLAN

1 : 1000

SP = Soak pits for lower floor roof runoff and water tank overflow

ST = Silt traps for Coredrain runoff

LEGAL DESCRIPTION	COUNCIL	AREAS	ZONES
ADDRESS: 125 NIKAU PALM RD CITY: PARAPARAUMU	Zone: RURAL Setbacks: Compliant Height Restriction: Compliant Recession Plane: Compliant Site Coverage: Compliant	Allowed Coverage: 35% Site Area: 22730m ² Footprint area: 193.7m ² Coverage: 0.85%	Wind Zone: HIGH Wind Region: R2 Corrosion Zone: 1 Earthquake Zone: A
LOT 4 DP 82049			

LOWER FLOOR AREA = 193.7M2
UPPER FLOOR AREA = 201.2M2
TOTAL FLOOR AREA = 394.9M2
BALCONY AREA = 66.7M2

125 NIKAU PALM ROAD
PARAPARAUMU

Rev: Description: Date:

IF IT ISN'T DIMENSIONED - DO NOT SCALE


03

DATE: 26 MAR 2009
SCALE: As indicated @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURAL DM

© ARCHITECTURE DM LTD

ARCHITECTURAL DESIGNERS NZ INC



TYPICAL ENGINEERED INTERNAL PAD DETAIL

1:20



KAPITI COAST DISTRICT COUNCIL
APPLICATION FOR A CONNECTION TO COUNCIL WATER SUPPLY

..... Roulston (full name)
PLEASE PRINT

.....
(postal address) hereby apply for an "ORDINARY" service to be laid from the Kapiti Coast District Council water supply to the premises owned by me at:

PROPERTY ADDRESS in full 25 Nisany Palm Rd
(if different from above)

Lot 4 DP 82049

Fees payable (on application)

Inspection \$
Connection \$
Total \$ N/C

Note: All dwelling units to pay full inspection fees.
The connection fee to be divided equally between dwelling unit situated the same lot sharing a common lot.

.....
Owners signature

.....
Date

THIS PART TO BE COMPLETED BY PLUMBER

I, T.B.A (full name)
of (address) being a
Licensed Craftsman Plumber apply for permission to connect the above premises to the Kapiti Coast District Council water supply. I agree to comply in every respect with the Kapiti Coast District Council Water Supply Bylaw.

NB: Connection NOT permitted until permit obtained.

.....
(Signature)

.....
(Craftsman Licence No)

.....
(Date)

1. Existing Water Supply
2. Pressure: High/Low
3. E/W cylinder type new duty
4. Approximate age of water piping
5. If premises have swimming pool, what capacity?


To be retained/dismantled
"Header Tank"/Pressure Reducing Valve
Exhaust pipe/pressure relief valve
Copper/PVC/Alkathene
Filter Plant Yes/No

6. State precisely how it is proposed to make the new connection

OFFICE USE ONLY

BUILDING CONSENT NO <u>090214</u>	PLUMBERS PRODUCER STATEMENT TO BE PROVIDED
Date Issued	Connection Recorded











Site Inspection Report - New BC Applications

BC Application number 90214 Lot 4 DP 82049

Site Address: 125 NIKAU PARK RD

Building Project: new building

Check NCS status is currently "To Site Inspection"

Item to be checked	Decision	Record any relevant information	Action required
Contours match application?	Yes/No		
Datum point identified?	Yes/No		
Boundaries identified?	Yes/No	Survey RGS with Rural Forestry	
Check ground conditions OK?	Yes/No	Level site, compacted ground hard as Engineer involves	
Check f/path, kerb & channel, grass berm, note existence/damage.	Yes/No	Good condition	
Vehicle entrance crossing installed (describe condition)	Yes/No	Rural. Good condition	
Photos taken? (Save & link to NCS)	Yes/No	in house file	
Dogs on property?	Yes/No		
Is there a requirement for further foundation investigation e.g. Engineers design	Yes/No		Referred to Approvals T/L Yes / No
Record all decisions in accordance with KCDC Policy 007. Circle Yes or No in each case.			

Note: if there is a requirement for further information or some areas which do not appear to comply refer file to Team Leader Consent Approvals for action.

Inspecting Officer: Name CALVIN MA Signature [Signature]

Date Inspected: 2.14.09

Unless further foundation information required, change NCS status to "To Plumbing & Drainage" and place file in P&D shelf area for Approvals. If further information is required, then Status change to "To Plumbing & Drainage" and hand to Team Leader Consent Approvals for action.

FOR COUNCIL USE:

DEPARTMENT	TICK FOR REFERRAL	COMMENTS	APPROVING OFFICER/ DATE
Resource Consents (refer PIM Sheet)	✓		
Plumbing and Drainage	✓		8/11/5/2009
Building	✓	Stuart Nepia 11-05-09	
Fire Design			
Compliance Schedule			
Environmental Health			
Site- Footpath & Entrance Conditions		Ground	
NOTES: SEE SITE NOTES			



Building Consent N

Building Project

Location (Site Add)

Building Category

090214

New Dwelling
125 Nikau Palm Road
PARAPARAUMU

0 1 2 3

Application workflow checklist

RECEIVED - 1 APR 2009 KAPITI COAST DISTRICT COUNCIL	Name & Signature Note # A signature confirms that the application contains sufficient information to enable compliance with the building code to be assessed	Date
# Note: Checked, date stamped and initialled by TO/BCO. Select and circle appropriate category above & identify allocation to appropriate technical groups and if required to go to "site inspection" AP-WI-001	Palmer	1/4/09
Payment taken and receipted (details entered inside this cover sheet) by CSO CS-WI-008	Angie	1/04/09
Data entered and invoiced by CSO CS-WI-008	Angie	1/04/09
Pages numbered by CSO CS-WI-008		
BC Application and documentation scanned, checked & status update by CSO CS-WI-009	Sarah & Angie	1/04/09
BC Application signed over to BC CS-WI-009	Angie	1/04/09
Application reviewed by Technical Officers who sign off at back of this form AP-WI-026 & AP-WI-009	Simon Copp Stuart Nepia	4/5/09 11/05/09
Once Technical review complete, passed to CS for Plan Production and Invoicing AP-WI-009		
CSO checks data entry input, including required inspections CS-WI-012		
BC, plans and other appropriate paperwork produced by CSO CS-WI-012	Jard K	12/5/09
BC, Approved plans and appropriate paperwork sent to applicant or agent with receipt by CSO CS-WI-012		
Inspection envelope prepared by CSO with endorsed plans and other appropriate paperwork and filed to cabinet. CS-WI-012		

CONSENT DATA INPUT REQUIREMENTS

REQUIRED INSPECTIONS	32	✓	Lapse and cancellation after 12mths of consent	23	✓	Installation of solid fuel appliance (wood burner) comply and secured
✓ Foundation/Piles						
✓ Block	2	✓	Engineer design specific components	23A	✓	Second hand wood burner certified
✓ Pre-Slab (Plumbing)	3	✓	Foundations to solid bearing of 200mm	25	✓	Contractor to leave site clean and clear
✓ Pre-Slab (Building)	4		NZS3604 as acceptable solution in terms of NZ Building Code	30		To comply with Food Hygiene Regulations 1974
Sub-Floor						
✓ Drainage	6		Not approved as Habitable Room	31		As in CCZ, all fixings need to be stainless steel
✓ Pre-Wrap	9	✓	Note and comply with all endorsements on approved plans	33		Approval only given for relocation purposes
✓ Pre-Clad	10	✓	Names and Registration of plumber and drain-layer required	34		If cladding to have pre-finished colour coating, to be appropriate for coastal conditions
✓ Weathertightness						
✓ Pre-lining (Building)	11	✓	Concealed soil and TV pipes and gas flues only allowed in ducts or minimum framed	38	✓	Window sashes on upper levels less than 760mm above floor to have stays fixed
✓ Pre-lining (Plumbing)						
Wet areas - membrane	12	✓	Hot & Cold water pipes tested to 1500kPa	39		Construction of playground to comply with NZS5828
✓ Post Lining						
Brick Veneer	13		Roof stormwater to be connected to existing	40		Fencing, gates, doors directly leading to swimming pool to comply with Pool Act 1987
Retaining Wall						
✓ Final (Dwelling)	14		Copper water pipes not permitted	43	✓	Textured systems should be applied by licensed, trained applicators – supply warranty
Final (Commercial & Multi-resd)						
	15		Owner/builder to ensure prop foundation height will allow satisfactory connection	44	✓	Exterior cladding system to be completed and inspected prior to internal lining
	21	✓	Minimum FFL to comply with NZS3604			

STANDARD CONSENT CONDITIONS		
37		
72		
80		

NON-STANDARD ADDENDA

FOR OFFICE USE ONLY

FEES		APPLICATION FEE \$.....
Building Fee	\$ 3350.00	\$4277.00
Sewer Connection	\$.....	RECEIPT NO DATE.....
Water Connection	\$.....	
Vehicle Crossing	\$.....	INVOICE NO DATE.....
Damage Deposit	\$.....	78491 1/04/09.
Code Compliance Administration	\$.....	RECEIPT NO 294927 DATE.....
Building Research Levy	\$.....	294880 1/04/09.
Development Levy	\$.....	FEES PAID BY:
DBH Levy	\$.....	Roulston Family Trust
Compliance Schedule	\$.....	
Digital Storage Fee	\$ 36.00	BUILDING CONSENT , DATE ISSUED
Certificate of Title Charge	\$.....	NUMBER
Photocopying	\$.....	090214 1/04/09.
SUBTOTAL	\$.....	AUTHORISATION FOR REFUND OF DEPOSIT
Less Fee Paid	\$.....	Deposit held = \$.....
TOTAL	\$4277.00	Cost to Repair Damage Caused During Construction = \$.....
GST INCLUDED	\$.....	Total Balance to be Refunded
		Authority Number:
		Authorised: DATE:


GST 51-860-608

Received with thanks by 10/01
KAPITI COAST DISTRICT COUNCIL

1-04-09 13:20 Receipt no.294927

COPY *COPY* *COPY*

DR BC090214 4,277.00-
ARCHITECTURE DM
Architecture DM::17 Gear Street:PETONE:
GL 99742999 Roulston T 455.00-
CQ W
Roulston Family Trus 4,732.00



Building consent 090214

Section 51, Building Act 2004

The building

Street address of building: 125 Nikau Palm Road, Paraparaumu

Legal description of land where building is located: LOT 4 DP 82049

Valuation number: 1515007804

Building name:

Location of building within site/block number:

Level/unit number:

The owner

Name of owner: Tom Roulston

Contact person:

Mailing address: 28 Stellin Street, Avalon, LOWER HUTT

Street address/registered office:

Phone number: Landline:

Mobile: 0212441643

Daytime:

After hours:

Facsimile number:

Email address: tom@dvcs.co.nz

Website:

First point of contact for communications with the council/building consent authority:

Full Name: Architecture DM

Mailing Address: 17 Gear Street, PETONE

Phones: 04 5688468

Fax: 04 5688468

Building work

The following building work is authorised by this building consent:

Excavation of site & construction of New Dwelling

Rural Dwelling

This building consent is issued under section 51 of the Building Act 2004. This building consent does not relieve the owner of the building (or proposed building) of any duty or responsibility under any other Act relating to or affecting the building (or proposed building).

This building consent also does not permit the construction, alteration, demolition, or removal of the building (or proposed building) if that construction, alteration, demolition, or removal would be in breach of any other Act.

Compliance schedule

A compliance schedule is not required for the building.

Attachments

Copies of the following documents are attached to this building consent:

David Kevane

Signature

Customer Services

Position

On behalf of: KAPITI COAST DISTRICT COUNCIL

Date: 12/05/09

12 May 2009

Tom Roulston
28 Stellin Street
Avalon
LOWER HUTT

Dear Sir/Madam

Approval of Building Consent: 090214

Description: Excavation of site & construction of New Dwelling
Location: 125 Nikau Palm Road, Paraparaumu
Legal Description: LOT 4 DP 82049

I am pleased to inform you that the above building consent application has been approved. The building consent documents have been issued and are enclosed.

Before starting any work please read ALL the building consent documents carefully and in full so that you as the owner understand the conditions under which the consent has been issued.

As the owner you are also responsible for the following:

- ensuring that building work starts within 12 months of the approval of the building consent and that work progresses at a reasonable pace.
- ensuring that all required inspections are completed and that a Code Compliance Certificate is obtained once the work has been completed – please be aware that before a Code Compliance Certificate is issued, the building work must comply with the Building Act 2004 and the Building Code as at the date of final inspection.
- that no work with noisy equipment is to be carried out before 7.30 a.m. or after 6 p.m. Monday to Saturday. During the week there may be workers on site from 6.30 a.m. quietly preparing for work. Work with noisy equipment is not permitted on Sundays and public holidays.
- ensuring that no damage occurs to public property, for example footpaths or retaining structures. Should damage occur you will be required to pay for any repairs.
- ensuring that if you wish to make any changes to the approved building consent, then an amendment to the building consent will need to be lodged with us.

If you have any questions regarding your building consent or your responsibilities, please contact Kapiti Coast District Council on (04) 9045 617.

Addenda to Application

Application

Architecture DM
17 Gear Street
PETONE

No.

090214

Project

Description	New (& prebuilt) House, Unit, Bach, Crib, Town House etc. Being Stage 1 of an intended 1 Stages Excavation of site & construction of New Dwelling
Intended Life	Indefinite, but not less than 50 years
Intended Use	Rural Dwelling
Estimated Value	\$300,000
Location	125 Nikau Palm Road, Paraparaumu
Legal Description	LOT 4 DP 82049
Valuation No.	1515007804

Designer: Architecture DM 17 Gear Street, Petone : 04 568 8468

Contractor: ISP Consulting Engineers Level 1, 14 Lainos Rd, Lower Hutt

General Requirements

- a) The District Inspector is to be given 24 hours' notice before carrying out the following inspections:
1. Foundations
 2. Block
 3. Pre-slab
 4. Pre-slab
 5. Drainage
 6. Pre Wrap
 7. Pre Clad
 8. Weathertightness
 9. Preline
 10. Preline
 11. Postline
 12. Final Inspection
- b) To arrange for any of the above required inspections by Building Control Team, please contact the Call Centre on (04) 296 4700 between the hours of 7.30am and 5.30pm.

1. LAPSE AND CANCELLATION OF BUILDING CONSENT. A building consent shall lapse and be of no effect if the building work concerned has not been commenced within 12 calendar months after the date of issue. Or within such further period as the territorial authority allows.
2. The inspection of all specific design components of the building is the responsibility of the Design Engineer who is also required to supply a written report to Council.
3. All foundations are to be to solid bearing minimum of 300mm
4. Note and comply with endorsements on approved plans.
5. Names and registration numbers of plumber and drainlayer are required before work commences.
6. Concealed soil and TV pipes and gas flues are only permitted built into ducts or minimum 150mm framed walls or with the Phillips top plate connecting bracket.
7. Both hot and cold water pipes are to be tested to 1500 KPA pressure.
8. Minimum heights of finished concrete slab-on-ground floors above adjoining finished ground level to comply with the current NZS3604.
9. Seismic restraint to be provided to appliance and flue as per the manufacturer's recommendations, NZBC, C.1 and Acceptable Solutions 9.1.2 and 9.2.2
10. Contractor to leave site clear of all demolition materials and in a tidy state.
11. Restrictor stays, limiting sash opening to max 100mm must be fitted wherever sill height is less than 760mm and the difference in levels are 1 metre or greater. Refer F4.NZBC
12. Textured Systems should be applied by licensed, trained applicators only. Supply copy of warranty to Certifier.
13. Exterior cladding system to be previously completed and inspected by Council's Inspector prior to any subsequent prelining inspection/approval being granted for the fixing of internal linings.

I have read the foregoing addenda to application, and the Owner/Builder/Authorised Person hereby agrees to comply with them.

**OWNER/BUILDER/
AUTHORISED PERSON**

Date:



ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

COVER PAGE

01

DATE: 26 MAR 2009

SCALE: @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC



Sheet Number	Sheet Name
01	COVER PAGE
02	SITE PLAN
03	FOUNDATION & DRAINAGE PLAN
04	LOWER FLOOR PLAN
05	UPPER FLOORING PLAN
06	UPPER FLOOR PLAN
07	BRACING PLANS
08	SECTIONS
09	SECTIONS
10	ROOF FRAMING PLAN
11	ROOFING PLAN

Sheet Number	Sheet Name
12	ELEVATIONS
13	ELEVATIONS
14	CONSTRUCTION DETAILS
15	CONSTRUCTION DETAILS
16	CONSTRUCTION DETAILS
17	CONSTRUCTION DETAILS
18	CONSTRUCTION DETAILS
19	CONSTRUCTION DETAILS
20	CONSTRUCTION DETAILS
21	DOOR SCHEDULE
22	WINDOW SCHEDULE



125 NIKAU PALM ROAD
PARAPARAUMU

Rev: Description: Date:

Check and confirm all dimensions prior to commencing any work on-site.

If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.


Any conflicts on the documents are to be notified to the designer prior to commencing work.

LOWER FLOOR PLAN

DESIGN BY: Designer

© ARCHITECTURE DM LTD

A D | N Z
ARCHITECTURAL DESIGNERS NZ INC



ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

UPPER FLOORING PLAN

05

DATE: 26 MAR 2009
SCALE: As indicated @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE


P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD


A D N Z

ARCHITECTURAL DESIGNERS NZ INC



LEVEL 2 SLAB TO FOUNDATION WALL DETAIL


1:20



CONCRETE SLAB FOOTING DETAIL

1:20

NOTE: All beams are engineered design - please refer to engineers documentation for all calculations and connection/fixing details



LEVEL 2 FLOORING PLAN

1:100

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

UPPER FLOOR PLAN

06

DATE: 26 MAR 2009
SCALE: 1:100 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE


P (04) 568 8468
F (04) 568 8468
M 027 452 4670


E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD


A D N Z

ARCHITECTURAL DESIGNERS NZ INC





LEVEL 1 BRACING PLAN
1:100



LEVEL 2 BRACING PLAN
1:100

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev:	Description:	Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

BRACING PLANS

07

DATE:	26 MAR 2009
SCALE:	1:100 @A3
JOB NUMBER:	NA
DRAWN BY:	S JOHNSON
DESIGN BY:	Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

SECTIONS

08

DATE: 26 MAR 2009
SCALE: 1:100 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670
E dean@architecturedm.co.nz
© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC

Corrugated profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900ctrs over PS40-40x09 Posi-STRUT MSG8 roof trusses @ 600ctrs with R3.6 insulation

PS40-60X05 Posi-STRUT MSG8 floor truss System @ 400ctrs as per MiTek specification

BEAM 8 - 2/290x45 MSG8 above

BEAM 11 - 125x6 SHS

SIKA 'RainTite' waterproof deck liquid membrane on 17mm H3.2 construction ply packed to a 1.5° fall (to each gutter) on H3.2 packers @ 400ctrs on 240x45 MSG8 joists @ 400ctrs

Arena 'Vetro' glass balustrade with 10mm grade 'A' safety glass & aluminium balusters @ 900max ctrs for high wind

CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on 90x45 MSG8 H1.2 framing @ 400 ctrs

Section 1

1:100

Corrugated profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900ctrs over 90x45 MSG8 trusses @ 900ctrs with R3.6 insulation

4.5mm Hardiflex soffit lining

Approved truss design

LIVING

DINING

BEDROOM

WIR

Double glazed powdercoated aluminium joinery

Plaster finish over EIFS cladding over 20mm drained cavity and Thermakraft Diflex 130 building wrap on 90x45 MSG8 H1.2 framing @ 400ctrs with R2.6 insulation

140x45 MSG8 H3.2 bearers on 125x125 H5 anchor piles in 350x350x900 conc pad

25 series reinforced concrete block retaining wall with control joints @ 6.0m ctrs

Engineered retaining wall footing detail

100mm 25MPA concrete slab @ 28 days with 665 mesh over 0.25 polythene on 50mm sand blinding on min 100mm compacted basecourse - 40mm R1.3 EPS insulation under slab

Standard 13mm GIB to all interior ceilings on Rondo steel system @450ctrs (Ultraline to diaphragms)

10mm Grade 'A' 1000mm high safety glass balustrade

Stair calculation
3200/17 = 188mm risers
280mm max tread depth

GARAGE

BEAM 1 - 310UB 46.2

LEVEL 1

Section 1

1:100

Corrugated profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900ctrs over 90x45 MSG8 trusses @ 900ctrs with R3.6 insulation

Corrugated profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900ctrs over PS40-40x09 Posi-STRUT MSG8 roof trusses @ 600ctrs with R3.6 insulation

Plaster finish over EIFS cladding over 20mm drained cavity and Thermakraft Diflex 130 building wrap on 140x45 MSG8 H1.2 framing @ 400ctrs with R2.6 insulation

PS40-60X05 Posi-STRUT MSG8 floor truss System @ 400ctrs as per MiTek specification

25 series reinforced concrete block retaining wall with control joints @ 6.0m ctrs

100mm 25MPA concrete slab @ 28 days with 665 mesh over 0.25 polythene on 50mm sand blinding on min 100mm compacted basecourse - 40mm R1.3 EPS insulation under slab

Coredrain as per manufacturers specifications

Standard 13mm GIB to all interior ceilings on Rondo steel system @450ctrs (Ultraline to diaphragms)

Butynol membrane roofing on 17mm H3.2 plywood over packed to a 1.5° fall on H3.2 packers @ 400ctrs on 140x45 MSG8 rafters @ 600 max ctrs

6mm Hardiflex lining fixed to 140x45 outriggers

Double glazed powdercoated aluminium joinery

Arena 'Vetro' glass balustrade with 10mm grade 'A' safety glass & aluminium balusters @ 900max ctrs for high wind

SIKA 'RainTite' waterproof deck liquid membrane on 17mm H3.2 construction ply packed to a 1.5° fall (to each gutter) on H3.2 packers @ 400ctrs on 140x45 MSG8 joists @ 400ctrs

CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on 90x45 MSG8 H1.2 framing @ 400 ctrs

BEAM 9 - 180PFC above

BEAM 11 - 125x6 SHS

10mm Grade 'A' 1000mm high safety glass balustrade

LIVING/DINING

GARAGE

BEAM 2A - 300 PFC
Lintel 1 = 2/290x45 MSG8

Section 2

1:100

NOTE: All beams are engineered design - please refer to engineers documentation for all calculations and connection/fixing details

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

SECTIONS

09

DATE: 26 MAR 2009
SCALE: 1:100 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468


F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz


© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC



Section 3

1:100



Section 4

1:100

NOTE: All beams are engineered design - please refer to engineers documentation for all calculations and connection/fixing details

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

ROOF FRAMING PLAN

10

DATE: 26 MAR 2009
SCALE: NTS @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE


P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC

NOTE: Please see attached truss layout producer statement



PRELIMINARY TRUSS LAYOUT & FIXING SCHEDULE

NOTE: All trusses have been designed utilizing the ground beams, load bearing walls, and sub floor beams as per the plans and information supplied. Highlighted additional structural platforms may be required and will be introduced at our discretion to enable a successful truss design.

IMPORTANT NOTE : A bottom chord restraint (runner) is required, fixed to the top of the bottom chord of the truss, spaced no greater than 1800mm centres, in the absence of 70x35 timber battens, or when using the metal Rondo system.

This Prelim Layout has been based on the limited set of drawings supplied.

TRUSS TIEDOWN LEGEND:

"Z" - 2/ Z nails
M/G - 2/ Multigrips (1/ each side of truss)
WS4 - 1/ WS4 Windstrap
CS6(wr) - ends of CS6 folded and nailed under top plate
CS6 - 1/ CS6 Cyclone strap
N.O.A. - 2/ Nail On Angles
NOTE: Remaining trusses without fixings, require a minimum of 2 skew nails.

ROOF FRAMING PLAN

NTS

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

ROOFING PLAN

11

DATE: 26 MAR 2009

SCALE: 1 : 100 @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM LTD

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

Custom Orb profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900crs over PS40-40x09 Posi-STRUT MSG8 roof trusses @ 600ctrs

Custom Orb profile Colorsteel roofing over Thermakraft 215 self supporting underlay over 70x45 purlins @ 900crs over 90x45 MSG8 trusses @ 900ctrs

25x1 Galv strap roof plane bracing with tensioners as per NZS3604:1999

SIKA 'RainTite' waterproof deck liquid membrane on 17mm H3.2 construction ply packed to a 1.5° fall (to each gutter) on H3.2 packers @ 400crs on 140x45 MSG8 joists @ 400ctrs

25x1 Galv strap roof plane bracing with tensioners as per NZS3604:1999

Butynol membrane roofing on 17mm H3.2 plywood over packed to a 1.5° fall on H3.2 packers @ 400crs on on H3.1 140x45 MSG8 rafters @ 600 max ctrs

New Roof:
Steel & Tube Colorsteel Corrugated Profile Endura 0.4mm BMT Roofing. Thermakraft 215 self supporting kraft paper type building underlay.

Roofing fixed to purlins with 12g x 50mm TEK screws as defined by manufacturers recommended fixing pattern for high wind.

New continuous spouting fixed to H3.1 cedar fascia.

Roof to comply with NZBC E2/AS1 Section 8.4 Profiled Metal Roof Cladding

Fix purlins to rafters with the following MiTek fixings for very high wind:

Use Type D 2.70kN fixings on Main & Periphery Roof Areas = Two 90 x 3.15 PD Nails + One Lumberlok Wire Dog or Two Lumberlok Blue Screws

Downpipes are to comply with E1/AS1. Table 5

DP1 = 100mm dia (64.5m2 roof area @ 8° max)
DP2 = 100mm dia (93.4m2 roof area @ 8° max)
DP3 = 100mm dia (54.5m2 roof area @ 12° max)
DP4 = 100mm dia (54.5m2 roof area @ 12° max)
DP5 = 65mm dia (20.4m2 roof area @ 1.5° max)
DP6 = 65mm dia (44.4m2 deck area @ 1.5° max)
DP7 = 65mm dia (22.0m2 deck area @ 1.5° max)

ROOFING PLAN

1 : 100

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

ELEVATIONS

12

DATE: 26 MAR 2009
SCALE: 1:100 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC

Colorsteel Custom Orb roofing

Butynol Membrane flat roofing

Double glazed aluminium joinery


LEVEL 2
3200

SPTV

Plaster finish over EIFS cladding on a drained cavity

WEST ELEVATION

1:100



SOUTH ELEVATION

1:100

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

ELEVATIONS

13

DATE: 26 MAR 2009

SCALE: 1 : 100 @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD


A D N Z

ARCHITECTURAL DESIGNERS NZ INC



NORTH ELEVATION

1 : 100



EAST ELEVATION

1 : 100



ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date: Site:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

CONSTRUCTION DETAILS

15

DATE: 26 MAR 2009

SCALE: 1:2 @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468


M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD


A D N Z

ARCHITECTURAL DESIGNERS NZ INC




HEAD DETAIL


NOTE:
Sill sealing method for flange
end type drainage systems



Continuous seal
Keep drainage
passage clear



SILL DETAIL




JAMB DETAIL

PLASTER WINDOW DETAILS


1:2

CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on timber framing.




SCHIST EXTERNAL CORNER DETAIL

CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on timber framing.



SCHIST INTERNAL CORNER DETAIL


CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on timber framing.



SCHIST CLADDING FOUNDATION DETAIL

CLADDING DETAILS


1:5




CLADDING JUNCTION DETAIL

Plaster render on 40mm EIFS cladding on 20mm H3.1 cavity battens fixed vertically on Thermakraft Diflex 130 building wrap on timber framing.


CraftStone exterior schist veneer cladding on Flexco Megamortar binding additive and primer on 6mm fibre cement backing sheet fixed on H3.1 Ex 45x20 cavity battens on Thermakraft Diflex 130 building wrap on timber framing.



EIFS EXTERNAL CORNER DETAIL



EIFS INTERNAL CORNER DETAIL



EIFS CLADDING FOUNDATION DETAIL

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

CONSTRUCTION DETAILS

17

DATE: 26 MAR 2009
SCALE: 1:5 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM


17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD



A D N Z
ARCHITECTURAL DESIGNERS NZ INC



(as shown in E2/AS1 fig.50)




HIDDEN GUTTER DETAIL

1:10



BARGE DETAILS

1:10



EAVE DETAILS

1:10

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

CONSTRUCTION DETAILS

18

DATE: 26 MAR 2009
SCALE: 1:10 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM


17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz


© ARCHITECTURE DM LTD

A D N Z
ARCHITECTURAL DESIGNERS NZ INC



MEMBRANE ROOF DETAIL

1:10



MEMBRANE DECK DETAIL

1:10

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

CONSTRUCTION DETAILS

19

DATE: 26 MAR 2009
SCALE: 1:10 @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz


© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC


TYPICAL FIXINGS:

EXT. BOTTOM PLATE TO SLAB: M12 RAGBOLTS @ 1200CRS. PLACE D.P.C UNDER PLATES.
TOP PLATE TO STUD: 2- 100 x 3.75 SKEWED NAILS AND 3 WIRE DOGS, OR 6.7kN ALTERNATE FIXING.
TRUSS TO TOP PLATE: 16kN "LUMBERLOK TRUSS TO TOP PLATE FIXING."
75 x 50 PURLINS TO TRUSSES: 2- 100 x 3.75mm NAILS AND EITHER OF 1 WIRE DOG OR 1- 100mm x 14g TYPE 17 SCREW TO AS 3566. TO MAIN ROOF AREAS
AND
2-100 x 3.75mm SKEWED NAILS EITHER OF 2 WIRE DOG OR 2- 100mm x 14g TYPE 17 SCREW TO AS 3566, TO PERIPHERY OF ROOF, AS SHOWN IN FIG. 10.16, NZS. 3604, 1999.



LINTEL FIXING DETAIL

NTS



ROOF PENETRATION DETAIL

NTS

ROULSTON RESIDENCE

125 NIKAU PALM ROAD
PARAPARAUMU

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.
Use stated dimensions in preference to scaled.
If in doubt ASK.
Drawings at a larger scale take precedence over those drawn at a smaller scale.
Site measure all openings/spaces for items manufactured off-site.
Notes on one plan and not necessarily on other drawings are applicable to all drawings.
Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

CONSTRUCTION DETAILS

20

DATE: 26 MAR 2009
SCALE: As indicated @A3
JOB NUMBER: NA
DRAWN BY: S JOHNSON
DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468
F (04) 568 8468
M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC.

REVISIONS:

Rev: Description: Date:

GENERAL NOTES:

Check and confirm all dimensions prior to commencing any work on-site.

Use stated dimensions in preference to scaled.

If in doubt ASK.

Drawings at a larger scale take precedence over those drawn at a smaller scale.

Site measure all openings/spaces for items manufactured off-site.

Notes on one plan and not necessarily on other drawings are applicable to all drawings.

Any conflicts on the documents are to be notified to the designer prior to commencing work.

IF IT ISN'T DIMENSIONED - DO NOT SCALE

WINDOW SCHEDULE

22

DATE: 26 MAR 2009

SCALE: 1 : 50 @A3

JOB NUMBER: NA

DRAWN BY: S JOHNSON

DESIGN BY: Designer

ARCHITECTURE DM

17 GEAR ST
PETONE

P (04) 568 8468

F (04) 568 8468

M 027 452 4670

E dean@architecturedm.co.nz

© ARCHITECTURE DM LTD

A D N Z

ARCHITECTURAL DESIGNERS NZ INC


2/190X45 MSG8 LINTELS

2/140X45 MSG8 LINTELS

2/240X45 MSG8 LINTELS

ENGINEERED LINTEL

ENGINEERED LINTEL




2/90X45 MSG8 LINTELS

2/190X45 MSG8 LINTELS

2/90X45 MSG8 LINTELS


2/190X45 MSG8 LINTELS

ENGINEERED LINTEL



WINDOW SCHEDULE

1 : 50



125x6 SHS
(COL 6)

125x6 SHS (BM 12)
2/290x45 MSG8 (BM 8) ABOVE

125x6 SHS (BM 11)
180PFC (BM 9) ABOVE


2/290x45 MSG8 (BM 10)

2/90x45

2/90x45

125x6 SHS
(COL 7)

SCALE 1:100



CBS

240y45 MSG8 - 400

310UB46 (BM 1)

- OUTLINE OF
WALL ABOVE

250PFC (BM 2)

300 PFC (BM 2a)

2/90x45

180 PFC (BM 7)

2/90x45

180PFC (BM 5)

90x45

2/90x45

2/240x45
(BM 3a)

2/90x45

2/290x45
(LINTEL 1)

200 PFC (LINTEL 2)

2/22/15

2/290x45
(BM6)



2/22/15


SCALE 1:100

8. ENGINEER TO INSPECT ALL STEEL CONNECTIONS PRIOR TO CLOSING IN. ENGINEER REQUIRES 24 HOURS NOTICE BEFORE ANY VISIT.


CLIENT ROULSTON RESIDENCE

PROJECT NIKAU PALM RD
PARAPARARIMU

DATE	11/3/09	DWG No.	S2
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040




25 SERIES BLOCK RETAINING WALL
 UP TO 3.2m MAXIMUM RETAINED
 SCALE 1:20




20 SERIES BLOCK WALL
 FOOTING DETAIL
 SCALE 1:20


CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S3
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040



BEAM 1 TO BLOCK WALL
CONNECTION DETAIL




CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S4
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040



BEAM 2a TO FLOOR JOIST
CONNECTION DETAIL
 SCALE 1:10

CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S5
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040




ELEVATION


BEAM 1 TO BEAM 2
CONNECTION DETAIL

SCALE 1:10


CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S7
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040



PLAN VIEW




SECTION A




ELEVATION

**BEAM 2 & COLUMN 6 TO WALL
CONNECTION DETAILS**




**BEAM 3b TO WALL
CONNECTION DETAIL**

SCALE 1:10



ELEVATION




VIEW A


**BEAM 2 TO BEAM 3
CONNECTION DETAIL**

SCALE 1:10

CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S8
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040




PLAN VIEW




ELEVATION

**BEAM 5 TO WALL
 CONNECTION DETAIL**
 SCALE 1:10




ELEVATION

**BEAM 2a TO BEAM 5 & WALL
 CONNECTION DETAIL**
 SCALE 1:10




PLAN VIEW




SECTION A


CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S9
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040




**LINTEL 2 TO WALL
 CONNECTION DETAIL**
 SCALE 1:10




**BEAM 4 TO WALL
 CONNECTION DETAIL**
 SCALE 1:10




**BEAM 5 TO DECK JOISTS
 CONNECTION DETAIL**
 SCALE 1:10



**BEAM 4 TO BLOCK WALL & JOISTS
 CONNECTION DETAIL**
 SCALE 1:10




**BEAM 7 TO WALL
 CONNECTION DETAIL**
 SCALE 1:10




SECTION A

CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S10
SCALE	AS SHOWN	JOB No	23040
DRAWN	GSH		



**BEAM 8 & BEAM 9 TO COLUMN 6
CONNECTION DETAIL**

SCALE 1:10



**BEAM 11 & BEAM 12 TO COLUMN 6
CONNECTION DETAIL**

SCALE 1:10

NOTE:

- FOR COLUMN 6 BASE PLATE
DETAILS REFER DRG S8
- FOR COLUMN 7 BASE PLATE
DETAILS REFER DRG S6
- BEAM 9 & BEAM 11 TO COLUMN
7 CONNECTION SIMILAR

CLIENT	ROULSTON RESIDENCE		
PROJECT	NIKAU PALM RD PARAPARARIMU		
DATE	11/3/09	DWG No.	S11
SCALE	AS SHOWN		
DRAWN	GSH	JOB No	23040

PRODUCER STATEMENT - PS1 - DESIGN
(Guidance notes on the use of this form are printed on the reverse side*)

ISSUED: ISP Consulting Engineers Ltd

TO: **Tom Roulston**
(Owner / Developer)TO BE SUPPLIED TO: **Hutt City Council**
(Building Consent Authority)IN RESPECT OF: **Engineering Calculations**
(Description of Building Work)AT:
(Address)

LOT.....DP.....

We have been engaged by the owner/developer referred to above to provide **structural design services and construction monitoring of specifically design elements** in respect of the requirements of Clause B1 (B2 of specifically designed elements) of the building code for

☐ All

Part only as specified of building work outside NZS3604 scope:
-Scala penetrometer tests
-Foundation design calculations and construction details outside
-Structural beam design calculations and connection details
-Reinforced masonry retaining wall design and construction details.

The design carried out by us has been prepared in accordance with Compliance Documents issued by Department of Building & Housing B1, VM1 & VM4

The proposed Building work covered by this producer statement is described on the drawings and Calculations titled ...125 Nikau Palm ...and numbered ...SK1-SK11 and pages 1 - 72.

On behalf of the Design Firm, and subject to:

- (i) Site verification of the following design assumptions: Bearing capacity of excavated foundations to satisfy the requirements of NZS3604:1999 and to be confirmed on site by an engineer.
- (ii) All proprietary products meeting their performance specifications requirements;

I **Believe on reasonable grounds** the building, if constructed in accordance with the drawings, specifications, and other documents provided will comply with the relevant provisions of the building code.

I, John O'Hagan am CPEng #179947


I am a member of: IPENZ and hold the following qualifications: BE(Hons), NZCE(Civil), MIPENZ, CPEng

The design firm issuing this statement holds a current policy of Professional Indemnity Insurance no less than \$ 500,000*.

The Design Firm is a member of ACENZ

SIGNED BY John O'Hagan ON BEHALF OF ISP Consulting Engineers Ltd

Date: 12 March 2009

(Signature).....

Note: this statement shall only be relied upon by the Building Consent Authority named above. Liability under this statement accrues to the Design Firm only. The total maximum amount of damages payable arising from this statement and all other statements provide to the Building Consent Authority in relation to this building work, whether in contract, tort or otherwise (including negligence), is limited to the sum of \$200,000*.
This form is to accompany Form 2 of the Building (Forms) Regulations 2004 for the application of a Building Consent.

**SPECIFIERS GUIDE**

PAGE 2.26.1

ISSUE NO. 03

PRODUCER STATEMENT - DESIGN

TO: WHOM IT MAY CONCERN

IN RESPECT OF: THE ARENA BALUSTRADING SYSTEM

STYLE: ARENA VETRO / DKG BRACKET FIX

as supplied by Unex Systems, the design of the balustrading system has been prepared in accordance with the approved documents issued by the Building Industry Authority; and with reference to AS/NZS 1664 Aluminium Structures Standard; and where applicable the established principles of structural design. The design of the load carrying members and their connections have been verified by load testing where applicable.

I BELIEVE ON REASONABLE GROUNDS that subject to all proprietary products (aluminium, fixings etc.) meeting their performance specifications requirements, and the general arrangement, post spacings and fixings are in accordance with the current Arena Fabricators Manual, the design of the balustrade complies with Section B1 Structures of the New Zealand Building Code.

This statement covers the design of the balustrade and its immediate fixings to the structure, but excludes the design of the supporting structure.


Signature: 

Date: 19/12/03

A.H. Thomas Registered Engineer No 3058

Site Address: 125 NIKAU PALM ROAD PARAPARAUMU

Name of Fabricator: ALTEC GROUP LIMITED

Signature of Fabricator: 

Date of Supply: TBA


THIS STATEMENT MUST BE COMPLETELY FILLED IN TO BE VALID

'VETRO' - STYLE SPECIFICATION 3.151.1

This specification details the members to be used, glass thicknesses required and the maximum spacing for the various posts for this style. A separate specification must be referred to for fixing to the substrate (refer to Chapter 4). Post spacing must not exceed the lesser of the spacing from both Chapter 3 and Chapter 4.

NOTE: For the Vetro Style we recommend always using 4 Substrate fixings per baseplate to give lateral stability to the post, even if 2 fixings is structurally adequate.

- (1) Glass shall be GRADE A SAFETY GLASS, TOUGHENED in accordance with AS/NZS 2208, with a minimum thickness as determined from the Table below. Glass shall be supported and glazed in accordance with NZS 4223. All exposed edges to be Flat Polished.
- (2) Fabrication and Installation to be in accordance with ASSEMBLY SPECIFICATION 5.161.1, the INSTALLATION INSTRUCTIONS in Chapter 9, and all other relevant portions of the ARENA FABRICATORS MANUAL.
- (3) APR2 posts should only be used for "top Fixed" situations. APS and APE may be used for "top fixed" or "side fixed" situations.



MAXIMUM POST CENTRES 'S max' (metres) ALWAYS TAKE THE LESSER OF THE VALUE BELOW AND THE VALUE FROM THE FIXING SPECIFICATION																			
HEIGHT (Note 3)	Post Type (Note 2)	Toughened Glass Thickness	Line No.	LOADING CLASS (Note 1)															
				A1								R							
				Design Wind Speed (Note 4)								Design Wind Speed (Note 4)							
				50	52	54	56	58	60	62	64	N/A	M 38	40	H 42	44	46	VH 48	50
1.0	APR2 or APS	8	1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10
		10	2	1.19	1.19	1.19	1.19	1.11	1.04	0.97	0.91	1.50	1.50	1.50	1.50	1.50	1.50	1.49	1.38
		12	3	1.19	1.19	1.19	1.19	1.11	1.04	0.97	0.91	1.80	1.80	1.80	1.80	1.76	1.62	1.49	1.38
	APE	12	4	1.39	1.39	1.39	1.38	1.29	1.20	1.13	1.06	1.80	1.80	1.80	1.80	1.80	1.80	1.74	1.60
		15	5	1.39	1.39	1.39	1.38	1.29	1.20	1.13	1.06	2.40	2.40	2.40	2.40	2.24	2.05	1.88	1.74
1.1	APR2 or APS	8	6	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.06
		10	7	1.08	1.08	1.06	0.98	0.91	0.85	0.80	0.75	1.50	1.50	1.50	1.50	1.45	1.34	1.23	1.14
		12	8	1.08	1.08	1.06	0.98	0.91	0.85	0.80	0.75	1.80	1.80	1.80	1.75	1.59	1.45	1.34	1.23
	APE	12	9	1.26	1.26	1.23	1.14	1.06	1.00	0.93	0.88	1.80	1.80	1.80	1.80	1.70	1.56	1.44	1.32
		15	10	1.26	1.26	1.23	1.14	1.06	1.00	0.93	0.88	2.40	2.40	2.24	2.04	1.85	1.70	1.56	1.44
1.2	APR2 or APS	8	11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.10	1.10	1.10	1.10	1.10	1.10	1.04	0.96
		10	12	0.97	0.96	0.89	0.82	0.77	0.72	0.67	0.63	1.50	1.50	1.50	1.47	1.34	1.22	1.12	1.04
		12	13	0.97	0.96	0.89	0.82	0.77	0.72	0.67	0.63	1.80	1.79	1.62	1.47	1.34	1.22	1.12	1.04
	APE	12	14	1.16	1.11	1.03	0.96	0.90	0.84	0.78	0.74	1.80	1.80	1.80	1.71	1.56	1.42	1.31	1.20
		15	15	1.16	1.11	1.03	0.96	0.90	0.84	0.78	0.74	2.40	2.09	1.88	1.71	1.56	1.42	1.31	1.20

(1) LOADING CLASS: Refer to Page 2.9.3 of this MANUAL for the scope of the Loading Class designations.

(2) POST TYPES: Refer to Chapter 1 for details.

(3) HEIGHT 'H': is the overall height of the balustrade above the substrate level shown. Interpolate for Heights between those shown.

(4) DESIGN WIND SPEED: in m/s. Refer to Pages 3.8.1 to 3.8.6 for details of applicable wind codes and the methods for determining the Design Wind Speed for any particular site.

GLASS THICKNESS REQUIREMENTS

The following is a summary of the requirements of NZS 4223 in its current edition, as it relates to the use of Toughened Glass in Arena proprietary balustrades. NZS 4223 should be referred to for a full guide, and for subsequent amendments. Arena Balustrades are not designed for use with laminated glass.

TABLE 1 - MAXIMUM GLASS HEIGHT (mm) FOR DIFFERENT TOUGHENED GLASS THICKNESSES FOR THE ARENA 'PANORAMA' AND 'METROPOLIS' STYLES

NOTE: post spacing must not exceed the given style and fixing specifications see Chapters 3 & 4

LOADING CLASS	GLASS THICKNESS mm	DESIGN WIND SPEED															
		40	42	44	46	48	50	52	54	56	58	60	62	64	66	68	70
A1	10	670	670	670	670	670	670	670	670	670	670	670	670	670	670	670	670
	12	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1010	990	960
	15	1280	1280	1280	1280	1280	1280	1280	1280	1280	1280	1270	1250	1230	1220	1180	1150
A2	10	670	670	670	670	670	670	670	670	670	670	670	670	670	670	670	670
	12	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1030	1010	990	960
	15	1380	1380	1380	1380	1380	1380	1370	1340	1320	1300	1270	1250	1230	1220	1180	1150
R	8	800	800	800	800	800	800	800	800	800	800	780	760	720	710	690	680
	10	1000	1000	1000	1000	1000	1000	1000	990	970	960	940	920	890	860	840	820
	12	1200	1200	1200	1200	1200	1180	1160	1140	1120	1100	1080	1060	1040	1010	990	960
	15	1500	1500	1490	1460	1430	1400	1370	1340	1320	1300	1270	1250	1230	1220	1180	1150

TABLE 2 - MAXIMUM POST SPACING (MITRES) FOR DIFFERENT TOUGHENED GLASS THICKNESSES FOR THE ARENA 'VETRO' STYLE


NOTE: post spacing must not exceed the given style and fixing specifications see Chapters 3 & 4

LOADING CLASS	GLASS THICKNESS mm	DESIGN WIND SPEED															
		40	42	44	46	48	50	52	54	56	58	60	62	64	66	68	70
A1	10	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20	1.20
	12	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50
	15	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.00
A2	8	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10
	10	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.48
	12	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.77
	15	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.35	2.30	2.25	2.18
R	8	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10	1.10
	10	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.50	1.48
	12	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.80	1.77
	15	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.40	2.35	2.30	2.25	2.18

Specifications subject to change without notice

DRY TIMBER DKG2 FIXING, SCREWS 90mm EDGE JOIST - SPECIFICATION 4.17.9

This specification for fixing ALUMA BALUSTRADES to certain timber substrates where a face gutter is also required. It applies to balustrade styles using VPH2 or DPE posts only. A separate specification must be referred to for the required balustrade style.



- (1) The DKG2-014 brackets are required to be installed before the gutter and drip edge.
- (2) The VPH2 or DPE balustrade posts are attached to the BSMF or BEMF baseplate as illustrated on page 7.3.1 of chapter 7. The baseplate is attached to the DKG2-014 bracket using four stainless steel M8 bolts, nuts and washers. The DKG2-014 bracket attaches to the structural timber using four M8 x 165mm stainless steel coach screws as illustrated. There must be a polymer FWP8-22G washer between the stainless steel washers and the aluminium componentry. Insert a thin Neoprene gaskets between the DKG2 bracket and the substrate to enhance water-proofing. Fasteners should be only those supplied by Unex Systems.
- (3) The threaded portion of the coach screws must be engaged with the structural timber framing by a minimum of 90mm. This will obtain if the dimension 'F' on the diagram (i.e. the distance from the back of the bracket to the face of the timber joist) is within the limits shown in the Table.

Where this does not occur the post spacing must be reduced by the proportion of the thread engagement to 90mm

- (4) The screw holes must be sealed as shown in figure 19 of E2/AS1. Check the suitability of screw protrusion beyond the timber framing.
- (5) Washers to be fitted under screw and bolt heads shall be as follows
 - For 8mm fasteners - 22mm O.D. S/S washer (Part No. FW8-22) with a polymer washer (Part No. FWP8-22G) between the S/S and the aluminium.

MAXIMUM POST CENTRES 'S max' (metres) ALWAYS TAKE THE LESSER OF THE VALUE BELOW AND THE VALUE FROM THE STYLE SPECIFICATION																									
'H' Height (Note 3)	Post Type	Fasteners - Qty and Type (Note 2)	'F' (See diagram)	Line No.	LOADING CLASS (Note 1)																				
					A1								A2	R											
					Design Wind Speed (Note 4)									Design Wind Speed (Note 4)											
					50	52	54	56	58	60	62	64	N/A	M	H	VH									
					50	52	54	56	58	60	62	64	N/A	38	40	42	44	46	48	50	52	54	56		
1.0	VPH2	4 x FC8-165	14-60	1	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.87	N/A	1.70	1.70	1.70	1.70	1.68	1.54	1.42	1.31	1.22	1.13		
	DPE	4 x FC8-165	14-60	2	1.07	1.07	1.07	1.07	1.06	0.99	0.92	0.87	N/A	2.01	2.01	2.01	1.84	1.68	1.54	1.42	1.32	1.22	1.13		
1.1	VPH2	4 x FC8-165	14-60	3	0.73	0.73	0.73	0.73	0.73	0.73	0.73	0.73	N/A	1.45	1.45	1.45	1.45	1.41	1.29	1.19	1.10	1.02	0.95		
	DPE	4 x FC8-165	14-60	4	0.89	0.89	0.89	0.89	0.89	0.89	0.89	0.87	N/A	1.72	1.72	1.72	1.72	1.68	1.54	1.42	1.32	1.22	1.13		
(1) LOADING CLASS: Refer to Page 2.9.3 of this MANUAL for the scope of the Loading Class designations. (2) FASTENER DESIGNATIONS: beginning with 'F' are part numbers for fasteners supplied by UNEX eg. FC8-165: FC = Coach Screw Stainless Steel. 8 = 8mm diameter, 165 = length in mm; 4 x FC8-165 fasteners may be substituted with 4 x M8 bolts (Grade 70 Stainless Steel); Substitution with other fasteners is not permitted. (3) HEIGHT 'H': is the overall height of the balustrade above the substrate level shown. Interpolate for Heights between those shown. (4) DESIGN WIND SPEED: in m/s, Refer to Pages 3.8.1 to 3.8.6 for details of applicable wind codes and the methods for determining the Design Wind Speed for any particular site.																									

Specifications subject to change without notice

PRELIMINARY PRODUCER STATEMENT

14333

Truss Design Criteria For Building Consent Application

CLIENT Name: Tom Roulston

SITE Details:

Address: 125 Nikau Palm Road
Paraparaumu

City:

Post Code: State:

Nominal Design Criteria:

Building importance: Residential

Roofing: Corrugated iron

Ceiling: 13mm Gib-board

Top chord purlins: 900 mm

BC restraints: 600 mm

Standard truss spacing: 900 mm

Standard roof pitch: 8.00 deg.

Ult. design wind speed: 44 m/s (wind classification = High)

Max. eaves height: 3 m

Max. ridge height: 12 m

Int pressure coeff. up: 0.2

Structural Fascia: Required

Design Roof Snow Load: 0 Pa
(incl. probability factor)

Location: Region N1 - lower Nth Island

Altitude Above Sea Level: 100 m

Building Exposure Factor: Sheltered



The truss designs for this project have been determined using computer software provided by the Technical Division within Pryda. These designs are in accordance with sound and widely accepted engineering principles and comply with the following New Zealand Standards:

AS/NZS1170.0 - 2002 Structural Design Actions Part 0: General Principles

AS/NZS1170.1 - 2002 Structural Design Actions Part 1: Permanent, imposed and other actions

AS/NZS1170.2 - 2002 Structural Design Actions Part 2: Wind actions

AS/NZS1170.3 - 2003 Structural Design Actions Part 3: Snow and ice actions

NZS3603: 1993 Timber Structures Standard

AS1649: 2001 Timber- Methods of test for mechanical fasteners and connectors
Basic working loads and characteristic strengths.

All trusses are to be manufactured in accordance with the fabrication specifications provided by Pryda, and installed connected and braced in accordance with the recommendations given in - : AS4440:2004 "Installation of nailplated timber roof trusses" and any other supplementary details that may be provided.

We confirm that the proposed trusses for this project will be manufactured in accordance with the fabrication specifications provided by Pryda Truss Systems. This is a preliminary producer statement only. A final certificate will be provided upon completion of manufacture.

This preliminary and future certificates will be void should any other manufacturer construct the proposed trusses.

Name: Damian

Signed: [Signature]

Position: Detailer

Date: 12.3.09

Producer Statement - PS1- Design

ISSUED BY: MiTek New Zealand Ltd

TO BE SUPPLIED TO: Building Consent Authorities in New Zealand

IN RESPECT OF: Posi-STRUT Design Manual, June 2008

AT: Various Locations in New Zealand

MiTek New Zealand Ltd has provided engineering design services in respect of the requirements of Clause B1 of the NZ Building Code for

☐ All

☒ Part only as specified – Posi-STRUT trusses

of the proposed building work.

The selection charts within this design manual have been prepared in accordance with **Compliance Documents and Verification Method B1/VM1** of the NZ Building Code and in accordance with sound and widely accepted engineering principles.

On behalf of **MiTek New Zealand Ltd**, and subject to:


1. The verification of the design assumptions within this manual
2. All proprietary products meeting their performance specification requirements;

I **believe on reasonable grounds** that the use of Posi-STRUT trusses in the building if constructed in accordance with the drawings, specifications and other documents provided, will comply with the relevant provisions of the Building Code.

MiTek New Zealand Ltd holds a current policy of Professional Indemnity Insurance of not less than \$500,000.

On behalf of MiTek New Zealand Ltd

Date: June 2008



.....
In Ling Ng
Technical Services Manager
BE (Hons), CPEng, IntPE
MIPENZ (ID: 146585)

MiTek New Zealand Ltd.

AUCKLAND: 40 Neales Road, East Tamaki 2013 PO Box 58-014, Greenmount 2141 Ph: 09-274 7109 Fax: 09-274 7100
CHRISTCHURCH: 14 Pilkington Way, Wigram 8042 PO Box 8387, Riccarton 8440 Ph: 03-348 8691 Fax: 03-348 0314

Design Loads

Refer also to NZS 3604, NZS 4203 and AS/NZS 1170

Posi-STRUT trusses supporting load-bearing walls are not covered by these selection charts and require special design.

Dead loads

Heavy Roof Rafter	0.65 kPa
Light Roof Rafter	0.25 kPa
Light Roof Purlin	0.20 kPa
Ceiling	0.20 kPa
Floor (1.5 kPa LL) + ceiling	0.40 kPa
Floor (3.0 kPa LL) + ceiling	0.50 kPa

Live loads

	Distributed	Conc.
Roof, maintenance	0.25 kPa	1.0 kN
Floor, domestic	1.5 kPa	1.8 kN
Floor, office	3.0 kPa	2.7 kN
Floor, public use	3.0 kPa	2.7 kN

Wind loads

	Design Wind Speed	q_u
Low	32 m/s	0.61 kPa
Medium	37 m/s	0.82 kPa
High	44 m/s	1.16 kPa
Very High	50 m/s	1.50 kPa

Combined pressure coefficients $C_p = 1.2$ max.

Snow loads

0.5 kPa and 1.0 kPa

Special design is required for higher snow loads.

Deflection Criteria

Refer also to BRANZ guidelines.

Floors

Span/600	10mm maximum under live load only. Short term load. (for liveliness control)
Span/600	15mm maximum under permanent long term load. (G+0.4Q, including creep)

Rafters

Span/400	15mm maximum under permanent long term load
Span/333	under wind load (with ceiling)
Span/167	under wind load (without ceiling)

Purlins

Span/400	15mm maximum under long term load
Span/167	under wind load

Cantilevers

Span/300	8mm maximum under dead and live load
----------	--------------------------------------

Design Strength

Trusses are designed to the Limit State Design provisions of NZS 4203 and NZS 3603.

Timber stresses







Timber properties to Table 2.3 NZS 3603:1993 Amendment 4

Timber Grade	Bending Strength f_b (MPa)	Compression Strength f_c (MPa)	Tension Strength f_t (MPa)	Modulus of Elasticity E (GPa)
MSG8	14.0	18.0	6.0	8.0
MSG10	20.0	20.0	8.0	10.0
MSG12	28.0	25.0	14.0	12.0

Modification factors

K_1	Load Case
0.6	Dead load only
0.8	Dead load and floor live load
0.8	Dead load and snow load
1.0	Dead load and roof live load
1.0	Dead load and wind load

Floor Trusses

Maximum Span (m) at Spacing = S								
Domestic Floor - 1.5 kPa Live Load								
	Truss Code	D mm	Machine Stress Graded MSG8			Machine Stress Graded MSG10 ⁽¹⁾		
			Spacing "S" mm			Spacing "S" mm		
			400	450	600	400	450	600
	PS20-21x07	217	3.3	3.2	2.8	4.2	3.9	3.3
	PS25-25x07	249	3.9	3.7	3.1	4.5	4.3	3.7
	PS30-30x07	303	4.4	4.2	3.6	5.2	4.9	4.2
	PS40-40x07	413	5.3	4.9	4.3	6.2	5.8	5.0
	PS20-21x09	217	4.1	3.8	3.2	4.6	4.4	3.8
	PS25-25x09	249	4.5	4.2	3.6	5.1	4.9	4.2
	PS30-30x09	303	5.1	4.8	4.1	5.8	5.5	4.8
	PS40-40x09	413	6.1	5.6	4.9	7.1	6.7	5.6
	PS20-21x14	217	4.9	4.7	4.1	5.3	5.1	4.1
	PS25-25x14	249	5.5	5.2	4.5	5.9	5.7	5.1
	PS30-30x14	303	6.3	5.9	5.1	6.7	6.5	6.0
	PS40-40x14	413	7.6	7.1	6.0	7.9	7.6	7.1
	PS40-45x05	D/(d1) 463/(70)	5.5	5.1	4.5	6.4	6.0	5.2
	PS40-50x05	503/(90)	6.4	6.0	5.2	7.3	7.0	6.0
	PS40-60x05	603/(140)	8.3	7.8	6.8	9.0	8.7	7.8
	PS20-19x09	197	3.3	3.2	2.5	4.0	3.8	3.2
	PS25-23x09	229	3.8	3.6	3.1	4.4	4.2	3.6
	PS30-28x09	283	4.4	4.1	3.6	5.1	4.8	4.1
	PS40-39x09	393	5.3	4.7	4.0	6.1	5.7	4.8
	PS25-24x09	239	4.4	4.1	3.2	4.8	4.6	4.1
	PS30-29x09	293	5.0	4.6	3.9	5.6	5.4	4.5




(1) When specifying check the availability of MSG10 timber.




(2) 140mm wide trusses may not be available from all fabricators.

(3) These sizes are useful to match solid timber joist sizes.

(4) Spans in bold and shaded indicate double webs (DW) are required at ends (see page 21).

Rafter Trusses

Maximum Span (m) at Spacing = S										
Light Roof - Low/Medium Wind - Grade MSG8										
	Truss Code	D mm	With Ceiling				Without Ceiling			
			Spacing "S" mm				Spacing "S" mm			
			600	900	1200	1800	900	1200	1800	2400
	PS20-21x07	217	5.2	4.5	3.8	3.2	5.3	4.6	3.7	3.3
	PS25-25x07	249	5.6	4.9	4.3	3.4	5.8	5.0	4.1	3.4
	PS30-30x07	303	6.3	5.6	4.8	3.8	6.5	5.6	4.5	4.0
	PS40-40x07	413	7.6	6.7	5.7	4.6	7.7	6.7	5.5	4.8
	PS20-19x09	197	5.0	4.4	3.8	3.1	5.2	4.5	3.6	3.2
	PS25-23x09	229	5.5	4.8	4.2	3.3	5.6	4.9	4.0	3.3
	PS30-28x09	283	6.2	5.5	4.8	3.9	6.4	5.6	4.5	3.9
	PS40-39x09	393	7.5	6.6	5.7	4.5	7.6	6.8	5.4	4.8
	PS20-21x09	217	5.5	5.0	4.4	3.6	5.7	5.2	4.3	3.7
	PS25-25x09	249	6.0	5.4	4.8	3.9	6.2	5.7	4.7	4.0
	PS30-30x09	303	6.7	6.1	5.5	4.4	6.9	6.4	5.3	4.6
	PS40-40x09	413	8.0	7.3	6.4	5.3	8.2	7.6	6.3	5.5

Maximum Span (m) at Spacing = S										
Light Roof - High/Very High Wind - Grade MSG8										
	Truss Code	D mm	With Ceiling				Without Ceiling			
			Spacing "S" mm				Spacing "S" mm			
			600	900	1200	1800	900	1200	1800	2400
	PS20-21x07	217	5.0	4.1	3.4	2.8	3.6	3.2	2.2	1.9
	PS25-25x07	249	5.5	4.4	3.8	3.1	3.9	3.4	2.7	2.0
	PS30-30x07	303	6.2	5.0	4.3	3.3	4.4	3.8	3.0	2.0
	PS40-40x07	413	7.2	5.7	5.0	4.1	5.3	4.5	3.8	2.7
	PS20-19x09	197	4.9	3.9	3.3	2.2	3.7	3.1	2.0	1.3
	PS25-23x09	229	5.4	4.3	3.7	2.7	4.1	3.3	2.1	1.3
	PS30-28x09	283	6.1	4.9	4.2	3.1	4.7	3.9	2.5	1.9
	PS40-39x09	393	7.1	5.5	4.7	2.5	5.3	4.8	3.9	2.6
	PS20-21x09	217	5.5	4.7	4.0	3.2	4.4	3.9	3.0	2.2
	PS25-25x09	249	6.0	5.1	4.4	3.4	4.8	4.1	3.2	2.6
	PS30-30x09	303	6.7	5.7	4.9	3.9	5.4	4.7	3.7	2.9
	PS40-40x09	413	8.0	6.9	5.9	4.2	6.4	5.4	4.2	3.9

(1) Spans in bold and shaded indicate double webs (DW) are required at ends (see page 21).

ARCHITECTURE DM

22/01/2009

Risk Matrix

Project No

125 NIKAU PALM ROAD, PARAPARAUMU

Building Face North

Risk Item	Selection	Description	Score
Wind Zone	H ▼	High wind zone	1
Storeys	H ▼	2 storey	2
Roof/Wall Intersection	VH ▼	Roof ends finishing within the boundaries formed by the exterior walls (e.g. lower ends of aprons, chimneys, dormers etc)	5
Eaves Width	M ▼	451 - 600mm for single storey, or over 600mm for two storey	1
Envelope Complexity	M ▼	Moderately complex, angular or curved shapes (e.g. Y or arrowhead) with no more than two cladding types	1
Deck Design	VH ▼	Enclosed deck, exposed in plan or cantilevered at second floor level or above	6
Total Risk Factor			16

Building Face South

Risk Item	Selection	Description	Score
Wind Zone	H ▼	High wind zone	1
Storeys	H ▼	2 storey	2
Roof/Wall Intersection	VH ▼	Roof ends finishing within the boundaries formed by the exterior walls (e.g. lower ends of aprons, chimneys, dormers etc)	5
Eaves Width	M ▼	451 - 600mm for single storey, or over 600mm for two storey	1
Envelope Complexity	L ▼	Simple rectangular, L, T or boomerang shape with single cladding type	0
Deck Design	L ▼	None, timber slat deck or porch at ground level	0
Total Risk Factor			9

Building Face East

Risk Item	Selection	Description	Score
Wind Zone	H ▼	High wind zone	1
Storeys	H ▼	2 storey	2
Roof/Wall Intersection	L ▼	Fully protected (e.g. hip & gable with eaves)	0
Eaves Width	M ▼	451 - 600mm for single storey, or over 600mm for two storey	1
Envelope Complexity	M ▼	Moderately complex, angular or curved shapes (e.g. Y or arrowhead) with no more than two cladding types	1
Deck Design	VH ▼	Enclosed deck, exposed in plan or cantilevered at second floor level or above	6
Total Risk Factor			11

Building Face West

Risk Item	Selection	Description	Score
Wind Zone	H ▼	High wind zone	1
Storeys	H ▼	2 storey	2
Roof/Wall Intersection	L ▼	Fully protected (e.g. hip & gable with eaves)	0
Eaves Width	M ▼	451 - 600mm for single storey, or over 600mm for two storey	1
Envelope Complexity	L ▼	Simple rectangular, L, T or boomerang shape with single cladding type	0
Deck Design	L ▼	None, timber slat deck or porch at ground level	0
Total Risk Factor			4

NOTE: Highest score is 16 so all claddings are to be on a cavity system in accordance with E2/AS1

GIB® Wall Bracing Calculation Sheet A

upper of two

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

Job Details

Name	ROLSTON
Street and Number	125 NIKAU PALM RD, PARAPARAUMU
Lot and DP Number	LOT 4 DP 82049
City/Town/District	KAPITI COAST
Designer and date	Dean Robb 1601/2009
Company Name	Architecture DM

Building Specification

Location of Storey	upper	▼	not applicable (slab)
Floor Loading	2 kPa	▼	
Foundation Type	slab	▼	
Building Height to Apex (m)	8	▼	
Roof Height above Eaves (m)	2	▼	
Stud Height (m)	2.7	▼	
Cladding Weight (top or single)	light	▼	
Cladding Weight (lower)	heavy	▼	
Cladding Weight (subfloor)	light	▼	
Roof Weight	light	▼	
Roof Pitch (degrees)	0-25	▼	
Room in Roof Space	no	▼	
Building Length (m)	22.2		
Building Width (m)	11		
Gross Building Plan Area (m2)	201.2		

Building Location

Wind Zone	High	Earthquake Zone
Region	R2 ▼	A ▼
Terrain	Inland ▼	
Exposure	Exposed ▼	
Topography	Gentle ▼	

Enter at least 'moderate' in a Lee Zone

Bracing Units required for Wind

per m	subfloor	walls
W along	n/a	69 BUs/m
W across	n/a	59 BUs/m
Totals		
W along	n/a	754 BUs
W across	n/a	1299 BUs

Bracing Units required for Earthquake

per m2	subfloor	walls
E	n/a	6.2 BUs/m2
Totals		
E along	n/a	1247 BUs
E across	n/a	1247 BUs

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BUs W/m	BUs EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Wall Bracing Calculation Sheet A

lower of two

V85A

GIB® EzyBrace™

GIB® Bracing Systems, 2006

Job Details

Name	ROLSTON
Street and Number	125 NIKAU PALM RD, PARAPARAUMU
Lot and DP Number	LOT 4 DP 82049
City/Town/District	KAPITI COAST
Designer and date	Dean Robb 1601/2009
Company Name	Architecture DM

Building Specification

Location of Storey	lower	▼	not applicable (slab)
Floor Loading	2 kPa	▼	
Foundation Type	slab	▼	
Building Height to Apex (m)	8	▼	
Roof Height above Eaves (m)	2	▼	
Stud Height (m)	2.7	▼	
Cladding Weight (top or single)	light	▼	
Cladding Weight (lower)	heavy	▼	
Cladding Weight (subfloor)	light	▼	
Roof Weight	light	▼	
Roof Pitch (degrees)	0-25	▼	
Room in Roof Space	no	▼	
Building Length (m)	22.2		
Building Width (m)	11		
Gross Building Plan Area (m2)	193.7		

Building Location

Wind Zone	High		Earthquake Zone	
Region	R2	▼	A	▼
Terrain	Inland	▼		
Exposure	Exposed	▼		
Topography	Gentle	▼		

Enter at least 'moderate' in a Lee Zone

Bracing Units required for Wind

per m	subfloor	walls
W along	n/a	168 BUs/m
W across	n/a	159 BUs/m
Totals		
W along	n/a	1848 BUs
W across	n/a	3530 BUs

Bracing Units required for Earthquake

per m2	subfloor	walls
E	n/a	13.5 BUs/m2
Totals		
E along	n/a	2615 BUs
E across	n/a	2615 BUs

GIB® Wall Bracing Calculation Sheet B						lower of two		V85A	
GIB® EzyBrace™					GIB® Bracing Systems, 2006				
Along									
Wall or Bracing Line	Bracing Elements provided							Wind	Earthq.
1	2	3	4	5	7	8	6	9W	10EQ
Line Label	Minimum BUs Req/Ach	Bracing Element No.	Supplier	Bracing Type	Element Length L (m)	Element Height H (m)	Angle to Bracing line (degrees)	BUs Achieved	BUs Achieved
A	enter	1	NZS 4229	MASONAF	6	2.7		3440	3440
		2							
line totals		3							
W	3440	4							
EQ	3440	5							
B	enter	1	GIB®	GS1a	2.5	2.7		167	144
		2	GIB®	GS1a		2.7			
line totals		3							
W	167	4							
EQ	144	5							
C	enter	1	EcoPLY	SP1	0.9	2.7		80	92
		2	EcoPLY	SP2	0.6	2.7		48	56
line totals		3	GIB®	GS1a	1.8	2.7		104	88
W	232	4							
EQ	236	5							
D	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
E	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
F	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
G	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
H	enter	1							
		2							
line totals		3							
W		4							
EQ		5							

Wind Earthq.
Totals Achieved 3839 3820
 OK OK
Totals Required (from Sheet A) 1848 2615

GIB® Bracing Systems, 2006

<i>For full construction details see literature GIB® Bracing Systems, 2006</i>
--

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
NZS 4229	MASONAR	6	645	645
EcoPLY	SP1	0.9	100	115
EcoPLY	SP2	0.6	90	105
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved

GIB® Wall Bracing Calculation Sheet B					lower of two		V85A		
GIB® EzyBrace™					GIB® Bracing Systems, 2006				
Across									
Wall or Bracing Line		Bracing Elements provided					Wind	Earthq.	
1	2	3	4	5	7	8	6	9W	10EQ
Line Label	Minimum BUs Req/Ach	Bracing Element No.	Supplier	Bracing Type	Element Length L (m)	Element Height H (m)	Angle to Bracing line (degrees)	BUs Achieved	BUs Achieved
M	enter	1	EcoPLY	SP1	0.9	2.7		80	92
		2	EcoPLY	SP1	0.9	2.7		80	92
line totals		3	EcoPLY	SP1	0.9	2.7		80	92
W	240	4							
EQ	276	5							
N	enter	1	NZS 4229	20 Block	1.2	3		235	235
		2							
line totals		3							
W	235	4							
EQ	235	5							
O	enter	1	EcoPLY	SP1	0.9	2.7		80	92
		2	EcoPLY	SP1	0.9	2.7		80	92
line totals		3	EcoPLY	SP1	0.9	2.7		80	92
W	240	4							
EQ	276	5							
P	enter	1	GIB®	GS1a	2	2.7		116	98
		2	GIB®	GS1a	2.4	2.7		160	139
line totals		3							
W	276	4							
EQ	236	5							
Q	enter	1	GIB®	GS1a	2	2.7		116	98
		2	NZS 4229	25 Block	6	2.7		3440	3440
line totals		3							
W	3556	4							
EQ	3538	5							
R	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
S	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
T	enter	1							
		2							
line totals		3							
W		4							
EQ		5							
							Wind	Earthq.	
Totals Achieved							4546	4561	
							OK	OK	
Totals Required (from Sheet A)							3530	2615	

GIB® Bracing Systems, 2006

*For full construction details see literature
GIB® Bracing Systems, 2006*

Supplier	System	Minimum Length (m)	BU's W/m	BU's EQ/m
	none			
GIB®	GS1a	1.8	65	55
		2.4	75	65
GIB®	GS2	1.2	70	60
		1.8	80	70
		2.4	90	80
GIB®	BL1	0.4	120	115
		0.6	125	115
GIB®	BL1a	1.8	130	115
GIB®	BLP	0.6	145	135
		0.9	145	145
GIB®	BLG	0.6	145	130
		1.2	150	130
NZS 4229	25 Block	6	645	645
NZS 4229	20 Block	1.2	245	245
EcoPLY	SP1	0.9	100	115
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			
Custom	Custom			

©Winstone Wallboards Limited, 1999-2006.
All rights reserved



**ISP CONSULTING
ENGINEERS LTD**

Civil & Structural
Electrical
Seismic Risk Analysis
Forensic Investigation
Building Compliance

Lower Hutt Office
Tel: 04 566 8004
Fax: 04 566 8037
Level 1, 14 Laings Rd
P.O. Box 30 535
Lower Hutt

Paraparaumu Office
Tel: 0800 477 546
P.O. Box 537
Coastlands Parade
Paraparaumu

Email: email@isp.co.nz
Web: www.isp.co.nz

Structural Calculations

For

125 Nikau Palm road, Proposed Residence Paraparaumu

These calculations are in accordance with:

AS/NZS 1170:2002 Structural Design Actions
NZS3101:1995 Design of Concrete Structures
NZS3404:1998 Design of Steel Structures
NZS3603:1993 Design of Timber Structures
NZS3604:1999 Timber Framed Buildings
NZS4229:1989 Design of Masonry Structures Not Requiring Specific Design
NZS4230:2004 Design of Reinforced Concrete Masonry Structures

Engineer:

Stuart Preston
Michael Younghusband

Initials:

SP
M.Y.

Preamble:

Design of a proposed house outside the scope of NZS3604, including:

- Scala Penetrometer soil tests
- Specific foundation design and construction details
- Structural beam design calculations and end connection details
- Reinforced masonry retaining wall design calculations and construction details.

Date:
9 March 2009

Job No.
23040



ISO 9001





drainage for upper floor roof runoff
storage tanks - see attached
specifications. Surplus stormwater
to confirm exact siting

Columns in lower storey

PS40-60X05 Posi-STRUT MSG8
floor truss System @ 400ctrs as per
MiTek specification

300 litre HWC
below connected to
wetback system





Date

Eng.

M.Y.

Job No.

Sheet No.


3



CALCULATIONS

Project


125 N. Hau Palm Road



Pile Layout

Driven piles
φ 150

Depositable
capacity
of 75kN



Date

27/02/09

Eng.

M.Y

Job No.

Sheet No.


5

Project

125 Nikau Palm Road



Retaining Wall





Any person wishing to rely on the information shown on this map must independently verify the information
Scale 1:10000 Topographical and Cadastral map derived from LINZ data. Printed 24/02/2009 15:55

Date: 24-Feb-09 Eng: M.Y. Job Number: 23046 Sheet No: 0
 Project: 125 Nikau street
 Wind from North direction




Site Wind Speed

$$V_{(z)} = V_r \times M_d \times (M_{(zcat)} \times M_s \times M_t)$$

$V_{r500} = 51 \text{ m/s}$ $M_d = 1$ $M_s = 1$
 Terrain Factor = 3. Obstructions 3-5m
 Building Height = 7m
 Gives $M_{(zcat)} = 0.83$ $M_s = 0.85$ for buildings in normal built-up areas.
 Refer to AS1170.2 Clause 4.3.1

Hill Shape Multiplier M_h



If $(H/2)/L_u < 0.05$ $M_h = 1$
 If $0.05 < (H/2)/L_u < 0.45$ $M_h = 1 + (H/(3.5(z+L_1)) \times (1-D/L_2)$
 If $(H/2)/L_u > 0.45$ $M_h = 1 + 0.71(1-D/L_2)$

$H = 140 \text{ m}$ (Rise height) Slope $[(H/2)/L_u] = 0.18$
 $L_u = 400 \text{ m}$ (distance from mid rise to crest) $L_1 = 144 \text{ m}$
 $D = 1000 \text{ m}$ (building distance from crest) $L_2 = 576 \text{ m}$
 $z = 7 \text{ m}$ (building height) $M_h = 1.00$
 $M_{lee} = 1$ $M_{lee} = 1.00$
 Elevation = 120 m $M_e = \text{greater of } 1 \text{ or } (Elevation - 500) \times 0.00015 = 1.00$
 $M_t = M_h \times M_{lee} \times M_e = 1.00$

$$V_{(z)} = 51.00 \times 1.00 \times 0.83 \times 1.00 \times 1.00 = 42.33 \text{ m/s}$$

NZS 3604:1999 Wind Speed Zone: High Wind Speed

Date: 24-Feb-09
 Project: 125 Nikau street

Eng: M.Y.

Job Number: 23046 Sheet No:

Wind from West direction



Site Wind Speed

$$V_{(z)} = V_r \times M_d \times (M_{(zcat)} \times M_s \times M_t)$$

$$V_{r500} = 51 \text{ m/s}$$

$$M_d = 1$$

$$M_s = 1$$

Terrain Factor = 3. Obstructions 3-5m

Building Height = 7m


$$\text{Gives } M_{(zcat)} = 0.83$$

$M_s = 0.85$ for buildings in normal built-up areas.

Refer to AS1170.2 Clause 4.3.1

Hill Shape Multiplier M_h

WIND DIRECTION



$$\begin{aligned} \text{If } (H/2)/L_u < 0.05 & \quad M_h = 1 \\ \text{If } 0.05 < (H/2)/L_u < 0.45 & \quad M_h = 1 + (H/(3.5(z+L_1)) \times (1-D/L_2)) \\ \text{If } (H/2)/L_u > 0.45 & \quad M_h = 1 + 0.71(1-D/L_2) \end{aligned}$$

H = 80 m (Rise height)

Lu = 450 m (distance from mid rise to crest)

D = 700 m (building distance from crest)

z = 7 m (building height)

$M_{lee} = 1$

Elevation = 80 m

Slope $[(H/2)/L_u] = 0.09$

$L_1 = 162 \text{ m}$

$L_2 = 648 \text{ m}$

$M_h = 1.00$

$M_{lee} = 1.00$

$M_e = \text{greater of } 1 \text{ or } (Elevation - 500) \times 0.00015 = 1.00$

$$M_t = M_h \times M_{lee} \times M_e = 1.00$$

$$V_{(z)} = 51.00 \times 1.00 \times 0.83 \times 1.00 \times 1.00 = 42.33 \text{ m/s}$$

NZS 3604:1999 Wind Speed Zone: High Wind Speed

Date	26/02/09	Eng.	M.Y.	Job No.	Sheet No.
Project	125 Nikau Palm				



Lintel 1

length : 3.1m

loads : Deck
Floor

See spreadsheet, Lintel 1

Lintel 2

length : 5.4m

loads : Deck
Floor

See spreadsheet

AS/NZS 1170 TIMBER BEAM CALCULATION SHEET - MSG8

Job Name: 125 Nikau palm


Job No. 23040

Sheet No.

Date: 26-Feb-09

Engineer M.Y

Beam No. Lintel 1



L = 3.1 m
a = m
b = 3.1 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.13
	Deck 2.25m x .35kPa		0.79
Total Dead Load		G =	0.92 kN/m

Live	Roof ($\Psi_c = 0$ for Q_f)		
	Floor 2kPa x 2.25m		4.50
Total Live Load		Q =	4.50 kN/m

$$W^* = 1.2 G + 1.5 Q = 7.85 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 2.72 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
Total Dead Point Load		G =	0.00 kN

Live			
Total Live Point Load		Q =	0.00 kN

Le (m) 0.5

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment $M^* = \frac{W^* L^2}{8} + \frac{P^* ab}{L}$

Profile Gauged

Section 290x90

(dry, $f_b = 14 \text{ Mpa}$)

All Timber is MSG8 or VSG8 $k_8 = 1.00$

$$\phi M_b = \phi k_1 k_8 f_b Z \quad \phi = k_1 = 0.8$$

Serviceability Deflection

(Under $W_s + P_s$)

$$(k_2 = 2) \Delta = 4.5 \text{ mm}$$

$$= \text{Span} / 687$$

$$M^* = 9.43 \text{ kNm}$$

$$Z = 1263.0 \times 10^3 \text{ mm}^3$$

$$D/B = 3$$

$$Le/B = 10$$

$$\phi M_b = 11.32 \text{ kNm}$$

$$El_{xx} = 1449.91 \times 10^9 \text{ Nmm}^2$$

$$\text{Under 1 kN Point Load } \Delta = 0.4 \text{ mm}$$

Reaction	Dead	Live	Ultimate
R1	1.43kN	6.98kN	12.17kN
R2	1.43kN	6.98kN	12.17kN

23040 Lintel 1 MSG8

26/02/2009

AS/NZS 1170 STEEL BEAM CALCULATION SHEET

Job Name:

125 Nikau Palm

Job No. 23040


Sheet No.

Date:

26-Feb-09

Engineer M.Y.

Beam No. lintel 2



L = 5.4 m ✓
a = m
b = 5.4 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.23
	floor (deck)	.35kPa x 2.25m	0.79
Total Dead Load		G =	1.02 kN/m

Live

Roof ($\Psi_c = 0$ for Q_f)		
Floor	2kPa x 2.25	4.50
Total Live Load		Q = 4.50 kN/m

$$W^* = 1.2 G + 1.5 Q = 7.97 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 2.82 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
Total Dead Point Load		G =	0.00 kN
Live			
Total Live Point Load		Q =	0.00 kN

Le (m)

1

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* L^2 / 8 + P^* ab / L$$

Profile

Channel Section

All Steel is Grade 300

Section

200PFC

$$M^* = 29.05 \text{ kNm}$$

$$\phi M_b = 54.8 \text{ kNm} /$$

okay

$$I_{xx} = 19.10 \times 10^6 \text{ mm}^4$$

Serviceability Deflection

$$\text{(Under } W_s + P_s) \Delta = 8.2 \text{ mm} /$$

$$= \text{Span} / 662$$

$$\text{(Under 1 kN Point Load)} \Delta = 0.9 \text{ mm} /$$

Reaction

R1

Dead

2.74kN

Live

12.15kN

Ultimate

21.52kN

R2

2.74kN

12.15kN

21.52kN

Date 26/02/09

Eng. M.Y

Job No.


Sheet No. 12

Project

125 Nikau Street



Beam 1



Loads

Floor (assuming loads are in most critical sections only)

Joists:




$$\text{Dead} : 0.3 \text{ kPa} \times 0.75 \text{ m} = 0.225 \text{ kN/m}$$

$$\text{Live} : 1.5 \text{ kPa} \times 1.5 \text{ m} = 1.125 \text{ kN/m}$$

$$M^* = 52.2 \quad \phi M_n = 172 \text{ kNm} - \text{OK} \quad (L_e = 2)$$

{ USE 310 UB 46.2 } See spreadsheet.

Beam 2



Loads

$$\begin{aligned} \text{Dead} : - \text{UDL} : & \text{Section A} : 0 \\ & \text{Section B} : 0.75 \text{ m} \times 0.35 = 0.263 \text{ kN/m} \\ & \text{Section C} : 4.6 \text{ m} \times 0.35 = 1.61 \text{ kN/m} \end{aligned}$$

$$\begin{aligned} - \text{Point loads} : & \text{Beam 3 reaction} = 0.61 \text{ kN} \\ & \text{Beam 1 reaction} = 3.48 \text{ kN} \end{aligned}$$

$$\begin{aligned} \text{Live} : - \text{UDL} & \text{Section A} : 0 \text{ kN/m} \\ & \text{Section B} : 0.75 \times 2 \text{ kPa} = 1.5 \text{ kN/m} \\ & \text{Section C} : 3.85 \times 1.5 \text{ kPa} + 0.75 \times 2.0 \text{ kPa} = 7.28 \text{ kPa} \end{aligned}$$

$$\begin{aligned} - \text{Point loads} & \text{Beam 3} = 3.0 \text{ kN} \\ & \text{Beam 1} = 10.8 \text{ kN} \end{aligned}$$

{ Use 250 PFC } See Space Case spreadsheet


$$M^* = 40.31 \quad \phi M_n = 61.0 \text{ kNm} \quad (L_e = 4.0) \quad \text{OK}$$

AS/NZS 1170 STEEL BEAM CALCULATION SHEET

Job Name: 125 Nikau Palm

Job No. 23040
Sheet No.

Date: 26-Feb-09

Engineer M.Y.
Beam No. Beam 1

L = 9.6 m
a = m
b = 9.6 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.46
	floor (deck)	.35kPa x 1.5m	0.53
Total Dead Load		G =	0.99 kN/m

Live

Roof ($\Psi_c = 0$ for Q_f)		
Floor	1.5kPa x 1.5	2.25
Total Live Load		Q = 2.25 kN/m

$$W^* = 1.2 G + 1.5 Q = 4.56 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 1.89 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
	Total Dead Point Load	G =	0.00 kN
Live			
	Total Live Point Load	Q =	0.00 kN

Le (m) 2

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* L^2 / 8 + P^* ab / L$$

Profile

Universal Beam

All Steel is Grade 300

$$M^* = 52.52 \text{ kNm}$$

$$\phi M_b = 172.0 \text{ kNm}$$

okay

Section

310UB46.2

$$I_{xx} = 99.50 \times 10^6 \text{ mm}^4$$

Serviceability Deflection

$$(\text{Under } W_s + P_s) \Delta = 10.5 \text{ mm}$$

$$= \text{Span} / 915$$

$$(\text{Under } 1 \text{ kN Point Load}) \Delta = 0.9 \text{ mm}$$

Reaction

R1

Dead

4.74kN

Live

10.80kN

Ultimate

21.89kN

R2


4.74kN

10.80kN


21.89kN

23040 Beam 2

Dead Loads




Live Loads




23040 Beam 2


Deflections from 1kN



Deflections under service





Moments (1.2G+1.5Q)



16 11/11

Load cases:
■ 5 1.2G+1.5Q



Reactions
No general restraint

Materials:
■ 1 STEEL

Sections:
■ 1 250 PFC

Date

26/02/09

Eng.

M.Y

Job No.

Sheet No.

1517


Project

125 Nikau Street



Beam 2a

length = 6.5m



Loads

floor

Roof

Wall - point load

Roof load:

$$G_{\text{roof}} = 0.35 \text{ kPa} \times 4.85 \text{ m} = 1.7 \text{ kN/m}$$

Roof above window:

$$G_{\text{wall}} = 0.208 \text{ kN/m}^2 \times 1.5 \text{ m} = 0.312 \text{ kN/m}$$

Reactions from total above window:

$$(1.7 \text{ kN/m} + 0.312 \text{ kN/m}) \times 3.8 \text{ m} / 2 = 3.823 \text{ kN}$$

Live load on roof



$$Q_{\text{roof}} = 0.25 \text{ kPa} \times 4.85 \text{ m} = 1.21 \text{ kN/m}$$

$$\text{Reactions: } 1.21 \text{ kN/m} \times 3.8 / 2 = 2.3 \text{ kN}$$

Floor loads

$$G: 0.35 \text{ kPa} \times 5.35 \text{ m} = 1.873 \text{ kN/m} \quad (\text{reactions} = 2.3 \text{ kN})$$

$$Q: 1.5 \text{ kPa} \times 3.85 \text{ m} + 2 \text{ kPa} \times 0.75 \text{ m} = 7.275 \text{ kN/m}$$



See Spacegass model printouts

⇒ Use 300 PFC

$$M^* = 74.6$$

$$\phi M_b = 144 \text{ kNm} \quad (L_c = 1.0)$$

OK

16/19

Load cases:

■ 2

Live, -9.15

-9.15

-7.28

-7.28

-7.28

-7.28

-9.15

-9.15

-2.3

-2.3

1

1

3

2


5

4

4

3

2



Beam 2a, live

Materials:
■ 1 STEEL

Sections:
■ 1 250 PFC

Job: I:\JOBFILES\ISP\23000\23040\23040 Beam 2a



Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: m/sec², Trans: mm, Stress: MPa

Scales - Frame: 1:37, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

4/8 20

Load cases:

■ 5 1.2G + 1.5Q



Beam 2a, moments

Materials:
■ 1 STEEL

Sections:
■ 1 250 PFC



Job: I:\JOBFILES\ISP\23000\23040\23040 Beam 2a

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: m/sec², Trans: mm, Stress: MPa

Scales - Frame: 1:37, Load: None, Disp: None, Moment: 2.622604, Shear: None, Axial: None, Torsion: None

Fig 21

Load cases:
■ 6 G + 0.4Q





Deflections

Materials:
■ 1 STEEL

Sections:
■ 1 300 PFC

Load cases:

■ 5 1.2G + 1.5Q



Beam 2a reactions

Materials:
■ 1 STEEL

Sections:
■ 1 300 PFC

Job: I:\JOBFILES\ISP\23000\23040\23040 Beam 2a

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m^3, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: m/sec^2, Trans: mm, Stress: MPa

Scales - Frame: 1:36, Load: None, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

Date

Eng.

M.Y

Job No.

Sheet No.

24/23


Project

125 Nikau Palm street.



Beam 3

trib area = 1m (Deck)



$$\text{Reactions} = 5.24$$

$$G: 0.3 \text{ kPa} \times 1\text{m} = 0.3 \text{ kN/m}$$


$$Q: 2 \text{ kPa} \times 1\text{m} = 2 \text{ kN/m}$$

$$1.2(0.3) + 1.5 \times 2 = 3.36 \text{ kN/m}$$

$$\text{Max moment} = \frac{wL^2}{8} = 3.78 \text{ kN/m}$$

Use 2/240 x 45

Beam 3a



Loads

UDL's

$$\text{Dead: } 0.35 \times 0.4\text{m} = 0.140$$

$$\text{live: } 2 \text{ kPa} \times 0.4\text{m} = 0.8 \text{ kN/m}$$

AS/NZS 1170 TIMBER BEAM CALCULATION SHEET - MSG8

Job Name: 125 Nikau Palm


Job No. 23040

Sheet No.

Date: 3-Feb-09

Engineer M.Y

Beam No. Beam 3



L = 3 m
a = m
b = 3 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.11
	deck	0.3kPa x 1m	0.30
Total Dead Load		G =	0.41 kN/m

Live	Roof ($\Psi_c = 0$ for Q_f)		0.00
	Floor	2kPa x 1	2.00
Total Live Load			Q = 2.00 kN/m

$$W^* = 1.2 G + 1.5 Q = 3.49 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 1.21 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
Total Dead Point Load		G =	0.00 kN
Live			
Total Live Point Load		Q =	0.00 kN

Le (m) 0.5

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* L^2 / 8 + P^* ab / L$$

Profile

Gauged

Section

240x90

(wetted, $f_b = 11.7 \text{ MPa}$)

All Timber is MSG8 or VSG8

$$M^* = 3.93 \text{ kNm}$$

$$Z = 868.5 \times 10^3 \text{ mm}^3$$

$$D/B = 3$$

$$Le/B = 10$$

$$k_8 = 1.00$$

$$\phi M_b = 6.50 \text{ kNm}$$

Serviceability Deflection

(Under $W_s + P_s$) $(k_2 = 2) \Delta = 3.1 \text{ mm}$

=Span/ 972

$$EI_{xx} = 826.85 \times 10^9 \text{ Nmm}^2$$

$$\text{Under 1 kN Point Load } \Delta = 0.7 \text{ mm}$$

Reaction

R1

Dead

0.61kN

Live

3.00kN

Ultimate

5.24kN

R2

0.61kN

3.00kN

5.24kN

23040 Beam 3 timber

2/03/2009

Date 04/03/09

Eng. M.Y

Job No. 23040


Sheet No. 25

Project


125 Nikau Palm



loading on Beam 3a



Pt load from beam 3.



$$\text{deflection limit at end} = \frac{700}{500} = 1.4$$

$$M^* = 4 \text{ kNm} \quad \phi M_n = 6.5 \text{ kNm} \quad (L_e = 2.0 \text{ m})$$

Use 2/240 x 45

$$\Rightarrow \text{deflection} = 0.74 \text{ mm} \quad \text{OK}$$

Beam 3b

$$G: 0.3 \times 1.2 \text{ m} = 0.36 \text{ kN/m}$$

$$Q: 2.0 \times 1.2 \text{ m} = 2.4 \text{ kN/m}$$

$$M^* = 3.95$$

$$\phi M_n = 6.24 \quad (L_e = 3.0 \text{ m})$$

Now deflections under service loads are 1.19 mm at end of cantilever which is quite high but there is a double twist around the perimeter of the deck which causes will spread the load so deflection. This will cause the deflections to be less than that calculated.


24-
26

SPACE GASS 10.60 - ISP CONSULTING ENGINEERS LTD

4 Mar 2009, 4:51 pm

Load cases:

■ 6 ——— G + 0.4Q



Live loads, Q
No general restraint

Materials:
■ 1 MSG8

Sections:
■ 1 240 x 90


Job: I:\JOBFILES\ISP\23000\23040\Beam 3a

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m^3, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa


Scales - Frame: 1:11, Load: None, Disp: 65.91797, Moment: None, Shear: None, Axial: None, Torsion: None

Beam 3b


Dead loads




Live Load



Deflection



Moments



Date

26/02/09

Eng.

M.Y

Job No.

Sheet No.

28

Project

125 Nikau Road



Beam 4

length = 30m

loads

Floor - trib width = 3.4m

Wall

Roof - trib width = 4.0m

See spreadsheet

 $\Rightarrow \{ \text{Use } 150 \text{ PFC} \}$

Beam 5

length = 5m

Floor - trib width = 0.75

Wall - 0.5kPa

Roof - $4.85 \text{ m} + 0.75 \text{ m} = 5.6 \text{ m}$ trib width. (conservative)

See spreadsheet,

Use 180 PFC

AS/NZS 1170 STEEL BEAM CALCULATION SHEET

Job Name: 125 Nikau street


Job No. 23040

Sheet No.

Date: 26-Feb-09

Engineer M.Y

Beam No. Beam 4



L = 3 m
a = m
b = 3 m

LOADING

1/. Uniformly Distributed Load

		Amount kN/m
Dead	Self Weight	0.18
	floor	3.4m x 0.3kPa
	wall	0.5kN/m
	roof	4.0m x 0.35kPa
		1.40
	Total Dead Load	G = 3.10 kN/m

Live	Roof ($\Psi_c = 0$ for Q_f)	4m x 0.25kPa	1.00
	Floor	3.4m x 1.5kPa	5.10
Total Live Load			Q = 6.10 kN/m

$$W^* = 1.2 G + 1.5 Q = 12.87 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 5.14 \text{ kN/m}$$

2/. Point Load

Dead		
	Total Dead Point Load	G = 0.00 kN
Live		
	Total Live Point Load	Q = 0.00 kN

Le (m) 1

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* \frac{L^2}{8} + P^* \frac{ab}{L}$$

Profile

Channel Section

All Steel is Grade 300

Section

150PFC

$$M^* = 14.47 \text{ kNm}$$

$$\phi M_b = 33.8 \text{ kNm} \checkmark$$

okay

$$I_{xx} = 8.34 \times 10^6 \text{ mm}^4$$

Serviceability Deflection

$$\text{(Under } W_s + P_s) \Delta = 3.2 \text{ mm} \checkmark$$

$$= \text{Span} / 924$$

$$\text{(Under 1 kN Point Load)} \Delta = 0.3 \text{ mm} \checkmark$$

Reaction	Dead	Live	Ultimate
R1	4.65kN	9.15kN	19.30kN
R2	4.65kN	9.15kN	19.30kN

AS/NZS 1170 STEEL BEAM CALCULATION SHEET

Job Name: 125 Nikau street


Job No. 23040

Sheet No.

Date: 26-Feb-09

Engineer M.Y

Beam No. Beam 5



L = 5 m

a = m

b = 5 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.21
	floor	0.75m x 0.3kPa	0.23
	wall	0.5kN/m	0.50
	roof	5.6m x 0.35kPa	1.96
Total Dead Load			G = 2.89 kN/m

Live	Roof ($\Psi_c = 0$ for Q_f)	5.6m x 0.25kPa	1.40
	Floor	0.75m x 1.5kPa	1.13
Total Live Load			Q = 2.53 kN/m

$$W^* = 1.2 G + 1.5 Q = 7.26 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 3.34 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
Total Dead Point Load			G = 0.00 kN

Live			
Total Live Point Load			Q = 0.00 kN

Le (m)

1

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* \frac{L^2}{8} + P^* \frac{ab}{L}$$

Profile

Channel Section

All Steel is Grade 300

Section

180PFC

$$M^* = 22.69 \text{ kNm}$$

$$\phi M_b = 45.1 \text{ kNm}$$

okay

$$I_{xx} = 14.10 \times 10^6 \text{ mm}^4$$

Serviceability Deflection

$$\text{(Under } W_s + P_s) \Delta = 9.7 \text{ mm}$$

$$= \text{Span} / 518$$

$$\text{(Under 1 kN Point Load)} \Delta = 0.9 \text{ mm}$$

Reaction

R1

Dead

7.24kN

Live

6.31kN

Ultimate

18.15kN

R2

7.24kN

6.31kN

18.15kN

Date	26/02/09	Eng.	M.Y	Job No.	23040	Sheet No.	11431
Project	125 Nikau Palm						
Beam 6 length = 3.3m Dead's Floor - Deck - 1.4m - Inside - 1.0m 2.4m See spreadsheet { Use 2/290 x 45 }							

AS/NZS 1170 TIMBER BEAM CALCULATION SHEET - MSG8

Job Name: 125 Nikau Palm


Job No. 23040

Sheet No.

Date: 26-Feb-09

Engineer M.Y

Beam No. Beam 6



L = 3.3 m

a = m

b = 3.3 m

LOADING

1/. Uniformly Distributed Load

		Amount	kN/m
Dead	Self Weight		0.13
	floor	2.4m x 0.3kPa	0.72
Total Dead Load		G =	0.85 kN/m

Live Roof ($\Psi_c = 0$ for Q_f)

	Floor	2.4m x 1.5kPa	3.60
Total Live Load		Q =	3.60 kN/m

$$W^* = 1.2 G + 1.5 Q = 6.42 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 2.29 \text{ kN/m}$$

2/. Point Load

		Amount	kN
Dead			
Total Dead Point Load		G =	0.00 kN
Live			
Total Live Point Load		Q =	0.00 kN

Le (m) 0.5

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = \frac{W^* L^2}{8} + \frac{P^* ab}{L}$$

$$M^* = 8.74 \text{ kNm}$$

Profile

Gauged

$$Z = 1263.0 \times 10^3 \text{ mm}^3$$

Section

290x90

(dry, $f_b = 14 \text{ Mpa}$)

$$D/B = 3$$

$$Le/B = 10$$

$$k_8 = 1.00$$

$$\phi M_b = 11.32 \text{ kNm}$$

Serviceability Deflection

(Under $W_s + P_s$)

$$(k_2=2) \Delta = 4.9 \text{ mm}$$

$$= \text{Span} / 676$$

$$EI_{xx} = 1449.91 \times 10^9 \text{ Nmm}^2$$

$$\text{Under 1 kN Point Load } \Delta = 0.5 \text{ mm}$$

okay

Reaction

R1

Dead

1.41kN

Live

5.94kN

Ultimate

10.60kN

R2

1.41kN

5.94kN

10.60kN

23040 Beam 6 timber

26/02/2009

Date

27/02/09

Eng.

M.Y

Job No.

23040

Sheet No.

33

Project

125 Nikau Palm



Beam 7

length 4.4m

loads

Glass wall (10mm thick) - $0.11 \text{ kN/m} \times 2.4 \text{ m} = 0.264 \text{ kN/m}$
 $\Rightarrow$ Use 0.3 kN/m

Floor $0.2 \text{ m} \times 0.3 \text{ kPa}$

Try Timber

2/290/45 - 1 kN/pt load deflection too much $\Rightarrow$ Try 150 PFC - 1 kN/pt load deflection too much $\Rightarrow$ 180 PFC OK

AS/NZS 1170 STEEL BEAM CALCULATION SHEET

Job Name: 125 Nikau Palm


Job No. 23040

Sheet No.

Date: 27-Feb-09

Engineer M.Y

Beam No. beam 7



L = 4.4 m

a = m

b = 4.4 m

LOADING

1/. Uniformly Distributed Load

		Amount kN/m
Dead	Self Weight	0.21
	Wall (Glass)	0.3kN/m
	floor	.2m x 0.3
		0.06
Total Dead Load		G = 0.57 kN/m

Live

Roof ($\Psi_c = 0$ for Q_f)		
Floor	0.2mx 1.5	0.30

Total Live Load Q = 0.30 kN/m

$$W^* = 1.2 G + 1.5 Q = 1.13 \text{ kN/m}$$

$$W_s = G + 0.4 Q_f = 0.69 \text{ kN/m}$$

2/. Point Load

Dead

		Amount kN
Total Dead Point Load		G = 0.00 kN

Live

		Amount kN
Total Live Point Load		Q = 0.00 kN

Le (m) 5

$$P^* = 1.2 G + 1.5 Q = 0.00 \text{ kN}$$

$$P_s = G + 0.4 Q_f = 0.00 \text{ kN}$$

Bending Moment

$$M^* = W^* L^2 / 8 + P^* ab / L$$

$$M^* = 2.74 \text{ kNm}$$

$$\phi M_b = 20.0 \text{ kNm}$$

okay

Profile

Channel Section

All Steel is Grade 300

Section

180PFC

$$I_{xx} = 14.10 \times 10^6 \text{ mm}^4$$

Serviceability Deflection

$$(\text{Under } W_s + P_s) \Delta = 1.2 \text{ mm}$$

$$= \text{Span} / 3690$$

$$(\text{Under 1 kN Point Load}) \Delta = 0.6 \text{ mm}$$

Reaction

R1

Dead

1.25kN

Live

0.66kN

Ultimate

2.49kN

R2

1.25kN


0.66kN

2.49kN

$\frac{1}{m}$

Project

125 Vikar street



Date

25/02/09

Eng.

M.Y

Job No.

23040

Sheet No.

36

Project

125 Nikou Street

Beam 9

length = 5.0m

trib width = 5.05m

See spreadsheet

 $\Rightarrow$ 180 PFCBeam 10

length = 3.6m

trib width = 5.05m

See spreadsheet

 $\Rightarrow$ 2/290x45 MSG8Beam 8

length = 4.75m

trib width = 1.25m

See spreadsheet

 $\Rightarrow$ 2/290x45 MSG8

AS/NZS1170 BEAM LOAD CALCULATION SHEET

Timber Roof Beam Calculation Sheet


Job Name: 125 Nihau Palm road

Job No. 23040

Date: 24-Feb-09

Engineer M.Y.

Beam No. Beam 8



L = 4.75 m
Trib Width = 1.25 m

LOADING

Uniformly Distributed Loads

	Amount
1. Dead	
Beam Self Weight	0.12 kN/m
Roof	0.38 kN/m
	0.3 kPa x Trib Width
Total Dead Load	G = 0.50 kN/m

$$Q_f = 1.8/A + 0.12 > 0.25 \text{ kPa} \quad \psi_a = 1.00$$

2. Roof Live Load	0.42 kPa x Trib Width x ψ_a	Q = 0.53 kN/m
-------------------	----------------------------------	---------------

3. Site Wind Speed

$$V_{(z)} = 42.33 \text{ m/s}$$

Upward Wind Loads

$$q_{(z)} = 0.5(\sigma_{air}) V_{(z)}^2 \times 10^{-3} = 1.08 \text{ kPa}$$

Downward Wind Loads

$$1.08 \text{ kPa}$$

External Pressures

$$p_e = C_{pe} K_a K_f K_p q_z$$

$$K_a = 1.00$$

$$K_f = 2.00$$

$$K_p = 1.00$$

$$C_{pe}(\text{min}) = -0.9$$

$$p_e(\text{min}) = -1.94 \text{ kPa}$$

$$C_{pe}(\text{max}) = 0.3$$

$$p_e(\text{max}) = 0.65 \text{ kPa}$$

Internal Pressures

$$p_i = C_{pi} q_z$$

$$C_{pi}(\text{max}) = 0.6$$

$$p_i(\text{max}) = 0.65 \text{ kPa}$$

$$C_{pi}(\text{min}) = -0.3$$

$$p_i(\text{min}) = -0.32 \text{ kPa}$$

Combined Pressures

$$\text{Note: } K_c > 0.8/K_a$$

$$p_z = (p_e - p_i) K_c$$

$$K_c = 0.95$$

$$p_z(\text{max}) = -2.45 \text{ kPa}$$

$$W_u(\text{max}) = -3.06 \text{ kN/m}$$

$$K_c = 0.80$$

$$p_z(\text{min}) = 0.77 \text{ kPa}$$

$$W_u(\text{min}) = 0.97 \text{ kN/m}$$

Load Combinations - Ultimate Limit State

$$W_{\text{medium}} = 1.39 \text{ kN/m}$$

$$W_{\text{short}} = 2.62 \text{ kN/m}$$

$$W^* = 2.62 \text{ kN/m}$$

$$\text{Note: Roof } Q_u = 0.00 \text{ kN/m}$$

Short term load critical

1.2 G + 1.5 Q =	1.39 kN/m
1.2 G + Q_u + W_u =	1.56 kN/m
0.9 G + W_u =	-2.62 kN/m
M* =	7.38 kNm

Beam Type MSG8/VSG8

Size

290x90

$f_b = 14$

Z = 1.26

$$\phi = 0.8$$

$$k_1 = 1.0$$

$$k_4 k_5 = 1$$

$$\phi M_b = \phi \cdot k_1 \cdot k_4 \cdot k_5 \cdot f_b \cdot Z = 14.55 \text{ kNm OKAY}$$

$$EI = 1449.91$$

$$k_2 = 2.0$$

Load Combinations - Serviceability Limit States

1kN Load	Long Term (G) Ws = 0.50 kN/m
Deflection = 1.5mm	4.5mm

$$\text{Span/ } 1046$$

$$\text{Span/ } 500$$

$$\text{Limit } 2.0\text{mm}$$

OKAY

OKAY

G + 0.7Q =	0.87
0.71x Wind ult =	2.18
Short Ws =	2.18 kN/m
	9.9mm

$$\text{Span/ } 478$$

$$\text{Span/ } 300$$

OKAY

Reactions	G	Q	Wind _{down}	Wind _{up}
	1.18 kN	1.26 kN	2.30 kN	-7.28 kN

Ult _{down}	Ult _{up}
3.71 kN	-6.22 kN

AS/NZS1170 BEAM LOAD CALCULATION SHEET


Steel Roof Beam Subjected To Wind Load

Job Name: 125 Nikau Palm Road

Job No. 23040

Date: 25-Feb-09

Engineer M.Y
Beam No. Beam 9



L = 5 m
Trib Width = 5.05 m

LOADING

Uniformly Distributed Loads

	Amount
1. Dead Beam Self Weight	0.21 kN/m
Roof	1.52 kN/m
	0.3 kPa x Trib Width
Total Dead Load	G = 1.72 kN/m

$$Q_f = 1.8/A + 0.12 > 0.25 \text{ kPa} \quad \psi_a = 0.90$$

2. Roof Live Load	0.25 kPa x Trib Width x ψ_a	Q = 1.13 kN/m
-------------------	----------------------------------	----------------------

3. Site Wind Speed

$V_{(z)} = 42.33 \text{ m/s}$

Upward Wind Loads

Downward Wind Loads

$$q_{(z)} = 0.5(\rho_{\text{air}}) V_{(z)}^2 \times 10^{-3} = 1.08 \text{ kPa}$$

1.08 kPa

External Pressures

$$p_e = C_{pe} K_a K_f K_p q_z$$

$$C_{pe}(\text{min}) = -0.9$$

$$C_{pe}(\text{max}) = 0.3$$

$$K_a = 0.90$$

$$K_f = 1.00$$

$$p_e(\text{min}) = -0.87 \text{ kPa}$$

$$p_e(\text{max}) = 0.29 \text{ kPa}$$

$$K_p = 1.00$$

Internal Pressures

$$C_{pi}(\text{max}) = 0.6$$

$$C_{pi}(\text{min}) = -0.3$$

$$p_i = C_{pi} q_z$$

$$p_i(\text{max}) = 0.65 \text{ kPa}$$

$$p_i(\text{min}) = -0.32 \text{ kPa}$$

Combined Pressures

Note: $K_c > 0.8/K_a$

$$K_c = 0.95$$

$$K_c = 0.89$$

$$p_z = (p_e - p_i) K_c$$

$$p_z(\text{max}) = -1.44 \text{ kPa}$$

$$p_z(\text{min}) = 0.54 \text{ kPa}$$

$$W_u(\text{max}) = -7.27 \text{ kN/m}$$

$$W_u(\text{min}) = 2.75 \text{ kN/m}$$

Load Combinations - Ultimate Limit States

$$\text{Note: Roof } Q_u = 0.00 \text{ kN/m}$$

$1.2 G + 1.5 Q =$	3.77 kN/m
$1.2 G + Q_u + W_u =$	4.82 kN/m
$0.9 G + W_u =$	-5.72 kN/m
M* =	17.88 kN/m

$$W^* = 5.72 \text{ kN/m}$$

Profile Channel Section

Section 180PFC

$L_{e(m)} = 1$

$$\phi M_b = 45.1 \text{ OKAY}$$

$$I_{xx} = 14.10 \times 10^9 \text{ mm}^4$$

Load Combinations - Serviceability Limit States

1kN Load	Long Term (G) Ws = 1.72 kN/m
Deflection = 0.9mm	5.0mm
Limit 2.0mm	Span/ 1005
OKAY	Span/ 500
OKAY	OKAY

G + 0.7Q =	2.52 kN/m
0.71x Wind ult =	5.16 kN/m
Short Ws =	5.16 kN/m
	14.9mm
Span/ 336	
Span/ 300	
OKAY	OKAY

Reactions	G	Q	Wind _{down}	Wind _{up}	Ult _{down}	Ult _{up}
	4.31 kN	2.83 kN	6.88 kN	-18.18 kN	12.05 kN	-14.30 kN

AS/NZS1170 BEAM LOAD CALCULATION SHEET

Timber Roof Beam Calculation Sheet


Job Name: 125 Nihau Palm road

Job No. 23040

Date: 24-Feb-09

Engineer M.Y.

Beam No. Beam 10



L = 3.6 m

Trib Width = 5.053 m

LOADING

Uniformly Distributed Loads

	Amount
1. Dead	
Beam Self Weight	0.12 kN/m
Roof	0.3 kPa x Trib Width
	1.52 kN/m
	kN/m
Total Dead Load	G = 1.64 kN/m

$$Q_f = 1.8/A + 0.12 > 0.25 \text{ kPa} \quad \psi_a = 1.00$$

2. Roof Live Load	0.25 kPa x Trib Width x ψ_a	Q = 1.26 kN/m
-------------------	----------------------------------	----------------------

3. Site Wind Speed

$V_{(z)} = 42.33$ m/s

Upward Wind Loads

Downward Wind Loads

$$q_{(z)} = 0.5(\rho_{air})V_{(z)}^2 \times 10^{-3} = 1.08 \text{ kPa}$$

1.08 kPa

External Pressures

$$p_e = C_{pe} K_a K_f K_p q_z$$

$$C_{pe}(\text{min}) = -0.9$$

$$C_{pe}(\text{max}) = 0.3$$

$$K_a = 1.00$$

$$K_f = 1.00$$

$$p_e(\text{min}) = -0.97 \text{ kPa}$$

$$p_e(\text{max}) = 0.32 \text{ kPa}$$

$$K_p = 1.00$$

Internal Pressures

$$p_i = C_{pi} q_z$$

$$C_{pi}(\text{max}) = 0.6$$

$$C_{pi}(\text{min}) = -0.3$$

$$p_i(\text{max}) = 0.65 \text{ kPa}$$

$$p_i(\text{min}) = -0.32 \text{ kPa}$$

Combined Pressures

Note: $K_c > 0.8/K_a$

$$K_c = 0.95$$

$$K_c = 0.80$$

$$p_z = (p_e - p_i) K_c$$

$$p_z(\text{max}) = -1.53 \text{ kPa}$$

$$p_z(\text{min}) = 0.52 \text{ kPa}$$

$$W_u(\text{max}) = -7.74 \text{ kN/m}$$

$$W_u(\text{min}) = 2.61 \text{ kN/m}$$

Load Combinations - Ultimate Limit State

$$W_{\text{medium}} = 3.86 \text{ kN/m}$$

$$\text{Note: Roof } Q_u = 0.00 \text{ kN/m}$$

$$W_{\text{short}} = 6.27 \text{ kN/m}$$

$$W^* = 6.27 \text{ kN/m}$$

Short term load critical

$$1.2 G + 1.5 Q = 3.86 \text{ kN/m}$$

$$1.2 G + Q_u + W_u = 4.57 \text{ kN/m}$$

$$0.9 G + W_u = -6.27 \text{ kN/m}$$

$$M^* = 10.15 \text{ kNm}$$

Beam Type MSG8/VSG8

Size

290x90

$f_b = 14$

$Z = 1.26$

$$\phi = 0.8$$

$$k_1 = 1.0$$

$$k_4, k_5 = 1$$

$$\phi M_b = \phi \cdot k_1 \cdot k_4 \cdot k_5 \cdot f_b \cdot Z = 14.55 \text{ kNm}$$

OKAY

$$k_2 = 2.0$$

$$EI = 1449.91$$

Load Combinations - Serviceability Limit States

1kN Load

Long Term (G) $W_s = 1.64 \text{ kN/m}$

$$G + 0.7 Q = 2.52$$

Deflection = 0.7mm

4.9mm

$$0.71 \times \text{Wind ult} = 5.50$$

Short $W_s = 5.50 \text{ kN/m}$

8.3mm

Limit 2.0mm

Span/ 729

Span/ 434

Span/ 500

Span/ 300

OKAY

OKAY

OKAY

Reactions

G

Q

Wind_{down}

Wind_{up}

Ult_{down}

Ult_{up}

2.95 kN

2.27 kN

4.69 kN

-13.93 kN

8.23 kN

-11.28 kN

AS/NZS1170 BEAM LOAD CALCULATION SHEET

Timber Roof Beam Calculation Sheet


Job Name: 125 Nikau Palm

Job No. 23040

Date: 25-Feb-09

Engineer M.Y.

Beam No. Beam 11



L = 5 m
Trib Width = 1.9 m

LOADING

3. Site Wind Speed

 $V_{(z)} = 42.33$ m/s

Inward Wind Loads

Outward Wind Loads

$$q_{(z)} = 0.5(\rho_{\text{air}})V_{(z)}^2 \times 10^{-3} = 1.08 \text{ kPa}$$

1.08 kPa

External Pressures

$$p_e = C_{pe} K_a K_f K_p q_z$$

$$K_a = 1.00$$

$$K_f = 1.00$$

$$K_p = 1.00$$

$$C_{pe}(\text{min}) = 0.70$$

$$p_e(\text{min}) = 0.75 \text{ kPa}$$

$$C_{pe}(\text{max}) = -0.5$$

$$p_e(\text{max}) = -0.54 \text{ kPa}$$

Internal Pressures

$$p_i = C_{pi} q_z$$

$$C_{pi}(\text{max}) = -0.30$$

$$p_i(\text{max}) = -0.32 \text{ kPa}$$

$$C_{pi}(\text{min}) = 0.3$$

$$p_i(\text{min}) = 0.32 \text{ kPa}$$

Combined Pressures

$$p_z = (p_e - p_i) K_c$$

$$K_c = 1.0$$

$$p_z(\text{max}) = 1.08 \text{ kPa}$$

$$W_{u(\text{in})} = 2.04 \text{ kN/m}$$

$$K_c = 1.0$$

$$p_z(\text{min}) = -0.86 \text{ kPa}$$

$$W_{u(\text{out})} = -1.63 \text{ kN/m}$$

Load Combinations - Ultimate Limit State

$$W^* = 2.04 \text{ kN/m}$$

$$M^* = 6.38 \text{ kNm}$$

Beam Type MSG8/VSG8

Size

290x45

$$f_b = 14$$

$$Z = 0.63$$

$$\phi = 0.8 \quad k_1, k_4, k_5 = 1$$

$$\phi M_b = \phi \cdot k_1 \cdot k_4 \cdot k_5 \cdot f_b \cdot Z = 7.27 \text{ kNm} \text{ OKAY}$$

$$EI = 724.96$$

Load Combinations - Serviceability Limit States

1.5 x 0.6kN Load

$$\text{Deflection} = 3.2 \text{ mm}$$

$$\text{Span/ } 1547$$

$$\text{Span/ } 500$$

OKAY

$$\text{Short } W_s = 0.71 \times \text{Wind Ult} = 1.45 \text{ kN/m}$$

$$16.3 \text{ mm}$$

$$\text{Span/ } 307$$

$$\text{Span/ } 300$$

OKAY

Reactions

$$5.11 \text{ kN}$$

Wind Loads from wall face on beams 8 & 9

41

AS/NZS1170 BEAM LOAD CALCULATION SHEET

Timber Roof Beam Calculation Sheet


Job Name: 125 Nikau Palm

Job No. 23040

Date: 25-Feb-09

Engineer M.Y.

Beam No. Beam 11



L = 5 m
Trib Width = 0.75 m

LOADING

3. Site Wind Speed

$V_{(z)} = 42.33$ m/s

Inward Wind Loads

$$q_{(z)} = 0.5(\sigma_{air})V_{(z)}^2 \times 10^{-3} = 1.08 \text{ kPa}$$

Outward Wind Loads

1.08 kPa

External Pressures

$$p_e = C_{pe}K_aK_fK_pq_z$$

$K_a = 1.00$
 $K_f = 1.00$
 $K_p = 1.00$

$$C_{pe}(\min) = 0.70$$
$$p_e(\min) = 0.75 \text{ kPa}$$

$$C_{pe}(\max) = -0.5$$
$$p_e(\max) = -0.54 \text{ kPa}$$

Internal Pressures

$$p_i = C_{pi}q_z$$

$$C_{pi}(\max) = -0.30$$
$$p_i(\max) = -0.32 \text{ kPa}$$

$$C_{pi}(\min) = 0.3$$
$$p_i(\min) = 0.32 \text{ kPa}$$

Combined Pressures

$$p_z = (p_e - p_i)K_c$$

$$K_c = 1.0$$
$$p_z(\max) = 1.08 \text{ kPa}$$
$$W_{u(in)} = 0.81 \text{ kN/m}$$

$$K_c = 1.0$$
$$p_z(\min) = -0.86 \text{ kPa}$$
$$W_{u(out)} = -0.65 \text{ kN/m}$$

Look at
wind loads
for model
in space loan

Load Combinations - Ultimate Limit State

$W^* = 0.81 \text{ kN/m}$

$M^* = 2.52 \text{ kNm}$

Beam Type MSG8/VSG8 Size 290x45

$f_b = 14$ $Z = 0.63$

$$\phi = 0.8 \quad k_1, k_4, k_5 = 1$$

$$\phi M_b = \phi \cdot k_1 \cdot k_4 \cdot k_5 \cdot f_b \cdot Z = 7.27 \text{ kNm OKAY}$$
$$EI = 724.96$$

Load Combinations - Serviceability Limit States

1.5 x 0.6kN Load

Deflection = 3.2mm

Span/ 1547

Span/ 500

OKAY


0.71x Wind Ult
Short Ws = 0.57 kN/m
6.4mm

Span/ 778


Span/ 300

OKAY


Reactions 2.02 kN



Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1
 Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa
 Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None




Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1
 Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa
 Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None



Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m^3, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None



Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1


Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m^3, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

■ 4

Wind (Southeast)



Wind, south east and downward
No general restraint

Materials:
■ 1 STEEL
■ 2 MSG8

Sections:

■ 1 125*6 SHS
■ 2 125*6 SHS
■ 3 180 PFC
■ 4 290 x90

Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1


Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

■ 6

Wind up and South east winds



Wind, South east and upward
No general restraint

Materials:
■ 1 STEEL
■ 2 MSG8

Sections:

■ 1 125*6 SHS
■ 2 125*6 SHS
■ 3 180 PFC
■ 4 290 x90


Job: I:\JOBFILES\ISP\23000\23040\23040 Column 1

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:73, Load: 0.134218, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

15 wind service (ne)




Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:59, Load: None, Disp: 27.20082, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

18 Wind 2 service (SE)



Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2


Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:59, Load: None, Disp: 66.40825, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

■ 10

1.2G+1.5Q



Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2


Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:59, Load: None, Disp: None, Moment: None, Shear: None, Axial: None, Torsion: None

Load cases:

12

G + Wdown2(southeast)



Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:59, Load: None, Disp: None, Moment: 0.165682, Shear: None, Axial: None, Torsion: None

Summary of demands


	Demand	Member capacity	
Beam 11	5.06 kNm	37.8 kNm (Le=5)	OK
Beam 12	6.15 kNm	37.8 kNm	OK
Column 5	2.12 kNm	kNm (Le=5)	OK
" 6	2.76 kNm	"	OK
" 7	3.49 kNm	"	OK

SPACE GASS 10.60 - ISP CONSULTING ENGINEERS LTD

12 Mar 2009, 11:28 am

Load cases:

10 1.2G+1.5Q

gravity moments
No general restraintMaterials:
1 STEEL
2 MSG8Sections:
1 125*6 SHS
2 125*6 SHS

Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa


Scales - Frame: 1:59, Load: None, Disp: None, Moment: 0.054291, Shear: None, Axial: None, Torsion: None

SPACE GASS 10.60 - ISP CONSULTING ENGINEERS LTD

12 Mar 2009, 11:29 am

Load cases:

11 G+ Wdown(northeast)

northeast moments
No general restraintMaterials:
1 STEEL
2 MSG8Sections:
1 125*6 SHS
2 125*6 SHS

Job: I:\JOBFILES\ISP\23000\23040\23040 top storey beam column modelv2

Units - Len: m, Sec: mm, Mat: MPa, Dens: T/m³, Temp: Celsius, Force: kN, Mom: kNm, Mass: T, Acc: g's, Trans: mm, Stress: MPa

Scales - Frame: 1:59, Load: None, Disp: None, Moment: 0.258877, Shear: None, Axial: None, Torsion: None

Date

6/03/09

Eng.

M.Y

Job No.

23040

Sheet No.

49

Project

125 N.kau Palm



Column 3

Loads

G: pt load: 1.18 kN

UDL: Wall + internal flooring + decking

Q: pt load: 1.26 kN

UDL: Wall, internal & Decking loadings

From Column 5 (125x9 SHS above) only

Ult down = 3.71

Ult up = -6.22

Note: does not include floor loads or wall loads

Design to NZS 3604

Column 4

Reactions from beam 8 & 9, through Column 6 to Column 4

G:

pt load: 5.5 kN

Does not include floor or wall loads

Q pt load: 4.09 kN

From beam 8 & 9

Ult down = 15.76 kN

Ult up = -20.0 kN

Design to NZS 3604

Timber Axial Capacity

Job Name 125 Nikau Palm
 Job Number 23040
 Location
 Date 6/03/2009
 Engineer *columns 1 & 2*

Lx 2.7 m dx = 90 mm S2 = 30

Ly 0.8 m dy = 90 mm S3 = 9

Φ 0.8
 k1 0.8
 k4 1
 k8 0.351
 ft 3 MPa
 fc 10 MPa
 A 8100 mm²

Load Duration

Medium ▼

Type of Timber

MSG6 wet ▼

Euler Buckling

E 4.8 GPa

Ixx 5.47E+06 mm⁴

Iyy 5.47E+06 mm⁴

N_{exx} = 35.5 kN

N_{eyy} = 404.6 kN

k8 Calculation

Seff 30

k8 wet 0.381

k8 dry 0.420

S = 10-25 0.381

k8 wet 0.351

k8 dry 0.324

S > 25 0.351

Compression Load

N* = 12.8 kN

Φ Nc = 18.2 kN

Φ Ne = 35.5 kN

OKAY

Tension Load

N* = 6 kN

Φ Nt = 15.6 kN

OKAY

Rowbustness Check

Nr* = 12.8 Mr* = 0.38

Φ Nr = 22.7 Φ Mr = 0.73

Consider

Capacity = 108 %

Check is a 0.6kN load at 1m from end of the member in combination with long term-axial load

Not an issue as there is a large box cladding around this member

